

CONTRACT CHANGE ORDER NUMBER	2	SUPPL. NO.	
------------------------------	---	------------	--

DATE PREPARED BY RESIDENT ENGINEER: 12/17/18

PROJECT NAME: DINNER CREEK CULVERT REPLACEMENT ON BRICELAND-THORNE ROAD (F5A010) AT P.M. 3.27 & 3.74

PROJECT NO. P1610515 CONTRACT NO. 211304

TO: GR WILCOX ENTERPRISES, INC.

YOU ARE HEREBY DIRECTED TO MAKE THE HEREIN DESCRIBED CHANGES FROM THE PLANS AND SPECIFICATIONS OR TO DO THE FOLLOWING DESCRIBED WORK NOT INCLUDED IN THE PLANS AND SPECIFICATIONS FOR THIS CONTRACT. NOTE THIS CHANGE ORDER IS NOT EFFECTIVE UNTIL APPROVED BY THE DIRECTOR OF PUBLIC WORKS

DESCRIPTION OF WORK TO BE DONE, ESTIMATE OF QUANTITIES, AND PRICES PAID. (SEGREGATE BETWEEN ADDITIONAL WORK AT CONTRACT PRICE, AGREED PRICE AND FORCE ACCOUNT.) UNLESS OTHERWISE STATED, RATES FOR RENTAL OF EQUIPMENT COVER ONLY. SUCH TIME AS EQUIPMENT IS ACTUALLY USED AND NO ALLOWANCE WILL BE MADE FOR IDLE TIME. THE LAST PERCENTAGE SHOWN IS THE NET ACCUMULATED INCREASE OR DECREASE FROM THE ORIGINAL QUANTITY IN THE ENGINEER'S ESTIMATE.

**INCREASE IN CONTRACT ITEMS AT CONTRACT PRICES**

ITEM NO. 5	TEMPORARY RAILING (TYPE K)				
	5 EA	125.00%	@	\$ 660.00 / EA	\$ 3,300.00
ITEM NO. 8	TEMPORARY FIBER ROLL (TYPE 1)				
	150 LF	25.00%	@	\$ 4.08 / LF	\$ 612.00
ITEM NO. 16	CHANNEL EXCAVATION (DINNER CREEK)				
	70 CY	26.92%	@	\$ 52.00 / CY	\$ 3,640.00
ITEM NO. 17	STRUCTURE EXCAVATION (CULVERT)				
	1,557 CY	57.88%	@	\$ 14.79 / CY	\$ 23,028.03
ITEM NO. 19	IMPORTED RIVER GRAVEL				
	84.60 CY	32.54%	@	\$ 114.50 / CY	\$ 9,686.70
ITEM NO. 20	EMBANKMENT				
	252 CY	24.47%	@	\$ 23.60 / CY	\$ 5,947.20
ITEM NO. 23	HOT MIX ASPHALT (TYPE A, 1/2" MIX)				
	33 TN	33.00%	@	\$ 163.80 / TN	\$ 5,405.40
ITEM NO. 24	CLASS A CONCRETE (ARCH CULVERT)				
	30 CY	44.12%	@	\$ 406.00 / CY	\$ 12,180.00
ITEM NO. 25	BAR REINFORCING STEEL				
	627 LB	10.00%	@	\$ 4.06 / LB	\$ 2,545.62
ITEM NO. 27	18'x9' STRUCTURAL STEEL ARCH CULVERT (0.168", 8g)				
	10 LF	10.00%	@	\$ 892.87 / LF	\$ 8,928.70
ITEM NO. 28	CLEAN RIVER RUN ROCK (6" TO 8" COBBLE)				
	21 CY	102.50%	@	\$ 250.00 / CY	\$ 5,125.00
ITEM NO. 29	ROCK SLOPE PROTECTION (1/2 TO 1 TN, METHOD A)				
	16 TN	10.67%	@	\$ 122.00 / TN	\$ 1,952.00
<b>TOTAL INCREASE =</b>					<b>\$ 82,350.65</b>

No adjustment to contract unit prices for the above items will be made in accordance with Section 9-1.06B, "Increases of More Than 25 Percent," of the Standard Specifications by reason of this change order.

**DECREASE IN CONTRACT ITEMS AT CONTRACT PRICES**

ITEM NO. 9	TEMPORARY SILT FENCE				
	-360 LF	-90.00%	@	\$ 14.00 / LF	\$ (5,040.00)
ITEM NO. 22	CLASS 2 AGGREGATE BASE				
	-15 CY	-11.54%	@	\$ 149.50 / CY	\$ (2,242.50)
<b>TOTAL DECREASE =</b>					<b>\$ (7,282.50)</b>

No adjustment to contract unit prices for the above items will be made in accordance with Section 9-1.06C, "Decreases of More Than 25 Percent," of the Standard Specifications by reason of this change order.

The Contractor shall be granted three (3) working days for additional channel excavation required by NMFS Hydrologist/Hydraulic Engineer.

**ESTIMATED TOTAL INCREASE = \$ 75,068.15**

BY REASON OF THIS CHANGE, THE CONTRACT TIME WILL BE INCREASED BY 3 WORKING DAYS

**SUBMITTED BY:**


SIGNATURE	PRINT NAME AND TITLE	DATE
	ANGI SORENSEN, CONSTRUCTION ENGINEER	

**DIRECTOR APPROVAL BY:**

SIGNATURE	PRINT NAME AND TITLE	DATE
	TOM MATTSON, DIRECTOR OF PUBLIC WORKS	

WE, THE UNDERSIGNED CONTRACTOR, HAVE GIVEN CAREFUL CONSIDERATION TO THIS CHANGE PROPOSED AND AGREE, IF THIS PROPOSAL IS APPROVED, THAT WE WILL PROVIDE ALL EQUIPMENT, FURNISH ALL MATERIALS, EXCEPT AS MAY OTHERWISE BE NOTED ABOVE, AND PERFORM ALL SERVICES NECESSARY FOR THE WORK ABOVE SPECIFIED, AND WILL ACCEPT AS FULL PAYMENT, THEREFORE, THE PRICES SHOWN ABOVE. NOTE: IF YOU, THE CONTRACTOR, DO NOT SIGN ACCEPTANCE OF THIS ORDER, YOUR ATTENTION IS DIRECTED TO THE REQUIREMENTS OF THE SPECIFICATION AS TO PROCEEDING WITH THE ORDERED WORK AND FILING A WRITTEN PROTEST WITHIN THE TIME THEREIN SPECIFIED.

**CONTRACTOR ACCEPTANCE BY:**

SIGNATURE	PRINT NAME AND TITLE	DATE
	GARY WILCOX SEC	12-20-18