

Humboldt Spirit Inc. PLN-12244-CUP

April 6, 2022

Site Management Plan Addendum


Location: 161 Oak Rock Rd. Garberville, CA 95542

APN: 222071030


This document serves as an addendum to the previously submitted Site Management plan written by Timberland Resource Consultants, for the purpose of clarifying the sizing and condition of the existing rainwater catchment pond located on parcel 221-071-030, as well as estimated water usage.

This existing off-stream rainwater catchment pond was incorrectly estimated with regards to the existing size of the pond. This pond is 140.53 feet long and 115.01 feet wide by 12 feet deep and has not been altered in size. This pond was recently lined and is shown to have an existing capacity of 930,626-gallons. The pond will not be deepened or widened, as its existing capacity is more than enough to supply irrigation water for the entire project. (see measurement photos below)



Estimated irrigation water usage for this project is 264,825-gallons annually. (8.8-gal./ft²) and is supplied by the existing rainwater catchment pond. Domestic water usage for this parcel is estimated to be 75,000-gallons annually and is sourced from the domestic spring.



Pond Length



Pond Width



Circular Pond

Calculate

CALCULATED POOL
VOLUME

930626

GALLONS

New Pond liner sizing and capacity

Site Management Plan

(Tier 1, Low-Risk)

WDID - 1_12CC407540

Humboldt County
APN: 222-071-030-000

Prepared by:



165 South Fortuna Boulevard, Fortuna, CA 95540
707-725-1897 • fax 707-725-0972
trc@timberlandresource.com

9/10/2021

Arrangement of Document Contents

- **Purpose**
- **Tier Designation**
- **Scope of Report**
- **Methods**
- **Property Description**
- **General Location Map**
- **Project Description**
- **Additional Project Permitting**
- **General Compliance Guide for Cannabis Cultivators**
 - Land Development and Maintenance, Erosion Control, and Drainage Features
 - Cleanup, Restoration, and Mitigation
 - Stream Crossing Installation and Maintenance
 - Soil Disposal and Spoils Management
 - Riparian and Wetland Protection and Management
 - Water Storage and Use
 - Fertilizers, Pesticides, and Petroleum Products
 - Cultivation Related Waste
 - Refuse and Domestic Waste
 - Annual Winterization Measures
- **Site Management Plan General Guidance Outline**
- **Statement of Limitations**
- **Monitoring Plan**
- **Implementation Schedule**
- **Site Maps**
- **Mitigation Report**
- **Attachments**
 - Photographs
 - Applicable BPTC's (BMP's)

Purpose

This Site Management Plan (SMP) has been prepared on behalf of the cannabis cultivator for the Humboldt County property identified as Assessor Parcel Numbers 222-071-030, by agreement and in response to the State Water Resources Control Board Cannabis Cultivation Policy (Cannabis Policy), in congruence with Order WQ 2019-0001-DWQ General Waste Discharge Requirements for Discharges of Waste Associated with Cannabis Cultivation Activities (General Order). The General Order implements the Cannabis Policy requirements, specifically those requirements that address waste discharges associated with cannabis cultivation activities. Cannabis cultivators covered under the General Order are subject to the requirements of the Cannabis Policy in its entirety. The Cannabis Policy provides a statewide tiered approach for permitting discharges and threatened discharges of waste from cannabis cultivation and associated activities, establishes a personal use exemption standard, and provides conditional exemption criteria for activities with a low threat to water quality.

Tier Designation

Tiers are defined by the amount of disturbed area. Tier 1 outdoor commercial cultivation activities disturb an area equal to or greater than 2,000 square feet and less than 1 acre (43,560 square feet). Tier 2 outdoor commercial cultivation activities disturb an area equal to or greater than 1 acre. Risk designation for Tier 1 and Tier 2 enrollees under the Cannabis Policy is based on the slope of disturbed areas and the proximity to a surface water body. Characterization is based on the risk designation summarized in Table 1 below.

Table 1: Summary of Risk Designation

Low Risk	Moderate Risk	High Risk
<ul style="list-style-type: none"> • No portion of the disturbed area is located on a slope greater than 30 percent, and • All of the disturbed area complies with the setback requirements. 	<ul style="list-style-type: none"> • Any portion of the disturbed area is located on a slope greater than 30 percent, and • All of the disturbed area complies with the setback requirements. 	<ul style="list-style-type: none"> • Any portion of the disturbed area is located within the setback requirements.

A thorough assessment of the project area including roads, disturbed areas, legacy features, and cultivation areas classify this enrollment into the **Tier 1, Low-Risk** designation.

Scope of Report

Tier 1 and Tier 2 cannabis cultivators are required to submit and implement a Site Management Plan that describes how they are complying with the requirements listed in Attachment A. The description shall describe how all applicable Best Practicable Treatment or Control (BPTC) measures are implemented. Cannabis cultivators within the North Coast Regional Water Quality Control Board jurisdiction are required to submit and implement Site Management Plans that describe how the Requirements are implemented property-wide, to include legacy activities. The SMP includes an Implementation Schedule to achieve compliance, but all work must be completed by the onset of the Winter Period each year. Projects designated as Moderate Risk are also required to have a Site Erosion and Sediment Control (plan) to achieve the goal of minimizing the discharge of sediment off-site. Projects designated as High Risk are also required to have a Disturbed Area Stabilization Plan to achieve the goal of stabilizing the disturbed area to minimize the discharge of sediment off-site and comply with the setback requirements. The cannabis cultivator shall ensure that all site operating personnel are familiar with the contents of the General Order and all technical reports prepared for the property. Projects which have over one acre of cannabis cultivation (total canopy area) are also required to have a Nitrogen Management Plan to describe how nitrogen is stored, used, and applied to crops in a way that is protective of water quality. A copy of the General Order, and technical reports required by the General Order, shall be kept at the cultivation site. Electronic copies of these documents are acceptable. Either format of maintained documents kept on site must be immediately presentable upon request.

Methods

The methods used to develop this SMP include both field and office components. The office component consisted of aerial photography review and interpretation, existing USGS quad map review, GIS mapping of field data, review of on-site photography points, streamflow calculations, general planning, and information gathered from the cannabis cultivator and/or landowner. The field component included mapping of all access roads, vehicle parking areas, Waters of the State, stream crossings, drainage features, cultivation sites, buildings, disturbed areas, and all other relevant site features within the project area and surrounding areas (as feasible). Cultivation areas, associated facilities, roads, and other developed and/or disturbed areas were assessed for discharges and related controllable water quality factors from the activities listed in the General Order. The field assessment also included an evaluation and determination of compliance with all applicable BPTC's per Section 2 of the General Order.

Property Description

The property assessed consists of one parcel totaling 104 acres located approximately 6 miles southwest of Garberville, California, at an elevation of approximately 1,400 feet above mean sea level. The property is located in Section 16, T5E, R3S, HB&M, Humboldt County, from the Garberville USGS 7.5' Quadrangle. Sproul Creek and Class II and III watercourses flow north-south through the property that drain to the South Fork Eel River.

Site Management Plan


General Location Map [WDID - 1_12CC407540]



 Property Boundary

Located in Section 16, T5E, R3S, HB&M, Humboldt County, from the Garberville 7.5' USGS Quad Map

TRC - 525



Project Description

Currently, no cannabis cultivation on the property exists. The proposed cultivation, if approved by Humboldt County, will consist of hoop-house style greenhouses with a general total cultivation area¹ of 30,000 ft². The cultivation areas to be developed will be located within an estimated 40,000 ft² of disturbed area, which are located in two separate areas on the property and one of which is located at the top of a ridge. The exact amounts of the General Cultivation Area and Land Disturbance Area are to be determined. This project is being permitted by Humboldt County to cultivate cannabis. This project was previously enrolled in the North Coast Regional Water Quality Control Board Order No. R1-2015-0023 under WDID-1B15169CNHU and has since enrolled with State Water Recourses Control Board as WDID-1_12CC407540. This project is being classified as Tier 1, Low-Risk.

Table 1: Cultivation Site Parameters.

Proposed Cultivation Area	Land Disturbance Area (ft ²)	General Cultivation Area ¹ (ft ²)	Adjoining Hillslopes (% Grade)
A	TBD	TBD	20 – 25%
B	TBD	TBD	10 – 15%
Totals:			

¹ Area refers to the total land disturbance area. The total cannabis canopy area may vary considerably from the disturbance area.

Table 2: Project Permitting

Additional Required Permits Related to Project, Type, and Status	
SIUR	Required (if diverted waters are stored and used for irrigation)
LSAA/1600	Required, To be submitted
401 WQC/404 permit	Required, To be submitted

General Compliance Guide for Cannabis Cultivators

Baseline Assessment of Requirements Related to Water Diversions and Waste Discharge for Cannabis Cultivation

This project was previously enrolled in the North Coast Regional Water Quality Control Board Order No. 2015-0023. No Water Resource Protection Plan (WRPP) was prepared by the previous Cultivator/landowner, Justin Baldwin. A Cleanup and Restoration Plan (CRP) was prepared by Natural Resource Management Corporation (NRM) for the landowner, however, this plan was never updated to address comments by the NCRWQCB and wasn't fully implemented. A re-assessment of the project was conducted and will be used as the baseline assessment for the preparation of this document. Sites listed in the attached Mitigation Report and Site Maps also reference corresponding WQ Sites in the 2015 Inspection Report, the 2020 Inspection Report, and the Projects in the 2018 CRP by NRM. Those documents are attached for reference.

Land Development and Maintenance, Erosion Control, and Drainage Features

Project Compliance Y/N

Roads are being classified as “permanent” (roads appurtenant to the project being used year-round), “seasonal” (roads appurtenant to the project being used primarily during summer months), “legacy” (roads not appurtenant to the project receiving little to no use), and “trail” (being used for occasional access to features on the property).

The majority of roads within the project area are shared and used by the Sproul Creek community. These roads consist of the Oak Rock Road (east to west road along the northern property boundary and Pepperwood Springs Road (north to south road bisecting the property). Official or unofficial road owners associations are responsible to maintain the basic functions of these roads.

Roads within the project area appear to have a moderate native rock component and high imported rock component and, based on observations of surface erosion relative to current surface drainage break frequency, are being classified as having low erodibility. This classification will be utilized to determine surface/ditch-line drainage break frequency based on Table 19 of the Handbook for Forest Ranch and Rural Roads, 2014.

TABLE 19. Recommended maximum rolling dip and ditch relief culvert spacing, in feet, based on road gradient and soil erodibility ^{1,2}

Soil erodibility	Road gradient (%) and drainage structure spacing (feet)				
	0-3	4-6	7-9	10-12	>12
High to moderate	250	160	130	115	100
Low	400	300	250	200	160

Currently, all permanent roads on the property have imported rock surfacing. Only one section of permanent road (Site 01 to 08) requires more rock surfacing.

Roads assessed by TRC were found to be in acceptable condition with imported rock surfacing. However, sections of permanent roads, seasonal roads, legacy roads, and trails require either the maintenance of existing drainage features or the installation of new drainage features. No wheel ruts were observed on the majority of access roads on the date of the site visit.

Controllable Sediment Delivery Sites (CSDS) were found on the property. Runoff and sediment was found discharging into surface waters at Sites 01, 03, 04, 05, 06, 07, 08, 11, 14, 19, 23, 24, 26, 27, and 29. See the attached photographs, Mitigation Report, Treatment Implementation Schedule, and Site Map to follow for site-specific details and treatments.

Overall erosion of road surfaces is minor and occurring due to road surface runoff being constrained to the tread path and/or lack of adequate drainage features and structures on the permanent, shared, road network.

No erosion is occurring at any of the Past Cultivation Areas.

No unstable areas were identified during the assessment of the property.

Cleanup, Restoration, and Mitigation:

Project Compliance Y/N

Cleanup of Past Cultivation Areas has occurred multiple times starting in 2016 as a result of the NCRWQCB's Inspection Report and the Cleanup and Restoration Plan prepared by NRM. Further cleanup of remnant cultivation-related wastes at Past Cultivation Areas has also occurred recently during the summer of 2021. Further removal of Past Cultivation Areas will be required by the cultivator at the Past Cultivation Areas adjacent to Cultivation Area A. Other remaining materials located around the property that are no longer used, associated with past cultivation, will also need to be removed and cleaned up.

No revegetation/besides seeding and mulching disturbed areas or sediment catchment sites are/ is being prescribed and implemented in this Site Management Plan. Further revegetation activities may be prescribed in the 401 Water Quality Certification. Any revegetation activities set forth under additional reports shall be followed.

Stream Crossing Installation and Maintenance:

Project Compliance Y/N

Fourteen watercourse crossings were identified during the assessment of the property. Two crossings (Sites 17 & 19) shall be decommissioned as the existing culverts are undersized for a 100-year storm event and are not used or required by the landowner. Ten watercourse crossings (Sites 03, 04, 05, 06, 07, 08, 23, 24, 26 & 35) shall be upgraded as the existing culverts are undersized for a 100-year storm event and require replacement. One crossing area (Sites 13 & 14) is multi-site areas where a watercourse is being diverted down the inside ditch, resulting in erosion of the inside ditch, and sediment discharge to surface waters. See attached photographs, Mitigation

Report, Treatment Implementation Schedule, and Site Map to follow for site-specific details and treatments.

A Lake and Streambed Alteration Agreement (LSAA/1600) with the California Department of Fish & Wildlife (CDFW) will be submitted for the proposed work on watercourse crossings.

Site ID_NUMBER	(ac) D_AREA	K_VALUE	Elevation (ft) Culvert_Elevation	Elevation (ft) Drainage_Divide	(mi) LENGTH	(in) CMP_DIA
Site 03	1.07	0.35	1515	1630	0.0962	12
Site 04	1.05	0.35	1500	1620	0.09	12
Site 05	2.18	0.35	1495	1660	0.1263	15
Site 06	4.29	0.35	1500	1770	0.212	12
Site 07	6.13	0.35	1505	1775	0.21	12
Site 08	1.79	0.35	1510	1710	0.1422	12
Site 11	2.6	0.35	1485	1650	0.111	24
Site 13	2.03	0.35	1470	1650	0.1314	
Site 35	1.6	0.35	1515	1650	0.01	8
Site 23	7.12	0.35	1430	1705	0.12	18
Site 24	9.15	0.35	1415	1710	0.25	18
Site 26	4.74	0.35	1385	1690	0.1939	18

Precipitation Depth-Duration-Frequency Values						Mean Annual Rainfall (in) =	
50-Year Storm			100-Year Storm			60	
Time, Min	Depth (in)	Inch/hr.	Time, Min.	Depth (in)	Inch/hr.		
10	0.620	3.72	10	0.693	4.16		

ID#	Runoff Coef. (K)	Altitude Index (1000's ft.)	Time of Concn. (min)	24-hr. Rainfall Intensity (in/hr)	Mean Annual Rainfall (in)	Drainage Area (ac)	Selected Discharge Method	Q 100	
								RATIONAL (cfs)	USGS MF (cfs)
Site 03	0.35	0.0	2	4.16	60	1.07	RATIONAL	1.56	1.86
Site 04	0.35	0.0	2	4.16	60	1.05	RATIONAL	1.53	1.83
Site 05	0.35	0.0	2	4.16	60	2.18	RATIONAL	3.17	3.45
Site 06	0.35	0.0	3	4.16	60	4.29	RATIONAL	6.24	6.19
Site 07	0.35	0.0	3	4.16	60	6.13	RATIONAL	8.92	8.44
Site 08	0.35	0.0	2	4.16	60	1.79	RATIONAL	2.60	2.91
Site 11	0.35	0.0	2	4.16	60	2.60	RATIONAL	3.78	4.01
Site 13	0.35	0.0	2	4.16	60	2.03	RATIONAL	2.95	3.24
Site 35	0.35	0.0	0	4.16	60	1.60	RATIONAL	2.33	2.64
Site 23	0.35	0.0	2	4.16	60	7.12	RATIONAL	10.36	9.60
Site 24	0.35	0.0	4	4.16	60	9.15	RATIONAL	13.32	11.94
Site 26	0.35	0.0	3	4.16	60	4.74	RATIONAL	6.90	6.75

ID#	Existing	Headwall	Selected	Discharge	Q100	Culvert	Culvert is	Recommended	Recommendation
	Culvert (D)	(HW)				HW/D		Capacity	
	Diameter (in)	Height (in)	Method	(cfs)	(cfs)	Undersized	(in)		
Site 03	12	0	0.0	RATIONAL	1.56	1.30		18	Q100
Site 04	12	0	0.0	RATIONAL	1.53	1.30		18	Q100
Site 05	15	0	0.0	RATIONAL	3.17	2.20	TRUE	18	Q100
Site 06	12	0	0.0	RATIONAL	6.24	1.30	TRUE	24	Q100
Site 07	12	0	0.0	RATIONAL	8.92	1.30	TRUE	30	Q100
Site 08	12	0	0.0	RATIONAL	2.60	1.30	TRUE	18	Q100
Site 11	24	0	0.0	RATIONAL	3.78	7.10		24	Q100
Site 13	0	0	0.0	RATIONAL	2.95	0.00	TRUE	18	Q100
Site 35	8	0	0.0	RATIONAL	2.33	0.00	TRUE	18	Q100
Site 23	18	0	0.0	RATIONAL	10.36	3.50	TRUE	30	Q100
Site 24	18	0	0.0	RATIONAL	13.32	3.50	TRUE	36	Q100
Site 26	18	0	0.0	RATIONAL	6.90	3.50	TRUE	24	Q100

Spoils Management:

Project Compliance Y / N

Currently, no spoils are present on the property. Any/all spoils generated through development or maintenance of roads, driveways, earthen fill pads, or other cleared or filled areas have not been side cast in any location where they can enter or be transported to surface waters. Any/all future spoils generated as a result of any future construction projects that are to be stored on the property shall be done so in accordance with the BPTC.

Riparian and Wetland Protection and Management:

Project Compliance Y / N

No disturbed areas were identified as being within riparian areas. All Past Cultivation Areas within the riparian setbacks have either naturally or artificially revegetated, and pose no threat to water quality.

Table 4: Riparian and Wetland Protection and Management

Disturbed Area	Disturbance Area Distances and Riparian Setbacks				
	Class I [Setback: 150']	Class II or Wetland [Setback: 100'] ¹	Class III [Setback: 50']	Perennial Spring [Setback: 150']	Disturbed Area Within Setbacks [ft ²]
Cultivation Area A	>200'	>130'	160'	>200'	0
Cultivation Area B	>200'	>200'	>80'	>200'	0
				Total =	0

Water Storage and Use:Project Compliance Y/N

All water on the property is derived from an off-stream rain catchment pond and a historic surface water diversion located on the property. The surface water diversion meets and exceeds the required water demands for both domestic and agricultural use. However, the off-stream rain catchment pond does not currently have enough volume to provide or hold water sufficiently to adequately provide water resources for irrigation purposes. Due to this the pond will be deepened to accommodate a larger, adequate, volume of water.

At present, there are no metering devices in place to record water usage associated with the irrigation of cannabis. If the water source is completely non-jurisdictional e.g. wells or off-stream pond with no inputs from surface water diversions water use may be recorded by a meter(s), calculated irrigation times, pump and fill tank measurements, or any other reasonably accurate means. Metering device(s) to monitor water usage shall be used to record all water used for the irrigation of cannabis and domestic use.

No matter the source or means of measurement, per the State General Order, all water used for the irrigation of cannabis shall be recorded daily, and recorded water use data shall be kept and maintained for 5 years. Monthly water usage shall be recorded for annual reporting purposes. These records are to be current, maintained, kept on-site, and presented should they be requested.

If water is also used for domestic uses, domestic water is to be metered separately from water used for the irrigation of cannabis and is required the same recording and record-keeping as water used for cannabis. Water meter(s), or water usage procedures, and water supply infrastructure shall be designed/installed in a manner such that water usage for the irrigation of cannabis can be recorded separately from water used for domestic use. Additionally, if there are multiple diversions of surface water, infrastructure/metering device(s) shall be designed/installed in a manner that each source of surface water is recorded separately.

For domestic use, water is stored in, and transferred from, two 305-gallon tanks, one 550-gallon tank, two 1,100-gallon tanks, and one 2,500-gallon tank. For agricultural use, water is caught and stored in an off-stream rain catchment pond with a current approximate volume of 500,000 gallons that will be increased to an unspecified volume. Multiple water storage tanks were found to have lids not in place to prevent access and entrapment of wildlife. Tank lids shall be kept closed at all times when access is not needed to prevent access and entrapment of wildlife. Tanks that do not utilize lids shall be retrofitted to be enclosed from wildlife. During the assessment water storage tanks were seen overflowing with diverted surface waters. Overflow prevention measures shall be installed on water storage and transfer infrastructure or water storage tanks to prevent the overflowing of tanks and unnecessary waste of water resources when water storage infrastructure has filled. Water conservation measures such as drip-line irrigation, morning or evening watering, and mulch or cover cropping of cultivated topsoils shall also be implemented.

At this time, the cannabis cultivator has 505,860 gallons of water storage installed for irrigation and domestic uses. Based on estimates, and considering the increased volume once the pond is enlarged, this volume of storage is sufficient to allow for full forbearance during the required period from April 1st to October 31st. Recorded water use data shall be used to determine remaining, or exact, storage needs to meet full forbearance. If in the future the volume of storage is insufficient, additional storage needed to meet water needs during the Forbearance Period shall be installed and filled before the next Forbearance Period. Monthly water usage estimates and the season total are as follows below.

Table 5: Estimated Annual Water Use

	Jan	Feb	March	April (25%)	May (60%)	Jun (80%)	Jul (100%)	Aug (100%)	Sep (70%)	Oct (20%)	Nov	Dec
Agriculture				17,438	40,500	54,000	67,500	67,500	47,250	13,500		
Sq. ft. =								% = percent of peak usage				
30,000												
								Total AG Water Use =			307,688	

Cannabis cultivators should be advised that transition to the state General Order will require additional infrastructure to use bladders for water storage.

A Lake and Streambed Alteration Agreement with the California Department of Fish and Wildlife will be submitted to continue the use of any diversions. If surface waters are diverted from the Points of Diversion(s) to storage and for later use for irrigation, a Small Irrigation Use and Registration with the California State Water Resource Control Board Division of Water Rights will be required. Any additional guidelines, treatments, or restrictions set forth under the finalized Lake and Stream Agreement shall be followed.

Irrigation Runoff:

During visits to the property, no irrigation runoff, or evidence of such runoff, was observed at any of the cultivation areas.

Fertilizers, Soils, Pesticides, and Petroleum Products:

Project Compliance Y/N

Fertilizers, pesticides, potting soils, compost, and other soils and soil amendments are stored currently on the property in a manner in which they will not enter or be transported into surface waters and so that nutrients or other pollutants will not be leached into groundwater. Cultivation areas will be maintained to prevent nutrients from leaving the site during the growing season and post-harvest.

However, at Site 31 a soil pile is located within the setbacks of a wetland area and shall be removed. Currently the soil pile is vegetated with grasses and thistles and not being transported or entering the adjacent wetland area. The thistles shall be removed as feasibly possible.

Fertilizers and soil amendments shall be applied and used per the manufacturer’s guidelines. The use of pesticide products shall be consistent with product labeling and all products on the property

are to be stored in closed structures to ensure that they do not enter or are released into surface or ground waters.

Currently, no petroleum products are present on the property. No trailered generators were present on the property on the date of inspection. If used, trailered generators require adequate secondary containment and shall have adequate secondary containment and cover from precipitation so that the secondary containment does not fill with precipitation.

Any/all fuel canisters, motor oil containers, and generators (large or small) shall be stored in secondary containment (e.g. drip pans, plastic totes, or sealed metal boxes) while being stored long term or not in immediate use, wherever these materials are used anywhere on the property. Fuel and oil spill kits shall be kept on-site wherever fuel is stored or where any petroleum-powered generator or pump is fueled. These kits shall be appropriately sized for the amount of fuel or oil that they are intended to be used on (e.g. the spill kit stored next to a 1,000-gallon fuel tank should be designed to contain an accidental spill of that amount, the same applies to a 5-gallon fuel canister and small generator or pump). See the Mitigation Report, Treatment Implementation Schedule, and Site Map to follow for site-specific details and treatments.

Should the cannabis cultivator at any point in the future obtain fuel storage or petroleum products, any/all future petroleum products and other liquid chemicals, including but not limited to diesel, biodiesel, gasoline, and oils shall be stored to prevent their spillage, discharge, or seepage into receiving waters. Storage tanks and containers shall be of suitable material and construction to be compatible with the substance(s) stored and conditions of storage such as pressure and temperature. Above ground storage tanks and containers shall be provided with a secondary means of containment for the entire capacity of the largest single container and sufficient cover shall be provided to prevent any/all precipitation from entering said secondary containment vessel. Cannabis cultivators shall ensure that diked areas are sufficiently impervious to contain discharged chemicals. Cannabis cultivators shall implement spill prevention, control, and countermeasures (SPCC) and have appropriate cleanup materials available onsite if the volume of a fuel container is greater than 1,320 gallons. Underground storage tanks 110 gallons and larger shall be registered with the appropriate County department and comply with state and local requirements for leak detection, spill overflow, corrosion protection, and insurance coverage. On-site storage of petroleum products or other fuels used for commercial activities may require registration as hazardous materials through the California Environmental Reporting System (CERS). Additionally, any waste oil generated from commercial activities (generators) is considered by the state hazardous waste and requires additional reporting. This cannabis cultivator is advised to contact local agencies to find out if such reporting applies to current operations.

Cultivation-Related Wastes:Project Compliance Y /N

Cultivation-related wastes, including, but not limited to, empty soil/soil amendment/fertilizer/pesticide bags and containers, empty plant pots or containers, dead or harvested plant waste, and spent growth medium, are stored in locations where they can enter or be blown into surface waters, or in a manner that could result in residues and pollutants within such materials to migrate or leach into surface water or groundwaters.

See Sites 20, 22, 31, and the Past Cultivation Areas in the Mitigation Report, Treatment Implementation Schedule, and Site Map to follow for site-specific details and treatments.

Organic cultivation-related wastes are collected from the cultivation areas and either disposed of properly with general waste or composted. The cannabis cultivator shall ensure that the locations where organic wastes are stored or composted are minimized in number and are sited outside of watercourse riparian areas and away from any form of surface runoff.

Non-organic cultivation-related wastes are stored in lidded trashcans and garbage bags adjacent to or in the residence, sheds, and cultivation areas and are disposed of regularly at a solid waste transfer station. The cannabis cultivator shall continue to gather and properly dispose of cultivation-related wastes and ensure that wastes are adequately contained from scavenging wildlife, and cannot be transported away from storage areas by wind or surface runoff.

Refuse and Domestic Waste:Project Compliance Y /N

Garbage and refuse are stored on the property within lidded trash cans and garbage bags and are disposed of regularly at the nearest solid waste transfer station. The cannabis cultivator shall continue to gather and properly dispose of refuse and ensure that refuse is adequately contained from scavenging wildlife, and cannot be transported away from storage areas by wind or surface runoff.

Human waste is managed by a septic system on site. Portable chemical toilets will be used in addition to the existing septic system once the property is permitted. It is the cannabis cultivator's responsibility to ensure compliance with such action with the Humboldt County Department of Environmental Health and Human Services.

Annual Winterization Measures

Winterization measures consist of general cleanup and winter-preparation activities that both prepare for and utilize, anticipated, local winter weather.

- Any exposed soils resulting from winterization activities shall be seeded and straw mulch.
- Any/all areas of exposed soils in and around cultivation areas are seeded and either straw mulched with weed-free straw or woodchips.
- All existing culvert inlets, interiors, and outlets shall be cleared of any existing or potential obstructions to include; debris upstream of the culvert such as sediment, loose, moveable rocks, and raftable, small, woody debris.
- Damage or wear resulting from vehicular use to road surfaces (such as rutting or wheel tracks) and/or road surfacing (such as rock) that would impair road surface drainage or drainage features (such as outsloping, waterbars, rolling dips, etc.) shall be repaired before the Winter Period.
- All existing surface drainage features and sediment capture features shall be maintained if needed to ensure continued function through the Winter Period.
- All fertilizers and petroleum products will be stored in an area located outside of riparian setbacks, completely sealed, placed in secondary containment (liquids), and stored in a manner that prevents contact with precipitation and surface runoff.
- Chemical toilets will be removed from the property until need resumes the following cultivation season, or at a minimum serviced and left unused during periods when not in use.
- Water storage tank lids shall be appropriately closed to prevent the access of wildlife.
- All refuse/trash shall be removed and disposed of appropriately.
- All inorganic material capable of being transported by wind or rain shall be secured and stored appropriately.

SITE MANAGEMENT PLAN GENERAL GUIDANCE OUTLINE

Implementation of Applicable BPTC Measures

Assessment of applicable BPTC measures consisted of a field examination on February 3rd, June 8th, and July 7th, 2021. Anywhere applicable BPTC measures are not met on the property, descriptions of the assessments and the prescribed treatments are outlined following each associated section below.

Summary of BPTC Measures Compliance

1. Sediment Discharge BPTC Measures Y/N
2. Fertilizer, Pesticide, Herbicide, and Rodenticide BPTC Measures Y/N
3. Petroleum Product BPTC Measures Y/N
4. Trash/Refuse, and Domestic Wastewater BPTC Measures Y/N
5. Winterization BPTC Measures Y/N

1. Sediment Discharge BPTC Measures

1.1. Site Characteristics

- 1.1.1. Provide a map showing access roads, vehicle parking areas, streams, stream crossings, cultivation site(s), disturbed areas, buildings, and other relevant site features.

See attached Site Map.

- 1.1.2. Describe the access road conditions including estimating vehicle traffic, road surface (e.g., paved, rocked, or bare ground), and maintenance activities. Describe how stormwater is drained from the access road (e.g., crowned, out slope, armored ditch, culverts, rolling dips, etc.).

See section “Land Development and Maintenance, Erosion Control, and Drainage Features” above, the attached Mitigation Report, Site Maps, and Treatment Implementation Schedule for site-specific descriptions, treatments, and the implementation schedule.

- 1.1.3. Describe any vehicle stream crossing including the type of crossing (e.g., bridge, culvert, low water, etc.).

See the section titled “Stream Crossing Installation and Maintenance” or the attached Mitigation Report and Site Maps for site-specific details and treatment schedules.

- 1.1.3.1. For Region 1 Dischargers, identify, discuss, and locate on the site map any legacy waste discharge issues that exist on the property.

Not applicable. No legacy waste discharge issues were identified during the assessment of the property.

- 1.2. Sediment Erosion Prevention and Sediment Capture (Moderate risk Tier 1 or Tier 2 Dischargers are required to submit a Site Erosion and Sediment Control Plan. Those Dischargers may refer to that plan rather than repeat it here)

1.2.1. Erosion Prevention BPTC Measures

- 1.2.1.1. Describe the BPTC measures that have been, or will be implemented to prevent or limit erosion. Provide an implementation schedule for BPTC measures that have not yet been implemented. Identify the erosion prevention BPTC measures on a site map.

See section “Land Development and Maintenance, Erosion Control, and Drainage Features”, attached Mitigation Report, Site Maps, Photographs, and Treatment Implementation Schedule for site-specific descriptions of physical BPTC measures being prescribed.

- 1.2.1.1.1. The description shall address physical BPTC measures, (e.g., placement of straw mulch, plastic covers, slope stabilization, soil binders, culvert outfall armoring, etc.) and biological BPTC measures (vegetation preservation/replacement, hydroseeding, etc.).

1.2.2. Sediment Control BPTC Measures

- 1.2.2.1. Describe the BPTC measures that have been, or will be implemented to capture sediment that has been eroded. Provide an implementation schedule for BPTC measures that have not yet been implemented. Identify the sediment control BPTC measures on a site map.

Not applicable. No BPTC measures have been or will need to be, implemented to capture sediment that has been eroded.

- 1.2.2.1.1. The description shall address physical BPTC measures, (e.g., placement of silt fences, fiber rolls, or settling ponds/areas, etc.) and biological BPTC measures (vegetated outfalls, hydroseeding, etc.).

1.2.3. Maintenance Activities - Erosion Prevention and Sediment Control

- 1.2.3.1. Describe how erosion prevention and sediment control BPTC measures will be monitored and maintained to protect water quality.

All recommended mitigations and annual maintenance work shall be inspected prior to and in conjunction with winter monitoring, as described in the attached “Monitoring Plan” to ensure that proper placement and installation, remain intact and functioning prior to and throughout the Winter Period.

1.2.3.2. Describe how any captured sediment will be either stabilized in place, excavated and stabilized on-site, or removed from the site.

Any significant amount of sediment and/or debris captured by drainage features will be allowed to stabilize and vegetate in place until the drainage feature is maintained. At that time the drainage feature will be cleared of obstructing sediment or debris so that it can continue to prevent further erosion.

1.2.4. Erosion control BPTC measures: Describe the interim soil stabilization, if applicable and long-term BPTC measures implemented to prevent sediment transport at each identified disturbed area(s) and improperly constructed features.

Not applicable. Currently there are no disturbed areas requiring erosion control measures. Disturbed areas associated with the installation of relocated cultivation areas will be treated with erosion control measures prescribed in the grading plan, or as needed, per the grading plans BPTC's or the attached BMPs.

2. Fertilizer, Pesticide, Herbicide, and Rodenticide BPTC Measures

2.1. Provide a summary table that identifies the products used at the site, when they are delivered to the site, how they are stored, and used at the site. If products are not consumed during the growing season, describe how they are removed from the site or stored to prevent discharge over the winter season.

Cannabis cultivation on the parcel was not active. The cultivator is in the process of getting county approval for cannabis cultivation on the parcel. An estimate of the products to be used is given below.

2.2. Provide a site map that locates storage locations.

Cannabis cultivation on the parcel was not active. Fertilizers and soil amendments were not being stored on the parcel. Storage locations will likely be near cultivation areas once they are approved and active. There are several sheds and covered areas on the property that would be likely locations. Storage locations shall be located outside of riparian setbacks and shall follow Cannabis Cultivation Policy, Att. A, Sec. 2, - Term 103 through 115.

2.3. Describe how bulk fertilizers and chemical concentrates are stored, mixed, applied, and how empty containers are disposed of.

Fertilizer, Pesticides, and Herbicide Products potentially used on Site

Product	Delivery and Storage	On-site usage	How removed or stored
Not known at this time.	Will likely be brought to the property in spring and during the season as needed. Products are required to be used and stored per Cannabis Cultivation Policy, Att. A Sec. 2, - Term 103 through 115.	Products to be used are not known at this time.	Unused products that remain on the parcel shall be removed or disposed of properly per Cannabis Cultivation Policy, Att. A Sec. 2, - Term 103 through 115. Cannabis cultivators are required to contain and regularly remove all debris and trash associated with cannabis cultivation activities from the cannabis cultivation site.

2.4. Describe procedures for spill prevention and cleanup.

The cannabis cultivator shall keep and use absorbent materials designated for spill containment and clean-up for use in an accidental spill. Should a spill of these materials occur, absorbent materials will be applied and cleaned up immediately following the manufacturer’s guidelines. See Cannabis Cultivation Policy, Att. A, Sec. 2, - Term 103 through 115 that is attached.

3. Petroleum Product BPTC Measures

3.1. Provide a summary table that identifies the products used at the site, when they are delivered to the site, how they are stored, and used at the site. If products are not consumed during the growing season, describe how they are removed from the site or stored to prevent discharge over the winter season.

See comprehensive table under 3.3.

3.2. Provide a site map that locates storage locations.

Cannabis cultivation on the parcel was not active. Storage locations will likely be in secure, covered areas outside of riparian setbacks per Cannabis Cultivation Policy, Att. A, Sec. 2, - Term 103 through 110, and 116 through 118.

3.3. Describe how fuels, lubricants, and other petroleum products are stored, mixed, applied, and empty containers are disposed of.

Petroleum products are required to be used and stored per Cannabis Cultivation Policy, Att. A, Sec. 2, - Term 103 through 110, and 116 through 118. The table below gives estimates.

Petroleum Products

Products used on site	When they are delivered to the site	How they are stored and used	How removed or stored
Gasoline	TBD	TBD	TBD, however, most likely will be stored in steel tanks, canisters, and the equipment's fuel tanks until it is used or within storage structures.
Propane	Brought to the site when needed throughout the year.	Stored in a fixed location propane tank or portable propane tanks. Used to fuel generators.	Stored in the fixed location propane tank or portable tanks until used.
Motor oil	TBD	TBD, however, most likely will be Stored alongside equipment or within storage sheds. Used to lubricate internal combustion engines.	TBD, however, most likely will be handled like this: After oil changes, the used motor oil is stored in either the container it came in or in sealed 5-gallon buckets for later disposal at an appropriate waste disposal facility.

3.4. Describe procedures for spill prevention and cleanup.

Any/all fuel canisters, motor oil containers, and small generators shall be stored in secondary containment (e.g. drip pans, plastic totes, or sealed metal boxes) while being stored long term or not in immediate use. Adequate quantities of absorbent materials shall be stored at all locations where these types of materials are used, stored, or mixed. Should a spill of these materials occur, absorbent materials will

be applied immediately and allowed enough time to absorb as much material as possible. Following treatment, absorbent materials applied as well as any contaminated soil will be removed and disposed of appropriately for the spilled material.

4. Trash/Refuse, and Domestic Wastewater BPTC Measures

- 4.1. Describe the types of trash/refuse that will be generated at the site. Describe how the material is contained and properly disposed of.

Domestic and commercial cannabis refuse will be generated at the site. The refuse is securely stored in trash bags, trash bins, and a utility trailer at the cultivation areas, residences, and within a contained refuse storage shed adjacent to the residences before disposal at an appropriate waste disposal facility.

- 4.1.1. Provide a site map that locates the trash/refuse storage locations.

Refuse is stored in trash bags, trash bins, and a utility trailer at mapped cultivation areas and the structures. See attached Site Map.

- 4.2. Describe the number of employees, visitors, or residents at the site.

There are going to be an estimated two regular employees who are at the site during the cultivation season. Additional employees are brought onto the property for short periods to complete projects requiring additional employees. Visitors are occasionally on-site, including consultants and regulatory agencies. There is also a full-time residence on the property as well.

- 4.2.1. Describe the types of domestic wastewater generated at the site (e.g., household-generated wastewater or chemical toilet).

Domestic sewage and wastewater (greywater) are generated on-site.

- 4.2.2. Describe how the domestic wastewater is disposed of.

- 4.2.2.1. Permitted onsite wastewater treatment system (e.g., septic tank and leach lines).

Domestic wastewater is currently disposed of via a septic system attached to the house. In the future, a chemical toilet service company could be hired for areas near the cultivation areas during the growing season.

Per Cannabis Cultivation Policy, Att. A, Sec. 2, Term 124 - Cannabis cultivators shall not dispose of domestic wastewater unless it meets applicable local agency and/or Regional Water Board requirements. Cannabis cultivators shall ensure that human or animal waste is disposed of properly. Cannabis cultivators shall ensure onsite wastewater treatment systems (e.g., septic system) are permitted by the local agency or applicable Regional Water Board. Term 125 states - if used, chemical toilets or holding tanks shall be maintained in a

manner appropriate for the frequency and conditions of usage, sited in stable locations, and comply with the riparian setback requirements.

- 4.2.2.2. Chemical toilets or holding tank. If so, provide the name of the servicing company and the frequency of service.

Not known at this time.

- 4.2.2.3. Outhouse, pit privy, or similar. Use of this alternative requires approval from the Regional Water Board Executive Officer; include the approval from the Executive Officer and any conditions imposed for use of this alternative.

Not applicable.

- 4.2.2.3.1. Provide a site map that locates any domestic wastewater treatment, storage, or disposal area.

See attached Site Map for locations of residences with attached septic and greywater systems.

5. Winterization BPTC Measures

- 5.1. Describe activities that will be performed to winterize the site and prevent discharges of waste. The description should address all the issues listed above.

See Mitigation Report and Annual Winterization Measures for prescribed general winterization measures that will be performed before each Winter Period, and site-specific interim measures that will be performed before the Winter Period until permanent, prescribed treatments can be executed.

- 5.2. Describe maintenance of all drainage or sediment capture features (e.g., drainage culverts, drainage trenches, settling ponds, etc.) to remove debris, soil blockages, and ensure adequate capacity exists.

Existing road surface drainage structures will be maintained or repaired as feasible and necessary with hand tools during annual winterization and monitoring. Prescribed repair and maintenance will be executed in accordance with the Mitigation Report, Annual Winterization Measures, Monitoring Plan, and the attached BMPs.

- 5.3. Describe any revegetation activities that will occur either at the beginning or end of the precipitation season.

See the Annual Winterization Measures, Monitoring Plan, and the attached BMPs for a description of areas requiring treatment with seed and straw mulch for erosion control prior to next winter period.

- 5.4. If any BPTC measure cannot be completed before the onset of the Winter Period, contact the Regional Water Board to establish a compliance schedule.

See the attached Mitigation Report and Treatment Implementation Schedule for site descriptions, treatments, and the implementation schedule.

- 5.5. For Region 1 Dischargers, describe any activities that will be performed to address legacy waste discharge issues. Region 6 Dischargers should consult with Regional Water Board staff to confirm if any other activities in addition to BPTCs are necessary to address legacy waste discharge issues.

Not applicable. No legacy waste discharge issues were identified during the assessment of the property.

**STATEMENT OF CONTINGENT AND LIMITING CONDITIONS CONCERNING
THE PREPARATION AND USE OF REPORTS ADDRESSING GENERAL
WASTE DISCHARGE REQUIREMENTS UNDER ORDER WQ 2017-0023-DWQ**

Prepared by Timberland Resource Consultants

1. This document has been prepared for the property within APN 222-071-030, in Humboldt County, for enrollment in the General Waste Discharge Order WQ 2019-0001-DWQ.
2. Timberland Resource Consultants does not assume any liability for the use or misuse of the information in this document.
3. The information is based upon conditions apparent to Timberland Resource Consultants at the time inspection(s) were conducted. Changes due to land use activities or environmental factors occurring after inspection have not been considered in this document.
4. Maps, photos, and any other graphical information presented in this report are for illustrative purposes. Their scales are approximate, and they are not to be used for locating and establishing boundary lines.
5. The conditions presented in this document may differ from those made by others or from changes on the property occurring after inspections were conducted. Timberland Resource Consultants does not guarantee this work against such differences.
6. Timberland Resource Consultants did not investigate a legal survey of the property.
7. Persons using this document are advised to contact Timberland Resource Consultants before such use.
8. Timberland Resource Consultants will not discuss this document or reproduce it for anyone other than the Client for which this document was prepared without authorization from the Client.



Forrest Hansen

Timberland Resource Consultants

Monitoring Plan

Cannabis cultivators shall regularly inspect and maintain the condition of access roads, access road drainage features, and watercourse crossings. At a minimum, cannabis cultivators shall perform inspections before the onset of fall and winter precipitation and following storm events that produce at least 0.5 in/day or 1.0 inch/7 days of precipitation. See Required Monitoring tables below for site-specific monitoring and reporting requirements. Cannabis cultivators are required to perform all of the following maintenance:

- Remove any wood debris that may restrict flow in a culvert.
- Remove sediment that impacts access road or drainage feature performance.
- Place any removed sediment in a location outside the riparian setbacks and stabilize the sediment.
- Maintain records of access road and drainage feature maintenance for annual reporting.

Cannabis cultivators that are operating in areas that are, or may become, inaccessible during winter months due to extreme weather such as snow, road closures, seasonal access roads to the property, or any other such conditions shall make additional efforts to enhance winterization measures in the absence of monitoring during storm events.


Monitoring Requirements

(Tier 1, Low-Risk, < 1 acre of cultivation)

Monitoring Requirement	Description
Winterization Measures Implemented	Report winterization procedures implemented, any outstanding measures, and the schedule for completion.
Tier Status Confirmation	Report any changes in the tier status.
Third-Party Identification	Report any change in third-party status as appropriate.

Annual Reporting

Annual Reports shall be submitted to the North Coast Regional Water Quality Control Board by March 1st following the year being monitored. The first Annual Report for this enrollment shall be submitted by March 1st, 2022, and a report on monitoring done during the 2021 calendar year. Annual reporting is required each subsequent year of enrollment.

		<h2 style="text-align: center;">Treatment Implementation Schedule</h2>	
Unique Point	Proposed Work Completion Date		
Immediately			
ST3	Immediately		
Water Storage and Use	Immediately		
Past Cultivation Areas	Immediately		
Prior to 10/15/22			
Site 01/WQ 2	Prior to 10/15/22		
Site 2	Prior to 10/15/22		
Site 09	Prior to 10/15/22		
Site 10	Prior to 10/15/22		
Site 12	Prior to 10/15/22		
Site 15	Prior to 10/15/22		
Site 16	Prior to 10/15/22		
Site 18	Prior to 10/15/22		
Site 20	Prior to 10/15/22		
Site 22/ST2	Prior to 10/15/22		
Site 25	Prior to 10/15/22		
Site 31	Prior to 10/15/22		
Site 32/R1/WQ 11	Prior to 10/15/22		
Site 33	Prior to 10/15/22		
Site 34	Prior to 10/15/22		
Prior to 10/15/23			
Site 03/WQ 3	Prior to 10/15/23 pending the approval of any required permits		
Site 04/WQ 4	Prior to 10/15/23 pending the approval of any required permits		
Site 05/WQ 5	Prior to 10/15/23 pending the approval of any required permits		
Site 06/WQ 6	Prior to 10/15/23 pending the approval of any required permits		
Site 07/WQ 7	Prior to 10/15/23 pending the approval of any required permits		
Site 08/WQ 8	Prior to 10/15/23 pending the approval of any required permits		
Site 13	Prior to 10/15/23 pending the approval of any required permits		
Site 14/WQ 10	Prior to 10/15/23 pending the approval of any required permits		
Site 28/WQ 19	Prior to 10/15/23		
Site 29/WQ 20	Prior to 10/15/23		
Site 30	Prior to 10/15/23		
Site 36	Prior to 10/15/23		
Site 35/C1	Prior to 10/15/23 pending the approval of any required permits		
Prior to 10/15/24			
Site 11/WQ 9	Prior to 10/15/24 pending the approval of any required permits		
Site 17/C4	Prior to 10/15/24 pending the approval of any required permits		
Site 19/C3/C3.1	Prior to 10/15/24 pending the approval of any required permits		
Site 23/C2/WQ 16	Prior to 10/15/24 pending the approval of any required permits		
Site 24/WQ 17	Prior to 10/15/24 pending the approval of any required permits		
Site 26/WQ 18	Prior to 10/15/24 pending the approval of any required permits		
Site 37/WQ 13	Prior to 10/15/24 pending the approval of any required permits		
Site 38/WQ 14	Prior to 10/15/24 pending the approval of any required permits		
As required			
Liquid Petroleum Products	As required		
Generators and Gas Powered Pumps	As required		
Site 21	-		
Site 27	As required		
POD/P1/WQ 12	As required		
P2	-		
G1, G2, G3, G4, OG1	-		

Site Management Plan

Site Map [WDID - 1_12CC407540]



	Property Boundary		Wetland
	Proposed Cultivation		Riparian Area
	Disturbed Area - None		Pond
	Past Cultivation		Structure


Roads	
	Permanent
	Seasonal Access
	Trail
	Foot Trail
	Legacy

Watercourses	
	Class II
	Class III
	Class IV

	Site
	POD
	Tank

40 contour intervals
 Map Date 09/10/2021
 Non-Site labels reference Waterboard
 Inspection Reports from 2015 and 2020

TRC - 525



Site Management Plan

Site Map [WDID - 1_12CC407540]




	Property Boundary		Wetland
	Proposed Cultivation		Riparian Area
	Disturbed Area - None		Pond
	Past Cultivation		Structure

Roads	
	Permanent
	Seasonal Access
	Trail
	Foot Trail
	Legacy
Watercourses	
	Class II
	Class III
	Class IV

	Site
	POD
	Tank

2020 NAIP DOQ
Map Date 08/10/2021
Non-Site labels reference Waterboard
Inspection Reports from 2015 and 2020

TRC - 525





SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 01/WQ 2	-123.836474 40.020162	Permanent	X	X	-	Prior to 10/15/22	
<p>Current Condition: Existing ditch relief culvert currently drains 850' of inside ditch line which has formed a gully below the road. This segment of road to the west property boundary has outboard berms from road surface grading which prevent surface runoff from leaving the road.</p>						<p>Prescribed Action: Multiple ditch relief culverts are to be installed on the inside ditch on the adjoining parcel to the north which is also enrolled in the State Cannabis General Order. See that enrollment for details. (WDID# 1_12CC417597) From this site to Site 08 and the property boundary to the west, remove the outboard roadside berms and out slope sections of this road in-between and up grade of the upgraded watercourse crossings, as feasible.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 2	-123.837191 40.020056	Permanent	X	X	-	Prior to 10/15/22	
<p>Current Condition: Concentrated road surface runoff is eroding the road surface and discharging in the surface waters.</p>						<p>Prescribed Action: Install a rocked rolling dip as flagged in the field, per the specifications outlined in the attached BMPs. See rocked/Rolling Dip Design and Placement, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 03/WQ 3	-123.837191 40.020056	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 8" diameter corrugated metal pipe that is too short, shotgunned, not-to-grade, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert with an 18" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 04/WQ 4	-123.838823 40.020109	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 8" diameter steel pipe that is too short, shotgunned, not-to-grade, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert with an 18" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 05/WQ 5	-123.839084 40.020141	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 12" diameter double-walled plastic pipe that is too short, shotgunned, not-to-grade, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert with an 18" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 06/WQ 6	-123.839334 40.020049	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 12" diameter half corrugated half steel metal pipe that is too short, shotgunned, not-to-grade, eroding the road fillslope at the outlet, and undersized for the 100 year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert with a 24" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 07/WQ 7	-123.839607 40.019924	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 12" diameter corrugated metal pipe that is too short, shotgunned, not-to-grade, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert with a 30" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 08/WQ 8	-123.840219 40.019507	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 8" diameter corrugated metal pipe that is too short, shotgunned, not-to-grade, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert crossing with an 18" culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 09	-123.835825 40.019852	Permanent	X	X	-	Prior to 10/15/22	
<p>Current Condition: Long, undrained, inside ditch is discharging to surface waters to the inlet of the watercourse crossing culvert at Site 11.</p>						<p>Prescribed Action: Install a 15" diameter ditch relief culvert per the specifications outlined in the attached BMPs. See Ditch Relief Culvert, and Permanent Culvert Crossing Design (Inlet and Outlet Armoring), General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 10	-123.835528 40.019428	Permanent	X	X	-	Prior to 10/15/22	
<p>Current Condition: Long, undrained, inside ditch is discharging to surface waters to the inlet of the watercourse crossing culvert at Site 11.</p>						<p>Prescribed Action: Install a 15" diameter ditch relief culvert per the specifications outlined in the attached BMPs. See Ditch Relief Culvert, and Permanent Culvert Crossing Design (Inlet and Outlet Armoring), General Operations BMPs, and General Erosion Control specifications.</p>	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 11/WQ 9	-123.83519 40.019238	Permanent	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of a 24" diameter double-walled plastic pipe that is adequately sized for the 100-year event but it is too short and lacks a rock armor energy dissipater that is resulting in the erosion of the fillslope.</p>						<p>Prescribed Action: Attach a minimum 20' culvert extension to the outlet of the existing culvert with a flexible single-walled 24" diameter pipe that outlets approximately where the existing flagging in the channel is located. Rock armor the outlet per the specifications outlined in the attached BMPs. See Permanent Culvert Crossing: Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 12	-123.8348 40.018782	Permanent	X	X	-	Prior to 10/15/22	
<p>Current Condition: Concentrated road surface runoff is eroding the road surface and discharging to surface waters.</p>						<p>Prescribed Action: Install a rocked rolling dip as flagged in the field, per the specifications outlined in the attached BMPs. See rocked/Rolling Dip Design and Placement, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 13	-123.834838 40.018542	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Class III watercourse lacks an adequate watercourse crossing and is being diverted down the inside ditch approximately 150' before being drained by the ditch relief culvert at Site 14.</p>						<p>Prescribed Action: Re-align the watercourse to its original channel by installing a new 18" diameter culvert crossing per the specifications in the attached BMP's. See Ditch Relief Culvert, and Permanent Culvert Crossing Design (Inlet and Outlet Armoring), General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 14/WQ 10	-123.835105 40.018163	Permanent	X	X	-	Prior to 10/15/23 pending the approval of any required permits	
<p>Current Condition: Ditch relief culvert consisting of a 12" diameter corrugated metal pipe that is shotgunned, not-to-grade, too short, and rusted through causing significant scour and erosion of the road fill prism. A Class III watercourse was diverted up grade by the inside ditch to this DRC.</p>						<p>Prescribed Action: Clear the inside ditch up grade to Site 13. Upgrade with a 18" diameter ditch relief culvert per the specifications outlined in the attached BMPs. See Ditch Relief Culvert, and Permanent Culvert Crossing Design (Inlet and Outlet Armoring), General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 15	-123.835168 40.018	Permanent	X	X	-	Prior to 10/15/22	
<p>Current Condition: Concentrated road surface runoff is eroding the road surface and discharging in the surface waters.</p>						<p>Prescribed Action: Install a rocked rolling dip as flagged in the field, per the specifications outlined in the attached BMPs. See rocked/Rolling Dip Design and Placement, General Operations BMPs, and General Erosion Control specifications.</p>	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 16	-123.835697 40.017686	Trail	X	X	-	Prior to 10/15/22	
Current Condition: Concentrated road surface runoff is eroding the road surface.						Prescribed Action: Install a waterbar to the specifications outlined in the attached BMPs. See attached BMPs: Waterbar Construction, General Operations BMPs, and General Erosion Control specifications.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 17/C4	-123.836204 40.017994	Trail	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
Current Condition: Class III watercourse crossing consisting of an 18" diameter double-walled plastic pipe on a road no longer needed or used.						Prescribed Action: Decommission the watercourse crossing per the specifications outlined in the attached BMPs: See Crossing Abandonment or Permanent Culvert Crossing, General Operations BMPs, and General Erosion Control specifications.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 18	-123.836856 40.018075	Trail	X	X	-	Prior to 10/15/22	
Current Condition: Concentrated road surface runoff is eroding the road surface and discharging to surface waters.						Prescribed Action: Install a waterbar to the specifications outlined in the attached BMPs. Maintain as necessary. See attached BMPs: Waterbar Construction, General Operations BMPs, and General Erosion Control specifications.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 19/C3/C3.1	-123.837057 40.018095	Trail	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
Current Condition: Class III watercourse crossing consisting of an 18" diameter double-walled plastic pipe on a road no longer needed or used. The installation of this culvert misaligned the watercourse.						Prescribed Action: Decommission the watercourse crossing, and re-align the watercourse as flagged, per the specifications outlined in the attached BMPs: See Crossing Abandonment, General Operations BMPs, and General Erosion Control specifications.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 20	-123.836426 40.017058	-	X	-	-	Prior to 10/15/22	
Current Condition: 10,000-gallon water storage bladder without containment.						Prescribed Action: Remove and dispose of the water storage bladder and all other cultivation-related wastes.	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 21	-123.837761 40.017071	-	-	-	-	-	
Current Condition: The "steep failing streambank" mentioned here in the original 2015 Inspection Report is associated with natural stream channel erosion which can be observed in other untouched reaches up and down channel from this. No development disturbances at this location created this condition. Also, the 2015 Inspection Report has no mention to why this location was even mentioned in the report or what the issue is with this location.						Prescribed Action: None. Site for reference.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 22/ST2	-123.835528 40.01678	-	X	-	-	Prior to 10/15/22	
Current Condition: Small, lined, off-stream water transfer and storage impoundment that has been cleaned up and disposed of.						Prescribed Action: Remove and dispose of the liner and all other cultivation-related wastes.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 23/C2/WQ 16	-123.835079 40.017189	Permanent	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
Current Condition: Class III watercourse crossing consisting of an 18" and 12" diameter corrugated metal pipes with one that is becoming plugged, and one already plugged, at the inlet, shotgunned, not-to-grade, too short, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.						Prescribed Action: Upgrade the existing culvert with an 30" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 24/WQ 17	-123.834765 40.01628	Permanent	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
Current Condition: Class III watercourse crossing consisting of an 18" diameter corrugated aluminum pipe that is shotgunned, not-to-grade, too short, eroding the road fillslope at the outlet, and undersized for the 100-year storm event. Concentrated road surface runoff is discharging to surface waters via a kickout drainage feature immediately down grade of the outlet.						Prescribed Action: Install a rocked rolling dip approximately 130' up grade of this watercourse crossing. Maintain the kickout drainage feature regularly. Upgrade the existing culvert with an 36" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 25	-123.834728 40.015839	Permanent	X	X	-	Prior to 10/15/22	
Current Condition: Concentrated road surface runoff is eroding the road surface and discharging in the surface waters.						Prescribed Action: Install a rocked rolling dip as flagged in the field that captures the inside ditch, per the specifications outlined in the attached BMPs. See rocked/Rolling Dip Design and Placement, General Operations BMPs, and General Erosion Control specifications.	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 26/WQ 18	-123.83422 40.015425	Permanent	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
<p>Current Condition: Class III watercourse crossing consisting of an 18" diameter steel pipe that is shotgunned, not-to-grade, too short, eroding the road fillslope at the outlet, and undersized for the 100-year storm event.</p>						<p>Prescribed Action: Upgrade the existing culvert with a 30" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 27	-123.834241 40.015334	Permanent	X	X	-	As required	
<p>Current Condition: Kickout drainage feature that is functioning properly.</p>						<p>Prescribed Action: None. Maintain regularly.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 28/WQ 19	-123.835923 40.014865	Permanent	X	X	-	Prior to 10/15/23	
<p>Current Condition: Long, undrained, inside ditch is discharging to surface waters down grade. Concentrated road surface runoff is eroding the road surface.</p>						<p>Prescribed Action: Clear the inside ditch up grade approximately 250'. Install an 18" diameter ditch relief culvert in combination with a rocked rolling dip, as flagged in the field, per the specifications outlined in the attached BMPs: See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 29/WQ 20	-123.83642 40.015433	Permanent	X	X	-	Prior to 10/15/23	
<p>Current Condition: Long, undrained, inside ditch is discharging to surface waters down grade. Concentrated road surface runoff is eroding the road surface.</p>						<p>Prescribed Action: Clear the inside ditch up grade approximately 250'. Install an 18" diameter ditch relief culvert in combination with a rocked rolling dip, as flagged in the field, per the specifications outlined in the attached BMPs: See Ditch Relief Culvert, and Permanent Culvert Crossing Design (Inlet and Outlet Armoring), General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 30	-123.836744 40.015336	Permanent	X	X	-	Prior to 10/15/23	
<p>Current Condition: Concentrated road surface runoff is eroding the road surface.</p>						<p>Prescribed Action: Install a rocked rolling dip as flagged in the field, per the specifications outlined in the attached BMPs. See rocked/Rolling Dip Design and Placement, General Operations BMPs, and General Erosion Control specifications.</p>	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 31	-123.834075 40.016781	-	X	-	-	Prior to 10/15/22	
Current Condition: Potting soils storage area within riparian setbacks and hosting thistles.						Prescribed Action: Relocate or reuse potting soils, eradicate thistles.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 32/R1/WQ 11	-123.834062 40.017236	Permanent	X	X	-	Prior to 10/15/22	
Current Condition: Pond overflow consisting of an 18" diameter double-walled pipe that is sized and functioning properly. However, the outlet lacks an adequate rock armor energy dissipater.						Prescribed Action: Install a rock armor energy dissipater per the specifications outlined in the attached BMPs. See Permanent Culvert Crossing Design: Inlet and Outlet Armoring.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 33	-123.834772 40.017832	Seasonal	X	X	-	Prior to 10/15/22	
Current Condition: Concentrated road surface runoff is eroding the road surface.						Prescribed Action: Install a rock armor energy dissipater per the specifications outlined in the attached BMPs. See Permanent Culvert Crossing Design: Inlet and Outlet Armoring.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 34	-123.834695 40.018155	Seasonal	X	X	-	Prior to 10/15/22	
Current Condition: Concentrated road surface runoff is eroding the road surface.						Prescribed Action: Install a rock armor energy dissipater per the specifications outlined in the attached BMPs. See Permanent Culvert Crossing Design: Inlet and Outlet Armoring.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 35/C1	-123.834266 40.01849	Permanent	X	X	X	Prior to 10/15/23 pending the approval of any required permits	
Current Condition: Class III watercourse crossing consisting of an 8" diameter corrugated metal pipe that is shotgunned, not-to-grade, too short, misaligned, and undersized for the 100-year storm event.						Prescribed Action: Upgrade the existing culvert with an 18" diameter culvert per the specifications in the attached BMP's. See Permanent Culvert Crossing, Permanent Culvert Crossing Design: Critical Dip and Hydrologic Disconnect Placement, Critical Dip, Culvert Orientation, Inlet and Outlet Armoring, General Operations BMPs, and General Erosion Control specifications.	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 36	-123.834668 40.019377	Permanent	X	X	-	Prior to 10/15/23	
<p>Current Condition: Existing ditch relief culvert consisting of a 15" diameter corrugated metal pipe that has a crushed inlet, improper angle, shotgunned, and exposed in the fill.</p>						<p>Prescribed Action: Clear the inside ditch up grade approximately 250'. Upgrade with a 15" diameter ditch relief culvert per the specifications outlined in the attached BMPs. See Ditch Relief Culvert, and Permanent Culvert Crossing Design (Inlet and Outlet Armoring), General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 37/WQ 13	-123.83238 40.016328	Legacy	X	X	-	Prior to 10/15/24 pending the approval of any required permits	
<p>Current Condition: Ditch relief culvert consisting of a 8" corrugated metal pipe that is no longer needed. No inside ditch or concentrated road surface runoff flows reach this culvert as the road up grade is heavily vegetated and not used. Legacy organic cultivation-related was observed within the outlet channel.</p>						<p>Prescribed Action: Remove the organic cultivation-related wastes from the outlet channel, remove the ditch relief culvert and install a waterbar to the specifications outlined in the attached BMPs. See Waterbar Construction, General Operations BMPs, and General Erosion Control specifications.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Site 38/WQ 14	-123.832253 40.015913	Legacy	X	X	X	Prior to 10/15/24 pending the approval of any required permits	
<p>Current Condition: Ditch relief culvert consisting of a 12" corrugated metal pipe that is no longer needed. No inside ditch or concentrated road surface runoff flows reach this culvert as the road up grade is heavily vegetated and not used. Legacy refuse metal debris have been discarded or used as rip-rap in the past below the outlet of the ditch relief culvert and is within the watercourse channel.</p>						<p>Prescribed Action: Remove the ditch relief culvert and install a waterbar to the specifications outlined in the attached BMPs. See Waterbar Construction, General Operations BMPs, and General Erosion Control specifications. Remove the legacy refuse metal debris, lay-back stream channel slopes, and treat disturbed soils with erosion control measures per the specifications outlined in the attached BMPs. See General Operations BMPs, and General Erosion Control specifications.</p>	
	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
POD/P1/WQ 12	-123.833113 40.01747	-	X	X	X	As required	
<p>Current Condition: Historic Point of Diversion of the Nelson Ranch, still in use.</p>						<p>Prescribed Action: Refer to Cannabis Cultivation Policy, Att. A, Sec. 2, Term 69, 74, 76, 77, 82, and 89 for the full text of requirements related to surface water diversions.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
P2	-123.834633 40.017287	-	-	-	-	-	
<p>Current Condition: POD and water storage tanks have been removed.</p>						<p>Prescribed Action: None. Site for reference.</p>	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
G1, G2, G3, G4, OG1	N/A	-	-	-	-	-	
Current Condition: All cultivation related wastes and refuse has been cleaned up and has been disposed of.						Prescribed Action: None. Site for reference.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
ST3	N/A	-	-	-	-	Immediately	
Current Condition: Plastic septic tank no longer in use.						Prescribed Action: None. Consult with Humboldt County Health and Human Services regarding the future of this septic tank.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Past Cultivation Areas	N/A	-	X	X	-	Immediately	
Current Condition: Past cultivation areas that are no longer used with remaining cultivation-related materials, fencing, and wastes.						Prescribed Action: Remove any remaining fencing, pots, or other cultivation-related wastes and materials from these areas. Seed and mulch the Past Cultivation Area, and any bare ground areas created during removal, with erosion control or native grass seed mix and weed free straw(or woodchips) per the specifications outlined in the attached BMPs: See General Erosion Control specifications. If cultivation soil is not re-used, contour the cultivation-related soils into the ground outside of any riparian buffer areas, and seed and mulch the contoured soils with erosion control or native grass seed mix and weed free straw.	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Water Storage and Use	N/A	-	X	X	-	Immediately	
Current Condition: Assuming the increasing the volume of the off-stream rain catchment pond, there will be enough water storage on the property to meet forbearance requirements during the required period from April 1st to October 31st. At present there are no devices or procedures in place to record water usage associated with the irrigation of cannabis and domestic use.						Prescribed Action: Refer to Cannabis Cultivation Policy, Att. A, Sec. 2, Term 69, 74, 76, 77, 82, and 89 for the full text of requirements related to surface water diversions. Water metering devices, or procedures for the well(s), shall be installed to record all water diverted, pumped, and used water for the irrigation of cannabis and domestic use. Water meter(s) and water supply infrastructure shall be designed/installed in a manner such that water usage for the irrigation of cannabis can be recorded separately from water used for domestic use. Additionally, if there are multiple sources of water, infrastructure/metering device(s) shall be design/installed in a manner that each source of water is recorded separately. Monthly water usage shall be recorded for annual reporting purposes. Also, water storage tank lids shall be appropriately closed to prevent the access of wildlife and, if not currently implemented, water conservation measures such as drip line irrigation, morning or evening watering, and mulch or cover cropping of cultivated top soils shall also be implemented.	



SMP - Mitigation Report

WDID# - 1_12CC407540

Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Liquid Petroleum Products	N/A	-	-	X	-	As required	
<p>Current Condition: All liquid petroleum products (e.g. any size container of any petroleum product) requires secondary containment while not in immediate use and cover from precipitation during the wet season. Adequate quantities of absorbent materials shall also be stored at all locations where these types of materials are used and stored.</p>						<p>Prescribed Action: Any/all liquid petroleum products and their containers shall be stored in secondary containment (e.g. plastic totes or sealed metal boxes) while being stored long term or not in immediate use, wherever these materials are used anywhere on the property. Adequate quantities of absorbent materials (e.g. purpose made materials for oil and fuel spills, cat litter) shall be stored at all locations where these types of materials are used and stored. Should a spill of these materials occur, absorbent materials will be applied immediately and allowed enough time to absorb as much material as possible. Following treatment, absorbent materials applied as well as any contaminated soil will be removed and disposed of appropriately for the spilled material. See attached BMPs: Generator, Fuel, and Oil Management for further details.</p>	
Unique Point	Lat-Long NAD 83	Road Type	Mitigation Planned	Monitor	1600	Treatment Priority	Date Completed
Generators and Gas Powered Pumps	N/A	-	-	X	-	As required	
<p>Current Condition: All liquid petroleum powered generators and pumps require secondary containment, and cover from precipitation during the wet season. Adequate quantities of absorbent materials shall also be stored at all locations where the generators and gas powered pumps are used and stored.</p>						<p>Prescribed Action: Any/all liquid petroleum powered generators or pumps (large or small) shall be stored in secondary containment (e.g. plastic totes, sealed metal boxes, drip pans, pre-fabricated portable containment berms or fabricated and lined containment basins) while being stored long term or not in immediate use, wherever these materials are used anywhere on the property. Adequate quantities of absorbent materials shall be stored at all locations where these types of materials are used and stored. Should a spill of these materials occur, absorbent materials will be applied immediately and allowed enough time to absorb as much material as possible. Following treatment, absorbent materials applied as well as any contaminated soil will be removed and disposed of appropriately for the spilled material. See attached BMPs: Generator, Fuel, and Oil Management for further details.</p>	

Attachments

Photographs

*Photo Dates: Febuary 3rd, June 8th, and July 7th , 2021
See attached Mitigation Report for site details.*



Site 03. Looking west.



Site 03. Looking down channel from the outlet.



Site 03. Looking down-channel from the outlet.



Site 03. Looking up-channel from the inlet.



Site 03. Looking at the outlet.



Site 04. Looking up-channel from the inlet.




Site 04. Looking at the inlet of the channel.



Site 04. Looking at the outlet.



Site 04. Looking down-channel from the outlet. The upgraded culvert will extend to where the man is hanging the blue flagging.



Site 05. Looking up grade to the east towards Site 04.



Site 05. Looking at the inlet to the lower right and up channel to the upper left.



Site 05. Looking at the outlet.



Site 05. Looking down-channel from the outlet.



Site 06. Looking at the inlet.



Site 06. Looking up-channel from the inlet.



Site 06. Looking at the outlet.



Site 06. Looking down-channel from the outlet. The upgraded culvert will outlet approximately where the blue flagging is hanging.



Site 07. Looking up-channel from the inlet.



Site 07. Looking at the outlet.



Site 07. Looking down-channel from the outlet. The upgraded culvert will outlet approximately in the brush to the upper center of the photo.



Site 08. Looking up-channel from the inlet of the culvert.



Site 08. Looking at the inlet.



Site 08. Looking at the outlet of the culvert.



Site 09



Site 10



Site 11. Looking at the outlet of the culvert.



Site 11. Looking at the inlet.



Site 11. Looking up-channel from the inlet.



Photo looking at where the proposed outlet of the watercourse crossing at Site 11 will be approximately.



Site 12. Hydrologic disconnect for Sites 13, 14, and 23.



Looking up grade from Site 12 towards Site 11.



Site 13. Looking up grade at Site 13. A Class III watercourse is diverted down the inside ditch to the right. Re-alignment of this watercourse will consist of a culvert installed diagonally across the road from the grass patch in the upper center-right to the lower left of the photo.



Site 13. Proposed outlet location.



Site 13. Proposed inlet location.



Site 14. Looking down grade at Site 14 with Site 15 further down grade a short distance.



Site 14. Looking at the outlet of the ditch relief culvert.



Site 14. Looking up grade towards Site 13.



Site 15 looking up grade towards Site 14. Hydrologic disconnect for Site 23.



Photo looking up grade at Site 16.



Site 17



Inlet of the watercourse crossing at Site 17.



Outlet of the watercourse crossing at Site 17



Site 19. The watercourse crossing here will be decommissioned and will be re-aligned to its natural channel up grade approximately to where this photo was taken.



Site 19. Approximate location of watercourse re-alignment. A waterbar (Site 18) will be installed further up grade from the re-aligned watercourse.



Inlet of Site 19



Inlet of Site 19 looking up channel.



Site 19. Looking down-channel from the outlet.



Site 19. Looking at the outlet.



Site 19. Photo of the southeastern embankment of G5/G6/G, immediately downstream of the outlet of the watercourse crossing at Site 19. Note vegetation and rotted trees in the upper right. Indicative that this location has been in this condition for many years and was not recently created.



Photo looking north at G5, G6, & G6 from the channel immediately below Site 19.



Site 20.



Site 21. This site was in the 2015 Inspection Report



Looking at the upper extent of Site 21.



Looking at the lower extent of Site 21.



Photo looking southwest at Site 21.



Site 22



Site 23. Looking down grade.



Site 23. The outlet is to the right-center, the inlet is to the left-center out of frame.



Outlet of watercourse crossing at Site 23. The blue flag represents the proposed outlet of culvert upgrade.



Site 23 looking up-channel from the inlet. The inlet is to the right of the photo by the tree.



Site 23. Looking down channel from the outlet. The upgraded culvert will outlet approximately where the blue flag is being hung.



Looking up grade from Site 23 towards Site 14 and 15.



Site 24. Looking down grade.



Site 24. Inlet of the watercourse crossing.



Site 24. Outlet of the watercourse crossing.



Site 25 looking up grade towards Site 24.



Site 26. Inlet of the watercourse crossing.



Site 26. Outlet of the watercourse crossing.



Site 26. Looking down channel from the outlet.



Site 27 looking up grade at Site 26.



Site 34. Looking up grade at Site 34.



Site 35. Looking at the inlet to the lower center-right and the incoming stream channel to the center-left where the rotten stump is located.



Site 35. Looking at the outlet(circled). The culvert upgrade will re-align the watercourse to its original channel, which will require the outlet to be placed in the lower left of the photo.




Site 35. Looking at the down channel and where the culvert outlet will approximately be located.



Site 36



Photo looking up grade at the road down to G1, G2, G3, and G4 from approximately where the photos on page 19 of the 2015 Inspection Report were taken.



Looking down grade from the same location the previous photo was taken, on the road down to G1, G2, G3, and G4.



G1



G2



G3



G4



G5, G6, & G7.



Looking up grade at OG1.



Looking down grade at OG1.



ST3



Photo looking at the Past Cultivation Area located adjacent to Site 31 and P27.

WDID: _____

Date: _____

Monthly Water Tracking



Month	Total Surface Water Diversion	Water input to Storage by Source	Water use by Source
January			
February			
March			
April			
May			
June			
July			
August			
September			
October			
November			
December			

WDID: _____

Date: _____

Monthly Water Tracking



165 South Fortuna Boulevard, Fortuna, CA 95540
707-725-1897 • fax 707-725-0972
tre@timberlandresource.com

BMP: Water Meters



Metering device(s) and/or a procedure (if the water source is completely non-jurisdictional e.g. wells or off-stream pond with no inputs from surface water diversions) to monitor water usage shall be used to record all water used for the irrigation of cannabis and domestic use. No matter the source or means of measurement, per the State General Order, all water used for the irrigation of cannabis shall be recorded daily and recorded water use data shall be kept and maintained for 5 years. Water use may be recorded by meter(s), calculated irrigation times, pump and fill, tank measurements, or any other reasonably accurate means. These records are to be current, maintained, kept on site, and presentable should they be requested. Monthly water usage shall be recorded for annual reporting purposes. For surface water diversions which are used at any point to provide water for the irrigation of cannabis, metering device(s) shall be installed immediately to record water diversion as it is diverted. Records of diverted surface water shall be kept and maintained for 5 years. These records are to be current, maintained, kept on site, and presentable should they be requested.

If surface water is also used for domestic uses, domestic water is to be metered separately from water used for the irrigation of cannabis and is required the same recording and record keeping as water used for cannabis. Water meter(s), or water usage procedures, and water supply infrastructure shall be designed/installed in a manner such that water usage for the irrigation of cannabis can be recorded separately from water used for domestic use. Additionally, if there are multiple diversions of surface water, infrastructure/metering device(s) shall be design/installed in a manner that each source of surface water is recorded separately.

State of California list of approved water meters and other measurement devices

- https://www.waterboards.ca.gov/waterrights/water_issues/programs/diversion_use/wm_vendors.html

Approved water meter provider (top link on the state waterboards list)

- <http://www.watermeters.com/>

Direct link to applicable meters from the www.watermeters.com website

- http://shop.watermeters.com/Cold-Water-Meters_c2.htm
Specifications <http://www.jerman.com/dljmeter.html>
- http://shop.watermeters.com/Polymer-Cold-Water-Meters_c7.htm
Specifications <http://www.jerman.com/plasmeter.html>

DLJ Epoxy Coated Bronze Water Meters

Models DLJ 50, DLJ 75, DLJ 7575, DLJ 100



Description

Operation The DLJ 50, 75, 7575 and 100 are multijet (inferential) impeller meters. The impeller and magnet are the only moving parts in the measuring chamber. The chamber is located in a strainer basket, which allows for high amounts of impurities to be passed through the meter without affecting operation. The impeller movement is transferred by a magnetic coupling to the hermetically sealed register.

Compliance The DLJ line of multijets complies with AWWA C708 and ISO 4064 Class B standards.

Installation The meter must be installed in a clean pipeline, free of any foreign materials. Install the meter with direction of flow as indicated by the arrow cast into the meter body. You can install the meter vertically or horizontally and with the register facing any direction.

Application The DLJ meter is for use only with cold water up to 122 degrees F (50 degrees C)

Construction The meter consists of an epoxy coated bronze maincase with the size and flow direction cast into it, an integral strainer/measuring chamber, a removable dry hermetically sealed register assembly and a secured calibration port (factory tested and set).

Characteristics	Specifications			
	DLJ 50 5/8" x 1/2"	DLJ 75 5/8" x 3/4"	DLJ 7575 3/4" x 3/4"	DLJ100 1"
Flow Rating (gpm)	20	20	30	50
Continuous Flow (gpm)	15	20	25	30
Normal Flow Range (gpm)	1 - 20	1 - 20	2-30	3 - 50
Low Flow (gpm)	1/4	1/4	1/4	1/2
Maximum Pressure (psi)	150	150	150	150
Maximum Temperature (°F)	122	122	122	122
Sweep Hand Registers (Gallons)	10	10	10	10
Register Capacity (Millions of Gallons)	10	10	10	10

watermeters.com

*the first and still the best online source
for water meters*

DLJ Meter



www.watermeters.com

DLJ Epoxy Coated Bronze Water Meters

Models DLJ 50, DLJ 75, DLJ 7575, DLJ 100

Direct Read Register The register is contained in a hermetically sealed nylon casing with a 5mm tempered glass lens. The totalizer wheels are large and easy to read and the sweep hand is designed not to interfere with the odometer reading. The register's circumference shows individual gallons down to increments of tenths of gallons, for precision reading. The large red spinning trickle indicator is excellent for leak detection. Each register clearly shows its applicable meter size.




Pulse Output The DLJ line is available with a dry contact reed switch pulse output. This requires external DC power, 4 watts, 30VDC maximum. Contact closure is 1 pulse per gallon.



Maintenance The register assembly is easily removable and replaceable if needed. The integral strainer on the measuring assembly prevents foreign debris damage and can be removed and flushed clean if merited.


Magnetic Drive The magnetic drive design facilitates coupling between the measuring chamber and the register assembly. The coupling will remain unless the flow rates are higher than recommended

Head Loss Curves - 1/2", 3/4", 1"



Connections Meter casing spuds conform to ANSI B2.1 and have external straight threads (referred to as non-tapered meter threading). All meters come with full bronze meter coupling sets bringing you to Male NPT.

Accuracy Curves - 1/2", 3/4", 1"



Specifications	Size			
	DLJ 50 5/8" x 1/2"	DLJ 75 5/8" x 3/4"	DLJ 7575 3/4" x 3/4"	DLJ100 1"
Length	7 1/2"	7 1/2"	9"	10 3/4"
Height	4 1/8"	4 1/8"	4 1/8"	3 7/8"
Width	3 3/4"	3 3/4"	3 3/4"	4 1/8"
Weight (lbs.)	4	4	5	5

Daniel L. Jerman Co.

275 Railroad Place
 Hackensack, NJ 07601
 Phone 800.654.3733
 Fax 201.487.3953
 International Phone 201.487.7444
 email: sales@watermeters.com

DLJ Meter



BMP: Generator, Fuel, and Oil Management

All bulk fuel storage or petroleum products, any/all future petroleum products and other liquid chemicals, including but not limited to diesel, biodiesel, gasoline, and oils shall be stored so as to prevent their spillage, discharge, or seepage into receiving waters. Storage tanks and containers shall be of suitable material and construction to be compatible with the substance(s) stored and conditions of storage such as pressure and temperature. Above ground storage tanks and containers shall be provided with a secondary means of containment for the entire capacity of the largest single container and sufficient cover shall be provided to prevent any/all precipitation from entering said secondary containment vessel.

If the volume of a fuel container is greater than 1,320 gallons, a Spill Prevention, Control, and Countermeasures (SPCC) plan will be required for the use the fuel tank.

On-site storage of petroleum products, or other fuels used for commercial activities may require registration as hazardous materials through the California Environmental Reporting System (CERS). Additionally, the waste oil generated from commercial activities (generators) and their used oil filters are considered hazardous waste and requires additional reporting. The discharger is advised to contact local agencies to find out if such reporting is applicable to currently operations

Used motor oil is recommended to be stored in sealed containers that the oil was originally packaged in, e.g. sealed buckets/quart or gallon jugs, or other sealed containers designed to store motor oil. Stored used oil is recommended to be regularly disposed of at hazardous waste disposal sites. Used oil filters are also recommended to be stored in sealed containers, e.g. sealed plastic totes/buckets, for later disposal at a hazardous waste disposal site. These storage containers are recommended to be stored in structures where they are protected from precipitation.

Further information regarding the State of California's requirements for the managing of Used Oil and Oil Filters can be found by entering the links below or searching the corresponding titles to the links.

California Department of Toxic Substances Control - Used Oil Generator Requirements

- <https://www.dtsc.ca.gov/InformationResources/upload/RAG-UsedOilforGenerators.pdf>

Department of Toxic Substances Control - Managing Used Oil Filters for Generator

- https://www.dtsc.ca.gov/InformationResources/upload/RAG_Used-Oil-Filters_Generators1.pdf

BMP: Generator, Fuel, and Oil Management (Generators and Pumps)

All generators and petroleum powered pumps shall have spill trays or secondary containment placed underneath them when using, fueling, or changing oil on them to prevent the potential for leeching, seepage or spillage of petroleum products. All spill trays and containment structures require cover from precipitation if used or left out over the winter period. All generators and petroleum powered pump locations shall have spill cleanup kits on hand.

Pre-fabricated secondary containment structures and spill trays can be purchased online or from local wholesalers of petroleum products. As an alternative to pre-fabricated secondary containment structures, structures can be constructed from wooden, cinderblock, concrete, or metal frames lined with PVC liners, e.g. pond liner/water bladder material, as long as the containment is fully sealed and constructed in a similar manner to examples of pre-fabricated containment structures found below. Ensure that diked areas are sufficiently impervious to contain discharged chemicals. All containment structures require cover from precipitation to prevent the containment from filling with water. Secondary containment for fuel tanks shall not be constructed.

As an alternative to pre-fabricated spill kits, kits can consist of sealed trashcans or buckets with industrial absorbent material (e.g. cat litter) and shovels, placed nearby any location where generators, pumps, or other petroleum products or chemicals are used.

Examples of industry standard pre-fabricated spill containment and clean-up kits can be found following or entering the links below. Pre-fabricated spill containment and clean-up kits can be purchased online, from Renner Petroleum, or other similar industry providers.

Ultratech Spill Containment

- <http://www.spillcontainment.com/categories/spill-containment/>

New Pig Portable and Collapsible Spill Containment

- <https://www.newpig.com/collapsible-berms/c/5142?show=All>

BMP: Generator, Fuel, and Oil Management



Example of a small, portable, and compact containment berm.



Example of a portable utility spill tray.

BMP: Generator, Fuel, and Oil Management



Example of secondary containment for a fuel tank. This container requires cover from precipitation.



Example of spill pallets for unused or used oil drums and other petroleum products.

BMP: Winterization and Interim Treatments for Erosion Control

- **Roads**
 - Existing or newly installed road surface drainage structures such as water bars, rolling dips, ditch relief culverts, and intentionally in/out-sloped segments of road shall be maintained to ensure continued function of capturing and draining surface runoff.
 - Hand tool kick-outs (lead out ditch) for existing wheel rut, surface run-off confinement.
 - Temporary waterbar/cross-wattles installed on road/trail sections of concentrating surface runoff.
 - Clean existing ditch relief culvert inlets, outlets, and contributing ditch lines of current and potential blockage debris by hand.
 - Hand place energy dissipating rock/small woody debris at ditch relief culvert outlets where erosion is occurring.
 - Wattles/straw bales placed at road runoff delivery sites.
 - Touch-up with hand tools of existing surface drainage structures (kick-outs, rolling dips, and waterbars).
 - Seed and straw un-used, or to be abandoned, road surfaces where erosion is occurring.
 - Frequent use of un-surfaced roads should be avoided, particularly when road surfaces are soft/saturated.

- **Crossings**
 - Clean inlets, outlets, and channels above of current and potential blockage debris by hand.
 - Hand place energy dissipating rock/small woody debris at ditch relief culvert outlets.
 - Hand placement of rock armor around culvert inlets.
 - Install staked wattles along the outboard road edge of out-sloped watercourse crossings where direct delivery of road surface runoff is occurring.
 - Hand placement of rock on crossing fill faces where erosion is/may occur as a result of poor crossing construction.

- **Cultivation Areas**
 - Use hand tools to capture cultivation related soils that are not contained (soil from post-harvest plant removal, soil/planter removal, general spillage).
 - Treat beds, pots, new soil storage piles, spent soil piles, and soil disposal piles with cover crops for soil stability and potentially nitrogen fixing/soil amendment.
 - Bagged potting soil should be covered.
 - Install staked wattles or an earthen berm around cultivation soils piles prior to the winter period, annually.
 - Any soil amendment, fertilizer, herbicide, or pesticide that is not 100% sealed should be stored under cover.
 - Cultivation sites with poor or concentrating drainage can have wattles or bales installed prior to winter to help prevent sediment and nutrients from leaving the site.
 - Plastic netting shall be disposed of or stored where it is inaccessible to wildlife.
 - Tarps/dep covers shall be stored so they cannot be blown away.
 - General waste from growing season gathered up and disposed of.
 - Exposed soil surfaces in the cultivation area, as well as graded fill slopes should be seeded, strawed, mulched, jute netted as needed.

- **General Areas**
 - Remove all refuse prior to leaving property for the season.
 - Back fill pit toilets to be abandoned.

BMP: General Recommendations

- **Fertilizers, soil amendments, and pesticides**
 - Fertilizer, soil amendments, and pesticide use it to be recorded in such a manner that cumulative annual totals are recorded for annual reporting.
 - Store in-use fertilizers in a securable storage container, such as a tote or deck box, adjacent to the mixing tanks.

- **Petroleum products and hazardous materials**
 - Utilize spill trays/containment structures and cover over the containment when using, fueling, changing oil on portable generators or petroleum powered water pumps to prevent the potential for leeching, seepage or spillage of petroleum products.
 - It is recommended that all petroleum products and other chemicals are registered with the California Environmental Reporting System (CERS) to satisfy future licensing requirements.

- **Water storage and Use**
 - Water use shall be designed and metered such that water used for the irrigation of cannabis will be recorded separately from domestic use. Water use for the irrigation of cannabis is to be recorded monthly for annual reporting.
 - Ensure lids are secured on all water storage tanks to prevent wildlife from becoming entrapped within the tank.
 - Install float valves, or implement another equivalent system, on all applicable water storage and transfer tanks to prevent unnecessary water diversion and the overflowing of water tanks.

BMP: General Operations BMPs

- If operations require moving of equipment across a flowing stream, such operations shall be conducted without causing a prolonged visible increase in stream turbidity. For repeated crossings, the operator shall install a bridge, culvert, or rock-lined crossing.
- During construction in flowing water, which can transport sediment downstream, the flow shall be diverted around the work area by pipe, pumping, temporary diversion channel or other suitable means. When any dam or artificial obstruction is being constructed, maintained, or placed in operation, sufficient water shall at all times be allowed to pass downstream to maintain fish life below the dam. Equipment may be operated in the channel of flowing live streams only as necessary to construct the described construction.
- Disturbance or removal of vegetation shall not exceed the minimum necessary to complete operations. The disturbed portion of any stream channel shall be restored to as near their original condition as possible. Restoration shall include the mulching of stripped or exposed dirt areas at crossing sites prior to the end of the work period.
- Structures and associated materials not designed to withstand high seasonal flow shall be removed to areas above the high-water mark before such flows occur.
- No debris, soil, silt, sand, bark, slash, sawdust, rubbish, cement or concrete washing, oil or petroleum products, or other organic or earthen material from any logging, construction, or associated activity of whatever nature shall be allowed to enter into or be placed where it may be washed by rainfall or runoff into waters of the State. When operations are completed, any excess materials or debris shall be removed from the work area. No rubbish shall be deposited within 150 feet of the high-water mark of any stream.


BMP: General Erosion Control

- Timing for soil stabilization measures within the 100 feet of a watercourse or lake: For areas disturbed from May 1 through October 15, treatment shall be completed prior to the start of any rain that causes overland flow across or along the disturbed surface. For areas disturbed from October 16 through April 30, treatment shall be completed prior to any day for which a chance of rain of 30 percent or greater is forecast by the National Weather Service or within 10 days, whichever is earlier.
- Within 100 feet of a watercourse or lake, the traveled surface of logging roads shall be treated to prevent waterborne transport of sediment and concentration of runoff that results from operations. Treatment may consist of, but not limited to, rocking, out sloping, rolling dips, cross drains, water bars, slope stabilization measures, or other practices appropriate to site-specific conditions.
- The treatment for other disturbed areas within 100 feet of a watercourse or lake, including: (A) areas exceeding 100 contiguous square feet where operations have exposed bare soil, (B) approaches to road watercourse crossings out to 100 feet or the nearest drainage facility, whichever is farthest, (C) road cut banks and fills, and (D) any other area of disturbed soil that threatens to discharge sediment into waters in amounts deleterious to the quality and beneficial uses of water, shall be grass seeded and mulched with straw or fine slash. Grass seed shall be applied at a rate exceeding 100 pounds per acre. Straw mulch shall be applied in amounts sufficient to provide at least 2- 4-inch depth of straw with minimum 90% coverage. Slash may be substituted for straw mulch provided the depth, texture, and ground contact are equivalent to at least 2 – 4 inches of straw mulch. Any treated area that has been subject to reuse or has less than 90% surface cover shall be treated again prior to the end of operations.
- Within 100 feet of a watercourse or lake, where the undisturbed natural ground cover cannot effectively protect beneficial uses of water from operations, the ground shall be treated with slope stabilization measures described in #3 above per timing described in #1 above.
- Side cast or fill material extending more than 20 feet in slope distance from the outside edge of a landing which has access to a watercourse or lake shall be treated with slope stabilization measures described in #3 above. Timing shall occur per #1 above unless outside 100 feet of a watercourse or lake, in which completion date is October 15.
- All roads shall have drainage and/or drainage collection and storage facilities installed as soon as practical following operations and prior to either (1) the start of any rain which causes overland flow across or along the disturbed surface within 100 feet of a watercourse or lake protection, or (2) any day with a National Weather Service forecast of a chance of rain of 30 percent or more, a flash flood warning, or a flash flood watch.

BMP: General Erosion Control (Cont.)

- Erosion control and sediment detention devices and materials shall be incorporated into the cleanup/restoration work design and installed prior to the end of project work and before the beginning of the rainy season. Any continuing, approved project work conducted after October 15 shall have erosion control works completed up-to-date and daily.
- Erosion control materials shall be, at minimum, stored on-site at all times during approved project work between May 1 and October 15.
- Approved project work within the 5-year flood plain shall not begin until all temporary erosion controls (straw bales or silt fences that are effectively keyed-in) are installed downslope of cleanup/restoration activities.
- Non-invasive, non-persistent grass species (e.g., barley grass) may be used for their temporary erosion control benefits to stabilize disturbed slopes and prevent exposure of disturbed soils to rainfall.
- Upon work completion, all exposed soil present in and around the cleanup/restoration sites shall be stabilized within 7 days.
- Soils exposed by cleanup/restoration operations shall be seeded and mulched to prevent sediment runoff and transport.
- Straw Wattles (if used) shall be installed with 18 or 24-inch wood stakes at four feet on center. The ends of adjacent straw wattles shall be abutted to each other snugly or overlapped by six inches. Wattles shall be installed so that the wattle is in firm contact with the ground surface.

BMP: General Erosion Control (Cont.)




STRAW WATTLE NOTES:

1. STRAW WATTLES SHALL BE INSTALLED WITH 18 OR 24 INCH WOOD STAKES AT FOUR FEET ON CENTER. THE ENDS OF ADJACENT STRAW WATTLES SHALL BE ABUTTED TO EACH OTHER SNUGLY OR OVERLAPPED BY SIX INCHES.
2. STRAW ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE ROLL IN A TRENCH, 3"-5" DEEP. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND THE ROLL.

STRAW WATTLE INSTALLATION DETAIL

NTS



SILT FENCE NOTES:

1. THE CONTRACTOR SHALL INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT.
2. CONTRACTOR SHALL REMOVE SEDIMENT AS NECESSARY. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND IN AN AREA THAT CAN BE PERMANENTLY STABILIZED.
3. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.

SILT FENCE DETAILS


NTS

BMP: General Erosion Control (Cont.)




BMP: General Erosion Control (Cont.)

SPREAD THE STRAW



ANCHOR THE STRAW




- A. LAY BIRD CONTROL NETTING OR SIMILAR MATTING IN STRIPS DOWN THE SLOPE OVER THE STRAW. BURY UPPER END IN 6-8 INCH DEEP AND WIDE TRENCH.. MOST NETTING COMES IN 14 TO 17 FT. WIDE ROLLS.
- B. SECURE THE UPPER END WITH STAKES EVERY 2 FEET.
- C. OVERLAP SEAMS ON EACH SIDE 4-5 INCHES.
- D. SECURE SEAMS WITH STAKES EVERY 5 FEET.
- E. STAKE DOWN THE CENTER EVERY 5 FEET.

- F. STAKE MIDDLES TO CREATE DIAMOND PATTERN THAT PROVIDES STAKES SPACED 4-5 FEET APART.
- G. USE POINTED 1X2 INCH STAKES 8 TO 9 INCHES LONG. LEAVE 1 TO 2 INCH TOP ABOVE NETTING, OR USE "U" SHAPED METAL PINS AT LEAST 9 INCHES LONG.

NOTE: WHEN JOINING TWO STRIPS, OVERLAP UPPER STRIP 3 FEET OVER LOWER STRIP AND SECURE WITH STAKES EVERY 2 FEET LIKE IN "B" ABOVE

BMP: General Erosion Control (Cont.)



Notes:

1. Slope surface shall be smooth before placement for proper soil contact.
2. Stapling pattern as per manufacturer's recommendations.
3. Do not stretch blankets/matting tight - allow the rolls to mold to any irregularities.
4. For slopes less than 3H:1V, rolls may be placed in horizontal strips.
5. If there is a berm at the top of the slope, anchor upslope of the berm.
6. Lime, fertilize, and seed before installation. Planting of shrubs, trees, etc. should occur after installation.

NOT TO SCALE



DEPARTMENT OF
ECOLOGY
State of Washington


Slope Installation

Revised June 2016

Please see <http://www.ecy.wa.gov/copyright.html> for copyright notice including permissions, limitation of liability, and disclaimer.

BMP: General Erosion Control (Cont.)

Installation of a geosynthetic mat - Enkamat



BMP: General Erosion Control (Cont.)

Erosion Control Matting & Silt Fencing



Jute netting & Straw-wattles



BMP: General Erosion Control (Cont.)


TABLE 34. Guidelines for erosion and sediment control application

Timing of application	Technique	Portion of road and construction area treated
Erosion control during construction	Hydromulching, hydroseeding	Road fill slopes, cut slopes, bare soil areas
	Dry seeding	Road fill slopes, cut slopes, bare soil areas
	Wood chip, straw, Excelsior or tackified mulch	Road fill slopes, cut slopes, bare soil areas
	Straw wattles	Road fill slopes and cut slopes
	Gravel surfacing	Road, landing and turnout surfaces
	Dust palliative	Road surfaces
Sediment control during construction	Minimize disturbance (soil and vegetation)	All areas peripheral to construction
	Sediment basin	Roadside ditches, turnouts and small stream crossings
	Sediment traps (e.g., silt fences, straw bales barriers, woody debris barriers)	Road fill slopes, cutbanks, bare soil areas and ditches
	Straw bale dams	Ditches and small streams
	Sumps and water pumps	Stream channels and stream crossings
	Streamflow diversions (e.g., temporary culverts, flex pipe, etc.)	Stream channels and stream crossings
Permanent erosion control	Surface diversion and dispersion devices (pipes, ditches, etc.)	All disturbed bare soil areas
	Road shaping	Road and landing surfaces
	Gravel surfacing	Road, landing and turnout surfaces
	Bituminous or asphalt surfacing	Road surface
	Rolling dips	Road surface
	Ditch relief culverts	Roadbed and road fill
	Downspouts and berm drains	Road fill slopes
	Waterbars	Road and landing surfaces
	Berms	Road surface and roadside areas
	Ditches	Road and landing surfaces
	Riprap	Road fill slopes, stream crossing fills, cutbanks, stream and lake banks
	Soil bioengineering	Road fill slopes, cut slopes, stream crossings, streambanks
Tree planting	Road fill slopes, cutbanks, bare soil areas, stream crossings, streambanks	

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Permanent Culvert Crossing

- New culvert installations shall be sized to accommodate flows associated with a 100-year storm event.
- If the new culvert is replacing a poorly installed old culvert, the crossing may need to be abandoned to the following standard:
 - When fills are removed they shall be excavated to form a channel that is as close as feasible to natural watercourse grade and orientation, and that is wider than the natural channel.
 - Excavated banks shall be laid back to a 2:1 (50%) or natural slope.
- New culverts shall be placed at stream gradient, or have downspouts, or have energy dissipaters at outfall.
 - Align culverts with the natural stream channel orientation to ensure proper function, prevent bank erosion, and minimize debris plugging. See Figure 97 below.
 - Place culverts at the base of the fill and at the grade of the original streambed or install a downspout past the base of the fill. Downspouts should only be installed if there are no other options.
 - Culverts should be set slightly below the original stream grade so that the water drops several inches as it enters the pipe.
 - Culvert beds should be composed of rock-free soil or gravel, evenly distributed under the length of the pipe.
 - Compact the base and sidewall material before placing the pipe in its bed.
 - Lay the pipe on a well-compacted base. Poor basal compaction will cause settling or deflection in the pipe and can result in separation at a coupling or rupture in the pipe wall.
 - Backfill material should be free of rocks, limbs, or other debris that could dent or puncture the pipe or allow water to seep around the pipe.
 - Cover one end of the culvert pipe, then the other end. Once the ends are secure, cover the center.
 - Tamp and compact backfill material throughout the entire process, using water as necessary for compaction.
 - Backfill compacting will be done in 0.5 – 1.0 foot lifts until 1/3 of the diameter of the culvert has been covered.
 - Push layers of fill over the crossing to achieve the final design road grade, road fill above the culvert should be no less than one-third to one-half the culvert diameter at any point on the drivable surface.
- Critical dips shall be installed on culvert crossings to eliminate diversion potential. Refer to Figure 84 below.
- Road approaches to crossings shall be treated out to the first drainage structure (i.e. waterbar, rolling dip, or hydrologic divide) to prevent transport of sediment.
- Road surfaces and ditches shall be disconnected from streams and stream crossings to the greatest extent feasible. Ditches and road surfaces that cannot be feasibly disconnected from streams or stream crossings shall be treated to reduce sediment transport to streams.
- If downspouts are used, they shall be secured to the culvert outlet and shall be secure on fill slopes.
- Culverts shall be long enough so that road fill does not extend or slough past the culvert ends.
- Inlet of culverts, and associate fill, shall be protected with appropriate measures that extend at least as high as the top of the culvert.
- Outlet of culverts shall be armored with rock if road fill sloughing into channel can occur.
- Armor inlets and outlets with rock, or mulch and seed with grass as needed (not all stream crossings need to be armored).
- Where debris loads could endanger the crossing, a debris catchment structure shall be constructed upstream of the culvert inlet.
- Bank and channel armoring may occur, when appropriate, to provide channel and bank stabilization.



HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

FIGURE 97. Culvert alignment should be in relation to the stream and not the road. It is important that the stream enters and leaves the culvert in a relatively straight horizontal alignment so streamflow does not have to turn to enter the inlet or discharge into a bank as it exits. This figure shows a redesigned culvert installation that replaces the bending alignment that previously existed. Channel turns at the inlet increase plugging potential because wood going through the turn will not align with the inlet. Similarly, channel turns at the inlet and outlet are often accompanied by scour against the channel banks (Wisconsin Transportation Information Center, 2004).

BMP: Permanent Culvert Crossing Design (Critical Dip and Hydrologic Disconnect Placement)









FIGURE 84. Critical dips or dipped crossing fills should be centered near a stream crossing's down-road hinge line, not over the centerline of the crossing where overtopping could cause washout or severe erosion of the fill. If the stream crossing culvert (B) plugs, water will pond behind the fill until reaching the critical dip or low point in the crossing (C) and flowing back down into the natural stream channel. The down-road ditch must be plugged to prevent streamflow from diverting down the ditch line. For extra protection in this sketch, riprap armor has been placed at the critical dip outfall and extending downslope to the stream channel. This is only required or suggested on stream crossings where the culvert is highly likely to plug and the crossing fill overtopped. The dip at the hinge line is usually sufficient to limit erosional damage during an overtopping event. Road surface and ditch runoff is disconnected from the stream crossing by installing a rolling dip and ditch relief culvert just up-road from the crossing (A) (Keller and Sherar, 2003).

BMP: Permanent Culvert Crossing Design (Critical Dip)**Typical Critical Dip Design for Stream Crossings with Diversion Potential****Critical Dip Construction:**

1. Critical dip will be constructed on the lower side of crossing.
2. Critical dip will extend from the cutbank to the outside edge of the road surface. Be sure to fill inboard ditch, if present.
3. Critical dip will have a reverse grade (A) from cutbank to outside edge of road to ensure flow will not divert outside of crossing.
4. The rise in the reverse grade will be carried for about 10 to 20 feet and then return to original slope.
5. The transition from axis of bottom, through rising grade, to falling grade, will be in the road distance of at least 15 to 30 feet.
6. Critical dips are usually built perpendicular to the road surface to ensure that flow is directed back into the stream channel.

BMP: Permanent Culvert Crossing Design (Cofferdam Construction and Use Specifications)



BMP: Permanent Culvert Crossing Design **(Cofferdam Construction and Use Specifications)**



FIGURE 197. Flex pipe stream diversion around a road construction site. The inlet to this 6 inch diameter flex pipe inlet collects clear streamflow from a retention dam above the project site and gravity feeds it around the project area and back into the natural channel downstream from construction work (see photo).



FIGURE 198. Sand bag retention dam on this small stream was used to pond streamflow so it could be pumped around a culvert installation site. The green intake hose is screened to keep out rocks and debris while the red pump hose extends several hundred feet around the project work area.



FIGURE 199. For larger streams, pump trucks, large pumps or multiple small pumps can be used to pump streamflow around project work sites. Here, a pump truck is used to temporarily divert flow in a fish bearing stream where dual culverts are being replaced with a railcar bridge. Young fish were removed from this fish bearing stream before project work started.

BMP: Permanent Culvert Crossing Design (Culvert Orientation)







FIGURE 155. Proper culvert installation involves correct culvert orientation, setting the pipe slightly below the bed of the original stream, and backfilling and compacting the fill as it is placed over the culvert. Installing the inlet too low in the stream (A) can lead to culvert plugging, yet if set too high (B) flow can undercut the inlet. If the culvert is placed too high in the fill (C), flow at the outfall will erode the fill. Placed correctly (D), the culvert is set slightly below the original stream grade and protected with armor at the inlet and outlet. Culverts installed in fish-bearing stream channels must be inset into the streambed sufficiently (>25% embedded) to have a natural gravel bottom throughout the culvert (Modified from: MDSL, 1991).

BMP: Permanent Culvert Crossing Design (Inlet and Outlet Armoring)



Riprap installed to protect the inlet and outlet of a stream crossing culvert from erosion or for energy dissipation should be keyed into the natural channel bed and banks to an approximate depth of about 1.5x the maximum rock thickness. Riprap should be placed at least up to the top of the culvert at both the inlet and outlet to protect them from splash erosion and to trap any sediment eroded from the newly constructed fill slope above.

BMP: Permanent Culvert Crossing Design (Inlet and Outlet Armoring) Cont.

- Inlets of culverts and associate fills shall be protected with rock armoring that extends at least as high as the top of the culvert.
- Outlets of culverts shall be provided a rock energy dissipater at the outfall of the culvert.
- Outlets of culverts and associate fills shall be protected with rock armoring that extends at least as high as the top of the culvert if road fill sloughing into channel can occur.
- Prior to inlet and outlet rocking, the inlet and outlets shall be prepared. Preparation will include removal of vegetation and stored materials from the inlet and outlet.
- Inlets may require construction of an inlet basin.
- Slopes at the outlet should be shaped to a 2:1 or natural slope prior to placing rock armor.
- Rock used at culvert inlets and outlets should be a matrix of various sized rocks and rip-rap that range from a 3" dia. to a 2' dia.
- The largest rocks should be places at the base of the culvert or fill. Incrementally smaller rocks shall be placed over the larger rocks at the armoring extend up the slope. Voids and spaces shall be back filled with smaller gravels and rocks.




FIGURE 107A. Riprap armor at culvert outlet (Modified from: Keller et al., 2011).




FIGURE 107B. Riprap armor at culvert inlet (Keller and Sheraz, 2003).

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Stream Bank Armoring (Riprap)



- Riprap should be installed on top of geotextile fabric or a clean mixture of coarse gravel and sand.
- The riprap should be keyed into the streambed and extend below the maximum expected scour depth with an adequately sized key base width at a thickness of a minimum of 2x the median (D50) rock diameter with the largest stone sizes placed at the base of the riprap structure.
- The armor should be set into the streambank so it does not significantly protrude into, or constrict, the natural channel, or otherwise reduce channel capacity.
- The riprap should extend along the length of unstable or over steepened bank and up the bank sufficiently to encompass the existing bank instability and/or design flood elevations.

BMP: Rocked Ford

- Rocked fords are drainage structures designed to carry watercourses across roads where culvert crossings are not feasible or un-necessary.
- In channel constructed fords shall be of appropriate material that shall withstand erosion by expected velocities and placed in a U-shaped channel to create a drivable crossing.
 - The road shall dip into and out of the rocked ford to minimize diversion potential. Construct a broad rolling dip across the roadbed, centered at the crossing, which is large enough to contain the expected 100-yr flood discharge while preventing flood flow from diverting down the road or around the rock armor.
- The road surface at the ford shall be constructed with clean rock. The rock shall be applied to a minimum depth of 6 inches.
 - A range of interlocking rock armor sizes should be selected and sized so that peak flows will not pluck or transport the armor off the roadbed or the sloping fill face of the armored fill.
- The ford's outlet shall be rock armored to resist downcutting and erosion.
 - *Excavate the keyway and armored area* - Excavate a two to three-foot-deep "bed" into the dipped road surface and adjacent fillslope (to place the rock in) that extends from approximately the middle of the road, across the outer half of the road, and down the outboard road fill to where the base of the fill meets the natural channel. At the base of the fill, excavate a keyway trench extending across the channel bed.
 - *Armor the basal keyway* - Put aside the largest rock armoring to create the buttresses. Use the largest rock armor to fill the basal trench and create a buttress at the base of the fill. This should have a "U" shape to it and it will define the outlet where flow leaves the armored fill and enters the natural channel.
 - *Armor the fill* - Backfill the fill face with the remaining rock armor making sure the final armor is unsorted and well placed, the armor is two coarse-rock layers in thickness, and the armored area on the fill face also has a "U" shape that will accommodate the largest expected flow.
 - *Armor the top of the fill* - Install a second trenched buttress for large rock at the break-in-slope between the outboard road edge and the top of the fill face.
- If water is expected during the time of use, an adequately sized pipe shall be installed to handle the flow if present (min. 6 inch).
 - The pipe shall be laid over the rocked ford surface.
 - The inlet should be at grade with the upstream flow.
 - The outlet shall drain onto the outlet armoring of the rocked ford.
 - A layer of clean rock/gravel shall be installed over the pipe to establish the running surface of the truck road.
 - Following use, the temporary pipe shall be removed and the placed rock/gravel shall be graded out of the ford and used on the approaches.
 - No significant alteration to the bed and bank of the stream shall occur.
- Road approaches to rocked fords shall be rock surfaced out to the first drainage structure (i.e. waterbar) or hydrologic divide to prevent transport of sediment using rock.
- Bank and channel armoring may occur when appropriate to provide channel and bank stabilization.
- Road approach rock and rock ford armoring shall be reapplied following use as needed to maintain a permanent crossing.

BMP: Rocked Ford (Cont.)

FORD: A large dip is graded into the road at the axis of the stream channel. The outside fill face is dished out to form a spillway with large rock. On large watercourses, rock is keyed several feet into firm native soils. The road surface is rocked with 6" of minus rock .



BMP: Armored Ford [Fill]

- Armored fords are drainage structures designed to carry watercourses across roads.
- Armored fords shall have a U-shaped channel to create a drivable crossing.
 - The road shall dip into and out of the armored ford to minimize diversion potential. Construct a broad rolling dip across the roadbed, centered at the crossing, which is large enough to contain the expected 100-yr flood discharge while preventing flood flow from diverting down the road or around the rock armor.
- The road surface at the armored ford shall utilize native soils.
- The ford's inlet shall be rock armored if a threat of head cutting exists.
 - *Excavate the keyway* - Excavate a one to three-foot-deep "bed" into the inboard edge of the road
 - *Armor the basal keyway* - place various sized rock in the constructed keyway to prevent head cutting. Use the largest rock armor to fill the keyway trench and create a buttress along the inboard edge of the road. This should have a "U" shape to it and it will define the inlet where flow leaves the natural channel and enters the road.
- The ford's outlet shall be rock armored to resist downcutting and erosion.
 - *Excavate the keyway and armored area* - Excavate a two to three-foot-deep "bed" into the dipped road surface and adjacent fillslope (to place the rock in) that extends from approximately the middle of the road, across the outer half of the road, and down the outboard road fill to where the base of the fill meets the natural channel. At the base of the fill, excavate a keyway trench extending across the channel bed.
 - *Armor the basal keyway* - Put aside the largest rock armoring to create the buttresses. Use the largest rock armor to fill the basal trench and create a buttress at the base of the fill. This should have a "U" shape to it and it will define the outlet where flow leaves the armored fill and enters the natural channel.
 - *Armor the fill* - Backfill the fill face with the remaining rock armor making sure the final armor is unsorted and well placed, the armor is two coarse-rock layers in thickness, and the armored area on the fill face also has a "U" shape that will accommodate the largest expected flow.
 - *Armor the top of the fill* - Install a second trenched buttress for large rock at the break-in-slope between the outboard road edge and the top of the fill face.
- If water is expected during the time of use, an adequately sized pipe shall be installed to handle the flow if present (min. 6 inch).
 - The pipe shall be laid over the armored ford surface.
 - The inlet should be at grade with the upstream flow.
 - The outlet shall drain onto the outlet armoring of the rock armored ford.
 - A layer of clean native shall be installed over the pipe to establish the running surface of the truck road.
 - Following use, the temporary pipe shall be removed and the placed native soil shall be removed and drifted along the approaches.
 - No significant alteration to the bed and bank of the stream shall occur.
- Road approaches to armored fords shall be treated with seed and straw mulch out to the first drainage structure (i.e. waterbar) or hydrologic divide to prevent transport of sediment pursuant to Item 18, Section II.
- Bank and channel armoring may occur when appropriate to provide channel and bank stabilization.
- Armored ford armoring shall be reapplied following use as needed to maintain a permanent crossing.


BMP: Armored Ford [Fill] (Cont.)

FIGURE 120. *This armored fill crossing of a steep, ephemeral stream was constructed to provide a low maintenance crossing. The crossing has been deeply dipped to reduce the volume of road fill and to eliminate the potential for stream diversion. The fill slope has been heavily armored through the axis of the crossing to contain flood flows and prevent down-cutting. Armored fills cannot be used on fish bearing streams.*

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Armored Ford [Fill] (Cont.)



FIGURE 121D. Well graded rock armor is then backfilled into the structure and spread across the breadth of the U-shaped stream crossing, and about one-third the way up the roadbed, so that streamflow will only flow over or come in contact with resistant armor material. The armor must be spread and compacted across the design width of the expected flood flow channel width so peak flows will not flank the armored structure.




FIGURE 121E. Two weeks after this armored fill was constructed, a storm flow event occurred and the structure maintained its function and integrity. The road approaches had not yet been compacted or surfaced with road rock.




FIGURE 121F. The same armored fill as it appeared after the first winter flood flows. No maintenance was required to reopen the road. It is also clear that no stream diversion is possible at this stream crossing site, and the volume of fill within the crossing has been reduced to the minimum amount needed to maintain a relatively smooth driving surface on this low volume road.

BMP: Vented Ford

Vented Ford



Dip area to accommodate a culvert sized for 100-year flow (minimum dimensions given below).



LIP

- Use smaller rock at lip of ford.
- Fill voids with smaller rock to prevent piping around the larger rock.



BMP: Crossing Decommissioning

- Excavate and removing all fill materials placed in the stream channel when the crossing was originally built.
- Excavated banks shall be laid back to a 2:1 (50%) or natural slope to prevent slumping and soil movement.
- Fill material should be excavated to recreate the original channel grade (slope) and orientation.
- All bare soils should then be mulched, seeded, and planted to minimize erosion until vegetation can protect the soil surface.
- The approaching road segments shall be cross-road(waterbars) drained to prevent road runoff from discharging across the freshly excavated channel sideslopes.
- When fills are removed, they shall be excavated to form a channel that is as close as feasible to natural watercourse grade and orientation.
- The excavated channel bed should be as wide, or slightly wider than, the original watercourse channel.
 - This can be better determined by observing the channel width of the watercourse up slope of crossing to be removed at a point in which the crossing or any other disturbance has not affected the natural channel slope and width.
- Temporary crossings shall be removed by November 15.
 - Any temporary culvert crossing left in after October 15 or installed between October 15 and May 1, shall be sized to accommodate the estimated 100-year flow.
- In certain situations, bank and channel rock and woody debris armoring may be appropriate to provide channel and bank stabilization.




FIGURE 263. On roads that are to be closed (decommissioned), all stream crossing culverts and fills should be removed. Stream crossing excavations are best performed using an excavator. The original channel should be excavated and exhumed down to the former streambed, with a channel width equal or greater than the natural channel above and below the crossing. Sideslopes should be laid back to a stable angle, typically a 2:1 (50%) gradient, or less. Spoil can be endhauled off-site or stored on the road bench adjacent the crossing, provided it is placed and stabilized where it will not erode or fail and enter the stream.

BMP: Rolling Dip Design and Placement

- Rolling dips are drainage structures designed to force surface water to be drained from the road surface.
- The road shall dip into, and rise out of, the rolling dip to eliminate the potential of road surface runoff to run further down road way.
- The rolling dip shall be constructed with clean native materials or rock surfaced where specified.
- The rolling dips outlet may be armored to resist down-cutting and erosion of the outboard road fill.
- Do not discharge rolling dips into any areas that show signs of instability or active landsliding.
- If the rolling dip is designed to divert both road surface and ditch runoff, block the down-road ditch with compacted fill in order to force all ditch flows through the trough (low point) of the rolling dip.

BMP: Rocked Rolling Dip Design and Placement

- Rocked rolling dips are drainage structures designed to carry known sources of surface water across road ways or from known persistently wet segments of road such as swales without defined watercourses or road segments with heavy bank/road seepage.
- The road shall dip into, and rise out of, the rocked rolling dip to minimize diversion potential.
- The rocked rolling dip shall be constructed with clean rock that is large enough to remain in place during peak flows. Rock size shall vary relative to the anticipated flow through the dip with larger rock used in location where greater flow is anticipated.
- The rocked rolling dips inlet and outlet shall be armored to resist down-cutting and erosion.
- The entire width of the rocked rolling dip shall be rock armored to a minimum of 5-feet from the centerline of the dipped portion of the rolling dip.
- If a keyway is necessary, the rocked rolling dip keyway at the base of the dip shall be of sufficient size, depth and length to support materials used in the rocked rolling dip construction back up to the road crossing interface.
- Do not discharge rolling dips into any areas that show signs of instability or active landsliding.
- If the rolling dip is designed to divert both road surface and ditch runoff, block the down-road ditch with compacted fill.
- The rolling dip should be designed as a broad feature ranging from 10-100 feet long so that it is drivable by most types of vehicular traffic and not significantly inhibit traffic and road use.





FIGURE 34. A classic Type I rolling dip, where the excavated up-road approach (B) to the rolling dip is several percent steeper than the approaching road and extends for 60 to 80 feet to the dip axis. The lower side of the structure reverses grade (A) over approximately 15 feet or more, and then falls down to rejoin the original road grade. The dip must be deep enough that it is not obliterated by normal grading, but not so deep that it is difficult to negotiate or a hazard to normal traffic. The outward cross-slope of the dip axis should be 3% to 5% greater than the up-road grade (B) so it will drain properly. The dip axis should be out-sloped sufficiently to be self-cleaning, without triggering excessive downcutting or sediment deposition in the dip axis (Modified from: Best, 2013).

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS


BMP: Rolling Dip Design and Placement (Types)

Type 1 Rolling Dip (Standard)




Type 1 rolling dips are used where road grades are less than about 12-14% and road runoff is not confined by a large through cut or berm. The axis of the dip should be perpendicular to the road alignment and sloped at 3-4% across the road tread. Steep roads will have longer and more abrupt dip dimensions to develop reverse grade through the dip axis. The road tread and/or the dip outlet can be rocked to protect against erosion, if needed.

Type 2 Rolling Dip (Through-cut or thick berm road reaches)



Type 2 rolling dips are constructed on roads up to 12-14% grade where there is a through cut up to 3 feet tall, or a wide or tall berm that otherwise blocks road drainage. The berm or native through cut material should be removed for the length of the dip, or at least through the axis of the dip, to the extent needed to provide for uninterrupted drainage onto the adjacent slope. The berm and slope material can be excavated and endhauled, or the material can be sidecast onto native slopes up to 45%, provided it will not enter a stream.

Type 3 Rolling Dip (Steep road grade)



Type 3 rolling dips are utilized where road grades are steeper than about 12% and it is not feasible to develop a reverse grade that will also allow passage of the design vehicle (steep road grades require more abrupt grade reversals that some vehicles may not be able to traverse without bottoming out).

Instead of relying on the dip's grade reversal to turn runoff off the roadbed, the road is built with an exaggerated outslope of 6-8% across the dip axis. Road runoff is deflected obliquely across the dip axis and is shed off the outsloped section rather than continuing down the steep road grade.

FIGURE 36. Rolling dip types

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Rolling Dip Design and Placement

FIGURE 33A. Rolling dip constructed on a rock surfaced rural road. The rolling dip represents a change-in-grade along the road alignment and acts to discharge water that has collected on, or is flowing down, the road surface. This road was recently converted from a high maintenance, insloped, ditched road to a low maintenance, outsloped road with rolling dips.



FIGURE 33B. This side view of an outsloped road shows that the rolling dip does not have to be deep or abrupt to reverse road grade and effectively drain the road surface. This outsloped forest road has rolling dips that allow all traffic types to travel the route without changing speed.



BMP: Waterbar/Rolling Dip Combined with DRC



FIGURE 39.

Waterbars are often used to drain surface runoff from seasonal, unsurfaced roads. Because they are easily broken down by vehicles, waterbars are only used on unsurfaced roads where there is little or no wet weather traffic. In this photo, a waterbar and ditch relief culvert are used to drain all road surface and ditch runoff from the insloped road prism.

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS


Diagram shows and discussed the use of a waterbar. However, a DRC combined with a rolling dip structure provides the same surface and ditch drainage for roads used year-round. Just as with the waterbar in the photo above, The DRC is installed just upslope from the rolling dip. This also creates a fail-safe should the DRC become plugged or overwhelmed.



FIGURE 238. *Traffic and surface runoff from graveled roads often produces surface erosion, turbid runoff and fine sediment transport that can be delivered to streams. Where ditches can't be eliminated, sediment traps and roadside settling basins can be installed to capture and remove most of the eroded sediment. This settling basin has been constructed along the inside ditch just before a stream crossing culvert inlet (see arrow). Eroded sediment from the road and ditch are deposited in the basin before flow is released to the stream. Fine sediments have filled about 1/3 of this basin and vegetation is now growing. Sediment basins require periodic maintenance to maintain their storage capacity.*

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Road Outsloping/Insloping



HANDBOOK FOR FOREST, RANCH, AND RURAL ROADS

FIGURE 29. Road shape changes as the road travels through the landscape. For example, an out-sloped road will have a steep or "banked" outslope through inside curves, a consistent outslope through straight reaches and a flat or slightly insloped shape as it goes through an outside curve. The road may have an outslope of 2-3% across the travel surface while the shoulder is more steeply outsloped to ensure runoff and sediment will leave the roadbed.

BMP: Steep Road Drainage Features




FIGURE 55. Steep roads that go straight up or down a hillside are very difficult to drain. This steep, fall line road developed a through cut cross section that was drained using lead out ditches to direct runoff off the road and onto the adjacent, vegetated hillside. The road was "outsloped" to drain runoff to the right side, and the lead out ditch was built slightly steeper than the road grade, to be self-cleaning. Four lead out ditches have been constructed at 100-foot intervals to the bottom of the hillside.

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Ditch Relief Culvert

- Install ditch relief culverts at an oblique (typically 30 degree) angle to the road so that ditch flow does not have to make a sharp angle turn to enter the pipe. On low gradient roads (<5%), where ditch flow is slow, ditch relief culverts can be installed at right angles to the road.
- Install ditch relief culverts (DRC) to outlet at, and drain to, the base of the fill
- If it cannot be installed at the base of the fill, install the DRC with a grade steeper than the inboard ditch draining to the culvert inlet, and then install a downspout on the outlet to carry the culverted flow to the base of the fillslope or energy dissipater material at outlet to prevent erosion or the outboard road fill.
- Downspouts longer than 20 feet should be secured to the hillslope for stability.
- Ditch relief culverts should not carry excessive flow such that gullying occurs below the culvert outlet or such that erosion and down-cutting of the inboard ditch is occurring.
- Do not discharge flows from ditch relief culverts onto unstable areas or highly erodible hillslopes.
- If the ditch is on an insloped or crowned road, consider reshaping road outsloping to drain the road surface. The ditch and the ditch relief culvert would then convey only spring flow from the cutbank and hillslope runoff, and not turbid runoff from the road surface.




HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

FIGURE 48. The elements of a properly installed ditch relief culvert. The culvert is angled at about 30 degrees to the road alignment to help capture flow and prevent culvert plugging or erosion of the inlet area. It is set at the base of the fill (ideally) or with a grade slightly steeper than the grade of the contributing ditch (but never with a grade less than 2 percent) (USDA-SCS, 1983). At a minimum, the grade of the ditch relief culvert should be sufficient to prevent sediment accumulation at the inlet or deposition within the culvert itself (it should be self-cleaning) (USDA-SCS, 1983).

BMP: Waterbar Construction

FIGURE 40. Waterbars are constructed on unsurfaced forest and ranch roads that will have little or no traffic during the wet season. The waterbar should be extended to the cutbank to intercept all ditch flow (1) and extend beyond the shoulder of the road. A berm (2) must block and prevent ditch flow from continuing down the road during flood flows. The excavated waterbar (3) should be constructed to be self-cleaning, typically with a 30° skew to the road alignment with the excavated material bermed on the downhill grade of the road (4). Water should always be discharged onto the downhill side on a stable slope protected by vegetation. Rock (shown in the figure) should not be necessary if waterbars are spaced close enough to prevent serious erosion. (5) The cross ditch depth (6) and width (7) must allow vehicle cross-over without destroying the function of the drain. Several alternate types of waterbars are possible, including one that drains only the road surface (not the ditch), and one that drains the road surface into the inside ditch (BCMF, 1991).

HANDBOOK FOR FOREST, RANCH, AND RURAL ROADS




BMP: Unstable Fill Removal and Treatment




FIGURE 230. *The most cost-effective treatment for unstable fills along the outside of a forest, ranch or rural road is simply the direct excavation of the unstable material. If road width is too narrow, additional width can often be derived from cutting into the bank. The excavation should encompass the unstable fill materials, beginning at the inside crack or scarp, and extending out and down the fill slope as far as possible. For proper surface drainage, and to retrieve most of the unstable fill, the excavation should have a concave profile when completed. Typically, the bulk of the fill is within 20 to 25 feet of the outside edge of the road and is easily reached by a mid-sized excavator. Any remaining fill is likely to be small enough that it will not fail or travel far enough to reach the stream.*


BMP: Unstable Fill Removal and Treatment



BMP: Unstable Fill Removal and Treatment



BMP: Unstable Fill Removal and Treatment



BMP: Rock Armor Cutbank



FIGURE 52. *This wet and potentially unstable cut slope on a newly constructed road was stabilized using a buttress of large rock armor. To assure their effectiveness, rock buttresses and other retaining structures should be designed by a qualified engineer or engineering geologist.*

HANDBOOK FOR FOREST, RANCH AND RURAL ROADS

BMP: Rip-Rap Size Class Table

TABLE 25. Standard classification and gradation of riprap by size of rock¹

Riprap size class	Median particle weight ²	Median particle diameter ² (in)	Minimum and maximum allowable particle size (in) ²						
			D ₁₅		D ₅₀		D ₈₅		D ₁₀₀
			Min	Max	Min	Max	Min	Max	Max
Class I	20 lb	6	3.7	5.2	5.7	6.9	7.8	9.2	12.0
Class II	60 lb	9	5.5	7.8	8.5	10.5	11.5	14.0	18.0
Class III	150 lb	12	7.3	10.5	11.5	14.0	15.5	18.5	24.0
Class IV	300 lb	15	9.2	13.0	14.5	17.5	19.5	23.0	30.0
Class V	¼ ton	18	11.0	15.5	17.0	20.5	23.5	27.5	36.0
Class VI	3/8 ton	21	13.0	18.5	20.0	24.0	27.5	32.5	42.0
Class VII	½ ton	24	14.5	21.0	23.0	27.5	31.0	37.0	48.0
Class VIII	1 ton	30	18.5	26.0	28.5	34.5	39.0	46.0	60.0
Class IX	2 ton	36	22.0	31.5	34.0	41.5	47.0	55.5	72.0
Class X	3 ton	42	25.5	36.5	40.0	48.5	54.5	64.5	84.0

¹Lagasse et al. (2006)

²Equivalent to spherical diameter

BMP: Storage Bladders

- Storage bladders shall be located and designed to minimize the potential for impacts due to rolling and/or failure. Storage bladders should be stored on flat slopes where stability will not be affected.
- Storage bladders shall be located to minimize the potential for water to flow into a watercourse in the event of a catastrophic failure.
- Bladders shall not be used unless the bladder is safely contained within a secondary containment system with sufficient capacity to capture 110 percent of a bladders maximum volume in the vent of bladder failure.
- Secondary containment is recommended in the form of a dirt berm, containment pit, combination of both, or impermeable material with skeletal support. The containment should be capable of holding 110 percent of the bladders volume.
- Secondary containment systems shall be of sufficient strength and stability to withstand the forces of released contents in the event of catastrophic bladder failure.
- Secondary containment systems that are exposed to precipitation shall be designed and maintained with sufficient capacity to accommodate precipitation and storm water inputs from a 25-year, 24-hour storm event.
- Bladders and containment systems shall be periodically inspected to ensure integrity.



This is an example of a containment pit which will assist in mitigating the impacts if this storage bladder failed.

BMP: Cultivation Site Restoration

- Remove all cultivation and associated materials from designated cultivation site.
 - This includes plant mass, root balls, potting containers, cultivation medium and any materials associated with the preparation, cultivation, and harvest of commercial cannabis.
 - Cultivation medium removed from the site shall be stored/disposed of in compliance with Order conditions related to spoils management.
- All disturbed and/or unstable slopes shall be stabilized and returned to pre-project conditions.
 - Slopes shall be contoured as close as feasible to natural grade and aspect.
 - Temporary erosion control shall be applied to prevent sediment run-off.
- Soil exposed as a result of project work, soil above rock riprap, and interstitial spaces between rocks shall be revegetated with native species by live planting, seed casting, or hydroseeding prior to the rainy season of the year work is completed.
 - Native plants characteristic of the local habitat shall be used for revegetation when implementing and maintaining cleanup/restoration work in riparian and other sensitive areas.
 - Native forbes and gramminoids shall be planted to replace sediment stabilization, sediment filtration and nutrient filtration
 - Native trees and shrubs shall be planted to replace bank stabilization, inputs of large woody debris and temperature control within riparian areas.
 - Restoration of the quality/health of the riparian stand shall promote: 1) shade and microclimate controls; 2) delivery of wood to channels, 3) slope stability and erosion control, 4) ground cover, and 5) removal of excess nutrients.