
REPORT

ACCESSIBILITY COMPLIANCE ASSESSMENT REPORT

Social Services Branch, 808 E. Street, Eureka, CA



PREPARED FOR

Travis I. Smith
County of Humboldt
County Administrative Office
825 5th Street, Room 112
Eureka, California 95501
TSmith@co.humboldt.ca.us

Project #: 1JKI00057.011

Date: 9/16/21



Jasper S. Kirsch, CASp, ICC, Assoc. AIA 1220 Concord Ave., Ste. 400 Concord, CA 94520 USA

jkirsch@jensenhughes.com +1 925-938-3550

Revision Record Summary

Revision Date	Revision No.	Revision Summary
9/02/21	0	Initial Issuance
9/16/21	1	Record 130E error corrected. Status changed to "Closed"

Table of Contents

1.0	INTRODUCTION	1
2.0	LIMITS OF REVIEW	1
APP	PENDICES	3
ΔΡΡ	PENDIX A ACCESSIBILITY COMPLIANCE ASSESSMENT REPORT	Δ_1

1.0 Introduction

The following is an Accessibility Compliance Assessment Report (ACAR) prepared by Jensen Hughes (Consultant) for the County of Humboldt (Client). Consultant was hired to provide Accessibility Inspection Services pertaining to the County leased facility currently being renovated for barrier remediation located at 808 E. Street, Eureka, CA. Inspections were limited to the assessment of "OPEN" barriers (with some exclusions as directed by Client) identified within the original ADA Access Compliance Assessment report of the property that were conducted and prepared by third-party consultant, SZS Engineering Access. The referenced report was originally dated/prepared on December 19, 2020 and an updated report was distributed to Consultant dated March 30, 2021 as a part of these services.

2.0 Limits of Review

The assessment and recommendations contained within this report are specific to the scoping and technical criteria of the current 2019 California Building Code (CBC) Chapter 11B and the 2010 Americans with Disabilities Act Accessibility Standards (ADAS).

The intent of this report is to verify that accessible elements were made in conformance with the applicable accessibility scoping and technical criteria and to otherwise identify issues of nonconformity within the constructed areas assessed by the Consultant and to provide recommendations to remediate these issues.

Where barriers have been verified as remediated:

- + Consultant will mark that barrier as "CLOSED" within this report with reference to the original barrier number, or is a remediation that was checked based on client's direction while on site;
- Include photo(s) of the new existing conditions;
- + Provide an as-built description of the new existing conditions as they relate to the remediation of the original barrier.

Where barriers have not been remediated:

- Consultant will mark that barrier remains "OPEN" within this report with reference to the original barrier number, or if a new barrier was identified;
- + Include photo(s) of the new existing conditions;
- + Provide an as-built description of the existing conditions as they relate to the barrier;
- Provide a barrier description and citations to the applicable scoping and technical criteria pertaining to the barrier;
- + Provide proposed solutions to remediate the barrier.

This report represents a professional opinion prepared by Consultant, based on our understanding and interpretation of applicable scoping and technical criteria. Consultant will endeavor to use reasonable professional efforts to interpret applicable accessibility requirements as they may apply but Consultant cannot and does not promise, warrant or guarantee that the project will comply with all interpretations of those accessibility requirements and/or similar requirements of other federal, state and local laws, rules, codes, ordinances and regulations as they may be interpreted by others, and/or apply to the project currently or in the future.

Submitted by:

Jensen Hughes

Prepared by:

Reviewed by:

Jasper Kirsch, CASp #661 Manager I Senior Accessibility Consultant Tadd Tsui, CASp #778 Accessibility Consultant

JK/TT:

1JKI00057.000\808 E. Street, Eureka, CA _Accessibility Compliance Assessment Report_20210916Rev1

4					7	•		
_/\ ·	n	n	01	n	d	11	00	C
\boldsymbol{A}_{i}	ועו	w		ш	ш	LL	Æ	. >

77 - 1	1	COL		
Tab	IP N	$T \cap C$	m au ho	nrc
1 uo	$\iota \iota \iota \iota \iota$		TILL	IUU

Appendix A Accessibility Compliance Assessment Report

SUMMARY

Facility: 808 E. Street	
Area: Exterior	
4C Exterior - Parking Lot - Parking - Access Aisle-Marking	CLOSED
5B Main Lobby 100A - Doors - Push Plates	OPEN
Area: Interior	
5B Main Lobby 100A - Doors - Push Plates	OPEN
6D Corridor 100B - Doors - Vision Lights	CLOSED
8K Corridor 100F - Doors - Door Pressure	OPEN
8L Corridor 100F - Doors - Door Threshold	OPEN
9B Corridor 100D - Signs - Room Designation Sign	CLOSED
10B Office 103 - Doors - Door Hardware	CLOSED
14D Office 127 (Converted to Staff Restroom) - Reach Range - Electrical Switch - Low	CLOSED
14E Office 127 (Converted to Staff Restroom) - Fire Alarms - Alarm Notification	CLOSED
14F Office 127 (Converted to Staff Restroom) - Toilet and Bathing Rooms - Mirrors	CLOSED
14G Office 127 (Converted to Staff Restroom) - Doors - Door Hardware	CLOSED
16 Office 117 (Relocated to 101) - Signs - Room Designation Sign	CLOSED
16A Office 101 (Relocated from 117) - Signs - Room Designation Sign	CLOSED
16B Office 101 (Relocated from 117) - Doors - Door Hardware	CLOSED
16C Office 101 (Relocated from 117) - Doors - Maneuvering Clearance	CLOSED
16E Office 101 (Relocated from 117) - Turning Space - Circular Turning Space	CLOSED
16F Office 101 (Relocated from 117) - Doors - Door Threshold	OPEN
16G Office 101 (Relocated from 117) - Fire Alarms - Alarm Notification	CLOSED
130A Office 127 (Relocated to 130) - Doors - Door Threshold	OPEN
130B Office 127 (Relocated to 130) - Doors - Door Hardware	CLOSED
130C Office 127 (Relocated to 130) - Fire Alarms - Alarm Notification	CLOSED
130D Office 127 (Relocated to 130) - Reach Range - Electrical Switch - High	OPEN
130E Office 127 (Relocated to 130) - Signs - Room Designation Sign	CLOSED
808 E. Street	

Location # 4 - Exterior - Parking Lot

Accessibility Element: Parking

40



Specific Item: Access Aisle-Marking

Barrier Description:

Access aisles not marked with a blue painted borderline around their perimeter, and the area within shall be marked with hatched lines a max. 36" on center.

As-Built: 36" on center

ADA 2010: 502.3.3

CBC 2019: 11B-502.3.3

4C

Exterior - Parking Lot

CLOSED



End of Location: 4 - Exterior - Parking Lot

Location # 5 - Main Lobby 100A

Accessibility Element: Doors

5B







Specific Item: Push Plates

Barrier Description:

Push plates not installed at proper height, one mounted between 7" and 8" above the ground on center, another mounted between 30" and 44" above the floor on center.

As-Built:

Lower push plate is 4" o.c. Upper push plate 37.5" o.c. (compliant) Additionally water faucet may be a hazard to wheelchair users.

Proposed Solution:

Remount lower push plate and modify water faucet to avoid sharp edges and extending into the required clear floor space. CBC 2019: 11B-404.2.9

Main Lobby 100A



End of Location: 5 - Main Lobby 100A

End of Area: Exterior

Location # 5 - Main Lobby 100A

Accessibility Element: Doors

5B



Specific Item: Push Plates

Barrier Description:

Push plates not installed at proper height, one mounted between 7" and 8" above the ground on center, another mounted between 30" and 44" above the floor on center.

As-Built:

Lower push plate is 2.5" o.c. Upper push plate 36.5" o.c. (compliant)

Proposed Solution: Remount lower push plate. CBC 2019: 11B-404.2.9

5B Main Lobby 100A



End of Location: 5 - Main Lobby 100A

Location #6 - Corridor 100B

Accessibility Element: Doors

6D



Specific Item: Vision Lights

Barrier Description:

Door, gate, or side light adjacent to a door or gate, containing one or more glazing panels that permit viewing through the panels does not have a panel with the bottom edge located less than 43" above the floor.

As-Built:

Opaque sheeting provided

ADA 2010: 404.2.11

CBC 2019: 11B-404.2.11

6D

Corridor 100B

CLOSED



End of Location: 6 - Corridor 100B

Location #8 - Corridor 100F

Accessibility Element: Doors

#8K



Specific Item: Door Pressure

Barrier Description:

Door takes less than 5 seconds to swing from a 90 degree open position to 12 degrees from the latch.

As-Built: 4 seconds

Proposed Solution: Adjust door closer speed. ADA 2010: 404.2.8

CBC 2019: 11B-404.2.8

8KCorridor 100F

OPEN

Accessibility Element: Doors

#8L



Specific Item: Door Threshold

Barrier Description:

Threshold at door exceeds 0.5".

As-Built: 5/8"

Proposed Solution:

Modify adjacent floor surfaces or provide compliant threshold with a max. of 0.25" vertical height or a max. of 0.5" height when beveled at 1:2 max.

ADA 2010: 404.2.5

CBC 2019: 11B-404.2.5

8L Corridor 100F

Corridor 100F





End of Location: 8 - Corridor 100F

Location #9 - Corridor 100D

Accessibility Element: Signs

9B



Specific Item: Room Designation Sign

Barrier Description:

Latch sign identifying a permanent room and/or space does not contain the required tactile characters and/or Braille or is not provided at all.

As-Built:

Signs provided at 111, 110, 108, 106, 105, 104, 109, 107

ADA 2010: 216.2

CBC 2019: 11B-216.2

9B

Corridor 100D

CLOSED



End of Location: 9 - Corridor 100D

Location # 10 - Office 103

Accessibility Element: Doors

10B



Specific Item: Door Hardware

Barrier Description:

Hardware to operate door (including handle, latches, and locks) is not accessible.

As-Built:

Door hardware replaced

ADA 2010: 404.2.7

CBC 2019: 11B-404.2.7

10E

Office 103

CLOSED



End of Location: 10 - Office 103

ADA 2010: 308.2; 308.3

CBC 2019: 11B-308.1; 11B

Facility: 808 E. Street Area: Interior

Location # 14 - Office 127 (Converted to Staff Restroom)

Accessibility Element: Reach Range

14D



Specific Item: Electrical Switch - Low

Barrier Description:

Electrical switch/outlet location is less than 15" measured to the bottom of the outlet box for unobstructed approach.

As-Built

Light switches and outlets corrected as part of alteration onverted to Staff Restroom) project.

CLOSED

-308.2; 11B-308.3



Accessibility Element: Fire Alarms

14E



Specific Item: Alarm Notification

Barrier Description:

Visible alarm notification appliances are not provided in public use and common use area where audible alarms are provided.

As-Built:

Strobe provided

CBC 2019: 907.5.2.3.1

14E

Office 127 (Converted to Staff Restroom)

CLOSED

Accessibility Element: Toilet and Bathing Rooms

14F



Specific Item: Mirrors

Barrier Description:

Mirrors serving accessible lavatories are installed with the bottom edge of the reflecting surface greater than 40" high.

As-Built: Mirror 40" ADA 2010: 603.3

CBC 2019: 11B-603.3

14F

Office 127 (Converted to Staff Restroom)

CLOSED

Accessibility Element: Doors

14G



Specific Item: Door Hardware

Barrier Description:

Hardware to operate door (including handle, latches, and looks) is not accessible.

locks) is not accessible.

As-Built: Lock compliant ADA 2010: 404.2.7

CBC 2019: 11B-404.2.7

14**G**

Office 127 (Converted to Staff Restroom)

CLOSED



End of Location: 14 - Office 127 (Converted to Staff Restroom)

Location # 16 - Office 117 (Relocated to 101)

Accessibility Element: Signs

16



Specific Item: Room Designation Sign

Barrier Description:

Latch sign identifying a permanent room and/or space does not contain the required tactile characters and/or Braille or is not provided at all.

As-Built:

Office 117 (Relocated to 101) Room 117 is now a private office: Compliant sign provided. Compliant door hardware is provided.

CLOSED

Accessibility Element: Signs



Specific Item: Room Designation Sign

Barrier Description:

Latch sign identifying a permanent room and/or space does not contain the required tactile characters and/or Braille or is not provided at all.

As-Built:

Compliant sign provided

ADA 2010: 216.2

ADA 2010: 216.2

CBC 2019: 11B-216.2

CBC 2019: 11B-216.2

Office 101 (Relocated from 117)

CLOSED

Accessibility Element: Doors

16B



Specific Item: Door Hardware

Barrier Description:

Hardware to operate door (including handle, latches, and locks) is not accessible.

As-Built:

Accessible door hardware provided

ADA 2010: 404.2.7


CBC 2019: 11B-404.2.7

Office 101 (Relocated from 117)

CLOSED

Accessibility Element: Doors

16C



Specific Item: Maneuvering Clearance

Barrier Description:

Front Approach, Pull Side: Door does not provide a minimum 60" long (measured perpendicular to doorway) x 18" wide (measured beyond latch side) maneuvering clearance (Exterior doors shall instead provide a minimum 24" wide clearance on exterior sides).

As-Built:

Compliant maneuvering clearance provided. 61" to desk

ADA 2010: 404.2.4.1

ADA 2010: 304.3.1

CBC 2019: 11B-304.3.1

CBC 2019: 11B-404.2.4.1

16C

Office 101 (Relocated from 117)

CLOSED

Accessibility Element: Turning Space

16E



Specific Item: Circular Turning Space

Barrier Description:

An accessible turning space of min. 60" diameter for a wheelchair is not provided in the room.

As-Built

Turning spaces and maneuvering clearances provided within 101 (Relocated from 117) the room

CLOSED



Accessibility Element: Doors

16F



Specific Item: Door Threshold

Barrier Description:

Threshold at door exceeds 0.5".

As-Built:

Typical throughout facility: 5/8" not 1:2

Proposed Solution:

Modify adjacent floor surfaces or provide compliant threshold with a max. of 0.25" vertical height or a max. of 0.5" height when beveled at 1:2 max.

ADA 2010: 404.2.5

CBC 2019: 11B-404.2.5

CBC 2019: 11B-404.2.5

16F

Office 101 (Relocated from 117)

OPEN

Accessibility Element: Fire Alarms

16G



Specific Item: Alarm Notification

Barrier Description:

Visible alarm notification appliances are not provided in public use and common use area where audible alarms are provided.

Strobe provided within room

Office 101 (Relocated from 117)

CBC 2019: 907.5.2.3.1

CLOSED

End of Location: 16 - Office 101 (Relocated from 117)

Location # 130 - Office 127 (Relocated to 130)

Accessibility Element: Doors

130A



Specific Item: Door Threshold

Barrier Description:

Threshold at door that is between 0.25" and 0.5" and is not properly beveled at 1:2.

As-Built: Bevel not 1:2

Proposed Solution: Provide compliant bevel. ADA 2010: 404.2.5

CBC 2019: 11B-404.2.5

130A

Office 127 (Relocated to 130)

OPEN

Accessibility Element: Doors

130E



Specific Item: Door Hardware

Barrier Description:

Hardware to operate door (including handle, latches, and locks) is not accessible.

As-Built⁻

Compliant door hardware provided

ADA 2010: 404.2.7

CBC 2019: 11B-404.2.7

130B

Office 127 (Relocated to 130)

CLOSED

Accessibility Element: Fire Alarms

130d



Specific Item: Alarm Notification

Barrier Description:

Visible alarm notification appliances are not provided in public use and common use area where audible alarms are provided.

As-Built:

Strobe provided

CBC 2019: 907.5.2.3.1

130C

Office 127 (Relocated to 130)

CLOSED

Accessibility Element: Reach Range





Specific Item: Electrical Switch - High

Barrier Description:

Electrical switch/outlet location exceeds 48" measured to the top of the outlet box for unobstructed approach.

49.75"

Proposed Solution:

Reinstall electrical switch/outlet when alteration occurs. Verify code at time of construction or previous alteration for safe harbor of 54" max. for light switch.

ADA 2010: 308.2; 308.3

CBC 2019: 11B-308.1; 11B

-308.2; 11B-308.3

Office 127 (Relocated to 130)

OPFN

Accessibility Element: Signs





Specific Item: Room Designation Sign

Barrier Description:

Latch sign identifying a permanent room and/or space does not contain the required tactile characters and/or Braille or is not provided at all.

Compliant sign provided

ADA 2010: 216.2

CBC 2019: 11B-216.2

Office 127 (Relocated to 130)

CLOSED



End of Location: 130 - Office 127 (Relocated to 130)

End of Area: Interior

End of Report: 808 E. Street