

RECEIVED

APR 03 2019

\*The free Adobe Reader may be used to view and complete this form. However, software must be purchased to complete, save, and reuse a saved form.

File Original with DWR MAY 19 2014

# Well Completion Report

State of California

Refer to Instruction Pamphlet  
No. e0213421

Page 1 of 2

Owner's Well Number 1

Date Work Began 05/12/2014 Date Work Ended 5/14/2014

Local Permit Agency Humboldt County E.H.D.

Permit Number 11/12-1064 Permit Date 5/15/13

DWR Use Only - Do Not Fill In

07N 04E - 08

Humboldt County  
Cannabis Svcs.

State Well Number/Site Number

Latitude N Longitude W

APN/TRS/Other

**Geologic Log**

Orientation  Vertical  Horizontal  Angle Specify \_\_\_\_\_

Drilling Method Direct Rotary \_\_\_\_\_ Drilling Fluid \_\_\_\_\_

Depth from Surface		Description
Feet	to Feet	Describe material, grain size, color, etc
0	4	Clayey Silt W/Rock Reddish
4	28	Schist Brown
28	63	Tuffs Lt. BROWN
63	160	Basalt Black

**Well Owner**

**Well Location**

Address Three Creeks Rd. Parcel #23

City Blue Lake County Humboldt

Latitude \_\_\_\_\_ N Longitude \_\_\_\_\_ W

Dec. Min. Sec. Dec. Min. Sec.

Datum \_\_\_\_\_ Dec. Lat. \_\_\_\_\_ Dec. Long. \_\_\_\_\_

APN Book 522 Page 021 Parcel 009

Township 07N Range 04E Section 08

**Location Sketch**  
(Sketch must be drawn by hand after form is printed.)

North

West

East

South

Illustrate or describe distance of well from roads, buildings, fences, rivers, etc. and attach a map. Use additional paper if necessary. Please be accurate and complete.

**Activity**

New Well  
 Modification/Repair  
 Deepen  
 Other \_\_\_\_\_  
 Destroy  
Describe procedures and materials under "GEOLOGIC LOG"

**Planned Uses**

Water Supply  
 Domestic  Public  
 Irrigation  Industrial

Cathodic Protection  
 Dewatering  
 Heat Exchange  
 Injection  
 Monitoring  
 Remediation  
 Sparging  
 Test Well  
 Vapor Extraction  
 Other \_\_\_\_\_

Total Depth of Boring 160 Feet

Total Depth of Completed Well 150 Feet

**Water Level and Yield of Completed Well**

Depth to first water 30 (Feet below surface)

Depth to Static \_\_\_\_\_

Water Level 30 (Feet) Date Measured 05/12/2014

Estimated Yield \* 10 (GPM) Test Type Air Lift

Test Length 4 (Hours) Total Drawdown 150 (Feet)

\*May not be representative of a well's long term yield.

Casings								
Depth from Surface	Borehole Diameter	Type	Material	Wall Thickness	Outside Diameter	Screen Type	Slot Size if Any	
Feet to Feet	(Inches)			(Inches)	(Inches)		(Inches)	
0	30	10	Blank	PVC Sch. 80	CL200	5		
30	150	10	Screen	PVC Sch. 80	CL200	5	Milled Slots	0.032

Annular Material			
Depth from Surface	Fill	Description	
Feet to Feet			
0	20	Bentonite	Sanitary Seal
20	150	Filter Pack	3/8" Pea Gravel

**Attachments**

Geologic Log  
 Well Construction Diagram  
 Geophysical Log(s)  
 Soil/Water Chemical Analyses  
 Other Location Map


Attach additional information, if it exists

**Certification Statement**


I, the undersigned, certify that this report is complete and accurate to the best of my knowledge and belief

Name FISCH DRILLING  
Person, Firm or Corporation

3150 JOHNSON ROAD HYDESVILLE CA 95547  
Address City State Zip

Signed  Date Signed 05/14/2014  
C-57 Licensed Water Well Contractor C-57 License Number

# Supply Creek Tract Land Owners Association



- Legend**
- Property Boundary
  - Habitat Conservation Covered Land
  - Public Road, County
  - Association Boundary
  - Zone 1, 150 - 2 1/2" - 3" - 4"
  - Class I watercourse
  - Class II watercourse
  - Class III watercourse