#### NOTES

THE CONTRACTOR MUST HAVE A CLASS "A" LICENSE FOR THIS PROJECT.

STANDARD PLAN LIST APPLICABLE TO THIS CONTRACT IS INCLUDED IN THE SPECIAL PROVISIONS.

1	TITI C	CHEET


2 TYPICAL ROAD SECTIONS

INDEX OF SHEETS

- 3 PROJECT CONTROL
- 1 144011
- 5 PROFII
- 6 DRAINAGE AND UTILITES
- 7 WATERLINE PROFILE
- B DRAINAGE DETAILS
- 9-10 STAGE CONSTRUCTION & TRAFFIC HANDLING
- 11 EROSION CONTROL
- 12 SIGNING & STRIPING
- 13-21 STRUCTURES PLANS

#### **GEOTECH REPORT**

2018 CRAWFORD & ASSOCIATES



## COUNTY OF HUMBOLDT DEPARTMENT OF PUBLIC WORKS PROJECT PLANS FOR CONSTRUCTION OF

MITCHELL ROAD (C4J090) AT P.M. 1.15 STORM DAMAGE PROJECT


FEMA 4301-DR-CA PW 1029 CONTRACT NO. 217300


TO BE SUPPLEMENTED BY STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS, STANDARD SPECIFICATIONS, AND LATEST REVISED 2018 STANDARD SPECIFICATIONS











COUNTY OF HUMBOLDT Department of Public Works

MITCHELL ROAD STORM DAMAGE PROJECT

TITLE SHEET

1

21

MARK
THOMAS

DESIGNED BY: LF

DRAWN BY: CM

REVIEWED BY: JT

ROAD NO: C4J090

CONTRACT NO: 217300

EMA 4301-DR-CA PW 1029

AILE POST: 1.15

NOT TO SCALE

DEL NORTE CO.







No. 72382 Exp. 6/30/20

ORIGINAL	LOW	BID	PRICE	CONSTRU	CTED	BY			RESID	ENT	ENGI	NEER	
I				PROJECT	СОМ	PLETED	7	/	CONS	ΓRŪ	CTION	COST	\$

#### **NOTES:**

STRUCTURE BACKFILL 95% RELATIVE COMPACTION



BAR IS ONE INCH ON ORIGINAL DRAWING
IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

	ROAD NAME: MITCHELL ROAD	<b>MARK</b>	
ON NG	ROAD NO: C4J090	THOMAS	
-	MILE POST: 1.15	DESIGNED BY: LF	Γ
•	FEMA 4301-DR-CA PW 1029	DRAWN BY: CM	H
ON JST	CONTRACT NO.: 217300	REVIEWED BY: JT	1
GLY	DATE: JANUARY 2019	APPROVED BY: JW	l


MITCHELL ROAD	STORM D	DAMAGE PROJECT	
TYPICAL	ROAD	SECTIONS	

COUNTY OF HUMBOLDT DEPARTMENT OF PUBLIC WORKS

2

21





#### MITCHELL ROAD

"M" 11+05.25 TO 12+67.23 NO SCALE

## -6" PERFORATED PLASTIC PIPE UNDERDRAIN \_6" 24" 18" STORM DRAIN

EP


0.25' HMA

FILTER FABRIC

- PERMEABLE MATERIAL


#### **UNDERDRAIN DETAIL**

NO SCALE



#### **PAVEMENT REINFORCING FABRIC DETAIL**

NO SCALE



#### NOTES:

- 1. CONTRACTOR MUST COMPLY WITH BUSINESS AND PROFESSIONS CODE SECTION 8771 (b) REGARDING REFERENCING, PRESERVING AND RECONSTRUCTING MONUMENTS, WHETHER OR NOT MONUMENTS ARE SHOWN
- 2. IF MONUMENT IS DAMAGED BY CONTRACTOR'S OPERATIONS, CONTRACTOR SHALL REPLACE MONUMENT AT CONTRACTOR'S EXPENSE.

#### **ABBREVIATIONS:**

NATIONAL GEODETIC SURVEY PERMANENT IDENTIFIER

#### LEGEND:

▲ CONTROL POINT


#### DATUM:


- 1. COORDINATES FOR THIS SURVEY ARE CALIFORNIA COORDINATE SYSTEM COORDINATES FOR THIS SURVEY ARE CALIFORNIA COORDINATE SYSTEM OF 1983 (CCS83) ZONE 1, NAD 83, EPOCH 2007.00 BASED ON A STATIC GPS CONTROL SURVEY. THE MAPPING ANGLE IS 1 DEGREE 23 MINUTES 05 SECONDS— ROTATE BEARINGS COUNTERCLOCKWISE BY THIS ANGLE TO OBTAIN "TRUE" OR GEODETIC BEARINGS. GRID DISTANCES SHOWN SHOULD BE DIVIDED BY THE COMBINED SCALE FACTOR OF 0.9998908 TO OBTAIN GROUND DISTANCES. MAPPING ANGLE AND GRID SCALE FACTOR TAKEN AT CONTROL POINT NO. 51. HORIZONTAL CONTROL IS IN US SURVEY FEET AND IS BASED ON STATIC GPS TIE TO NGS PID "LV180", AN NGS HPGN NETWORK POINT AT MURRAY FIELD IN EUREKA ON ABOVE STATED EPOCH. VERTICAL CONTROL IS ALSO BASED ON NGD PID "LV1180"' NAVD 88 DATUM, WITH ELEVATION OF 6.10 FEET.
- 2. NO DEEDED RIGHT OF WAY IS ON FILE WITH HUMBOLDT COUNTY FOR THIS SECTION OF MITCHELL ROAD PER RESEARCH BY HUMBOLDT COUNTY RIGHT OF WAY AGENT. THE DEEDS FOR BOTH PROPERTIES ARE RIGHT OF WAY AGENT. THE DEEDS FOR BOTH PROPERTIES ARE DESCRIBED IN DOCUMENT NO. 2007—15242—4 (PARCEL FIVE) AND DOCUMENT NO. 2002—15676—2. BOTH DEEDS CALL TO SIDELINES OF A FORTY FOOT ROAD AND CONTAIN CONSISTENT BEARINGS. THIS SURVEY HELD THE COURSES IN 2007—15242—4 (PARCEL FIVE) ON THE DOWNHILL SIDE OF THE PROJECT. THESE COURSES WERE OFFSET 40 FEET, SCALED TO GRID, AND ROTATED 2 DEGREES 00 MINUTES 34 SECONDS CLOCKWISE BASED ON THE PHYSICAL CENTER OF THE EXISTING ROAD AT POINTS "A" AND "B".


	ROAD NAME: MITCHELL ROAD	MARK	COUNTY OF HUMBOLDT
BAR IS ONE INCH ON ORIGINAL DRAWING	ROAD NO: C4J090	THOMAS	DEPARTMENT OF PUBLIC WORKS
	MILE POST: 1.15	DESIGNED BY: LF	MITCHELL ROAD STORM DAMAGE PROJECT
	FEMA 4301-DR-CA PW 1029	DRAWN BY: CM	
ITIS SHEET, ADVOST	CONTRACT NO.: 217300	REVIEWED BY: JT	PROJECT CONTROL
SCALES ACCORDINGLY			i notes i commot


NAME: MITCHELL RUAD	MARK MARK	COUNTY OF HUMBOLDI	SHEET
NO: C4J090	THOMAS	DEPARTMENT OF PUBLIC WORKS	3
OST: 1.15	DESIGNED BY: LF	MITCHELL ROAD STORM DAMAGE PROJECT	3
4301-DR-CA PW 1029	DRAWN BY: CM		OF
ACT NO.: 217300	REVIEWED BY: JT	PROJECT CONTROL	21
JANUARY 2019	APPROVED BY: JW		<b>Z</b> I

			CONST	RUCTION SURVEY C	ONTROL DATA	
	POINT #	NORTHING	EASTING	ELEVATION	DESCRIPTION	APPROX. LOCATION
<i>f</i>	51	2171801.92	5975269.57	228.44	SPIKE	-
1	56	2171659.42	5976058.81	148.04	SPIKE	-
	65	2171679.16	5976086.10	144.31	SPIKE	"M" 10+38.87 15.88' R
	57	2171747.06	5976130.78	136.50	MAGNETIC NAIL	"M" 11+12.93 10.46' R
	58	2171847.55	5976125.98	125.54	SPIKE	"M" 12+10.73 5.70' Rt
	64	2171964.98	5976119.04	112.78	SPIKE	"M" 13+27.48 13.06' Rt
6						









#### **GENERAL NOTES**

- 1. THE CONTRACTOR MUST POTHOLE AND VERIFY THE DEPTH OF THE EXISTING WATERLINE PRIOR TO THE INSTALLATION OF PROPOSED WATER FACILITIES. ANY UNANTICIPATED CONFLICTS SHALL BE REDESIGNED PRIOR TO BEGINNING WORK.
- 2. WHERE WATERLINE CROSSES STORM DRAIN, A FULL LENGTH STICK OF WATER MAIN PIPE MUST BE CENTERED ON THE CROSSING SO THE WATER PIPE JOINTS ARE AS FAR FROM THE CROSSING AS POSSIBLE.
- 3. SEE HUMBOLDT COMMUNITY SERVICES DISTRICT STANDARD PLAN FOR WATERLINE TRENCH AND TRACER WIRE DETAILS (WS-100A & WS-100B).

ELEV 142.0±

4. INSTALL MECHANICAL RESTRAINTS ON ALL WATERLINE BENDS AND JOINTS.

130

120)

110




FG @ Q WATERLINE

	ROAD NAME: MITCHELL ROAD	MARK ■	COUNTY OF HUMBOLDT
ORIGINAL DRAWING	ROAD NO: C4J090	THOMAS	DEPARTMENT OF PUBLIC WORKS
	MILE POST: 1.15	DESIGNED BY: LF	MITCHELL ROAD STORM DAMAGE PROJECT
	FEMA 4301-DR-CA PW 1029	DRAWN BY: CM	
NOT ONE INCH ON HIS SHEET, ADJUST ALES ACCORDINGLY	CONTRACT NO.: 217300	REVIEWED BY: JT	WATER LINE PROFILE
	DATE: JANUARY 2019	ADDROVED BY: IW	




12+00

21






RESTRAINED 8" PLASTIC PIPE (C900) WATER LINE








BAR IS ONE INCH ON ORIGINAL DRAWING	ROAD NAME: MITCHELL ROAD ROAD NO: C4J090	MARK THOMAS	COUNTY OF HUMBOLDT Department of Public Works	SHEE
ORIGINAL DRAWING	MILE POST: 1.15	DESIGNED BY: LF	MITCHELL ROAD STORM DAMAGE PROJECT	8
IF NOT ONE INCH ON THIS SHEET, ADJUST	FEMA 4301-DR-CA PW 1029 CONTRACT NO.: 217300	DRAWN BY: CM REVIEWED BY: JT	DRAINAGE DETAILS	of of
SCALES ACCORDINGLY	DATE: JANUARY 2019	APPROVED BY: JW	DITAINAGE DETAILO	





ELBOW ENERGY DISSIPATOR & ROCK SLOPE PROTECTION (RSP)











#### INDEX TO PLANS

SHEET NO.	TITLE
13 14	GENERAL PLAN INDEX TO PLANS
15	FOUNDATION PLAN
16	TYPICAL SECTION
17	CONCRETE BARRIER SLAB DETAILS
18	SOLDIER PILE WALL LAGGING DETAILS
19	SOLDIER PILE WALL DETAILS NO. 1
20	SOLDIER PILE WALL DETAILS NO. 2
21	SUB HORIZONTAL GROUND ANCHOR DETAILS

#### STANDARD PLANS DATED 2018

A3A	ABBREVIATIONS (SHEET 1 OF 3)
A3B	ABBREVIATIONS (SHEET 2 OF 3)
A3C	ABBREVIATIONS (SHEET 3 OF 3)
A10A	LEGEND - LINES AND SYMBOLS (SHEET 1 OF 5)
A10B	LEGEND - LINES AND SYMBOLS (SHEET 2 OF 5)
A10C	LEGEND - LINES AND SYMBOLS (SHEET 3 OF 5)
A10D	LEGEND - LINES AND SYMBOLS (SHEET 4 OF 5)
A10E	LEGEND - LINES AND SYMBOLS (SHEET 5 OF 5)
A10F	LEGEND - SOIL (SHEET 1 OF 2)
A10G	LEGEND — SOIL (SHEET 2 OF 2)
A10H	LEGEND - ROCK
A62C	LIMITS OF PAYMENT FOR EXCAVATION AND BACKFILL - BRIDGE SURCHARGE
	AND WALL
RSP B11-79	CONCRETE BARRIER TYPE 836 DETAILS No. 1
RSP B11-80	CONCRETE BARRIER TYPE 836 DETAILS No. 2





	ROAD NAME: MITCHELL ROAD	MAK!	<b>N</b> .
INE INCH ON L DRAWING	ROAD NO: C4J090	■ ■ THOMAS	
L DRAWING	FEMA NO.: 4301-DR-CA PW 1029	MILE POST: 1.15	DESIGNED BY:
NE INCH ON ET, ADJUST ACCORDINGLY	CONTRACT NO.: 217300	EA NO.:	DRAWN BY:
	DWG. FILE NAME:		REVIEWED BY:
	DATE: JANUARY 2019	REVISION DATE:	APPROVED BY:

COUNTY OF HUMBOLDT Department of Public Works	SHEET	
MITCHELL ROAD STORM DAMAGE PROJECT	14 OF	
INDEX TO PLAN	34	
INDEX IO PLAN		i

#### GENERAL NOTES:

DESIGN: AASHTO LRFD Bridge Design Specifications, 6th Edition with California Amendments.

LIVE LOAD: 240 psf equivalent to 2 feet soil weight.

SOIL PARAMETERS: (For determination of Design Lateral Earth Pressures)

Backfill soil weight = 120 lb/ft <sup>3</sup>
Friction Angle = 34.
Active Pressure coefficent, Ka = 0.283

SEISMIC PARAMETERS:

Active (seismic) pressure coefficient.  $k_e = \frac{0.092}{1}$ 

STEEL SOLDIER PILES:

ASTM A572/A, ASTM 572M Grade 50 Min, or ASTM A992

SHOTCRETE (FASCIA):

f'c = 4000 psify = 60 ksi

STRUCTURAL Treated

TIMBER: Douglas Fir, Grade No. 1 or better

Timber to be full sawn.

PRESTRESSING STEEL (GROUND ANCHORS):

Bars - ASTM Designation: A722 Type II (150 ksi) Strand Tendons - ASTM Designation: A416 (270 ksi

Low relaxation steel)

T = Design force on ground anchor (kips)

fpu = Minimum ultimate tesile strength of ground

anchor steel

As (Min) = Minimum cross sectional area ofsteel in ground anchor. (sq. in)

As (Min) = 1.0T (STRANDS) 0.75 fpu


As (Min) = 1.0T (BARS) 0.80 fpu

REINFORCED CONCRETE:

f'c = 3,200 psi (Concrete compressive strength

at 28 days)

fy = 60,000 psi (Yield strength of reinforcement)



#### STRUCTURE BACKFILL AND EXCAVATION

Indicates Structure Excavation, Soldier Pile Wall


Inicates Structure Backfill, Soldier Pile Wall

Indicates Permeable Material Class 3

#### NOTES:

- 1. Lagging and Backfill behind lagging shall be placed to at least 3'-0" above Ground Anchor prior to construction of the Anchor
- 2. Excavation shall not extend more than 3'-0" below a Ground Anchor until it is completely constructed and stressed
- 3. Contractor may submit alternative plans & details for approval by the Engineer
- 4. For limits of payments for roadway excavation, see "ROADWAY PLANS"





CURVE TABLE				
CURVE # RADIUS DELTA TANGENT LENGT				LENGTH
1 115.00' 21'34'45" 21		21.92'	43.31'	
2	1634.00'	6°25'33"	91.73'	183.26'
3	145.32'	15°05'55"	19.26'	38.29'
(4)	1635.55	4*52'36"	69.65	139.21'


 $\frac{\mathbf{PLAN}}{1" = 10},$ 

#### LEGEND

O - 24 inch diameter drilled hole

#### **BENCHMARK**

Coordinates for this survey are California Coordinate System of 1983 (CCS83) Zone 1, NAD 83, Epoch 2007.00 based on a static GPS Control Survey. The mapping angle is 1 degree 23 minutes 05 seconds— rotate bearings counterclockwise by this angle to obtain "True¢ or Geodetic bearings. Grid distances shown should be divided by the Combined Scale factor of 0.99988908 to obtain ground distances. Mapping angle and grid scale factor taken at Control Point No. 51. Horizontal control is in US Survey feet and is based on static GPS tie to NGS PID "LV1180", an NGS HPGN Network point at Murray Field in Eureka on above stated Epoch. Vertical control is also based on NGS PID "LV1180", NAVD 88 datum, with elevation of 6.10 feet.



## TYPICAL SECTION - GROUND ANCHOR WALL 1/4" = 1'-0"

#### NOTES:

- 1. For "SECTION B-B" and "SECTION C-C", see "SOLDIER PILE WALL LAGGING DETAILS" sheet.
- For "WALL DRAIN DETAIL", see "SOLDIER PILE WALL DETAILS No. 2" sheet.
- 3. Continue geocomposite drain under wall into permeable material




		RUAD NAME: MITCHELL ROAD	MAK!	N.	
BAR IS ONE INCH ON ORIGINAL DRAWING	ROAD NO: C4J090	■ ■ THOMAS			
	FEMA NO.: 4301-DR-CA PW 1029	MILE POST: 1.15	DESIGNED BY:	JB	
I	IF NOT ONE INCH ON THIS SHEET, ADJUST	CONTRACT NO.: 217300	EA NO.:	DRAWN BY:	GE
I		DWG. FILE NAME:		REVIEWED BY:	мь
SCALES ACCORDINGLY	DATE: JANUARY 2019	REVISION DATE:	APPROVED BY:	JH	
ľ					

COUNTY OF HUMBOLDT
DEPARTMENT OF PUBLIC WORKS

MITCHELL ROAD STORM DAMAGE PROJECT

TYPICAL SECTION

SHEET
16
OF
21



## TYPICAL SHOTCRETE FACING SECTION

1" = 1'-0'

PILE AND GROUND ANCHOR DATA TABLE						
	"RWLOL" LINE	TOP OF WALL	воттом оғ	PILE TIP	GROUND A	NCHORS
PILE NUMBER	STATION	ELEVATION	LAGGING ELEVATION	ELEVATION	Т	UNBONDED LENGTH
		(ft)	(ft)	(ft)	(kips)	(ft)
1	20+01.50	137.03	121.0	96.0	110	30.0
2	20+09.50	136.08	119.0	94.0	110	30.0
3	20+17.50	135.16	117.0	92.0	110	30.0
4	20+25.50	134.33	115.0	90.0	110	30.0
5	20+33.50	133.73	113.0	88.0	110	30.0
6	20+41.50	133.11	111.0	86.0	160	40.0
7	20+49.50	132.45	109.0	84.0	160	40.0
8	20+57.50	131.78	107.0	82.0	160	40.0
9	20+65.50	131.12	107.0	82.0	160	40.0
10	20+73.50	130.47	107.0	82.0	160	40.0
11	20+81.50	129.81	107.0	82.0	160	40.0
12	20+89.50	129.13	107.0	82.0	160	40.0
13	20+97.50	128.44	107.0	82.0	160	40.0
14	21+05.50	127.74	107.0	82.0	110	30.0
15	21+13.50	127.03	107.0	82.0	110	30.0
16	21+21.50	126.30	107.0	82.0	110	30.0
17	21+29.50	125.57	107.0	82.0	110	30.0
18	21+37.50	124.82	108.0	82.0	110	30.0
19	21+45.50	123.88	109.0	83.0	110	30.0
20	21+53.50	122.90	110.0	84.0	110	30.0
21	21+61.50	121.90	111.0	85.0	N/A	N/A
22	21+69.50	120.89	112.0	86.0	N/A	N/A
23	21+77.50	119.77	112.0	87.0	N/A	N/A
24	21+85.50	118.67	113.0	88.0	N/A	N/A



	ROAD NAME: MITCHELL ROAD	MAKI	K. I	COUNTY OF HUMBOLDT   SH	IEET
BAR IS ONE INCH ON ORIGINAL DRAWING	ROAD NO: C4J090	THO	MAS	DEPARTMENT OF PUBLIC WORKS	
	FEMA NO.: 4301-DR-CA PW 1029	MILE POST: 1.15	DESIGNED BY: JB	MITCHELL ROAD STORM DAMAGE PROJECT	
F NOT ONE INCH ON THIS SHEET, ADJUST	CONTRACT NO.: 217300	EA NO.:	DRAWN BY: GB		0F
	DWG. FILE NAME:		REVIEWED BY: MM	CONCRETE BARRIER SLAB DETAILS	
	DATE: JANUARY 2019	REVISION DATE:	APPROVED BY: JH	2	4 U J
				·	

#### NOTES:

- 1. Clearance to reinforcing steel in concrete barrier to be 1".
- 2. Not all barrier reinforcement shown.
- 3. No expansion joints in concrete barrier or barrier slab within wall limits.
- 4. Prepare and stain concrete on all exposed surfaces of concrete barrier.
- (A) 2" Min Expanded Polystyrene
- B 2" Expanded Polystyrene, see "SECTION A-A" for Soldier Pile
- © Contact joint
- D Pavement reinforcing fabric, see "ROADWAY PLANS"
- (E) 1/2" x 15 1/2" x 16" Cover Plate welded to the top of pile, see "SECTION Y—Y"

#### LEGEND:

Indicates 1" Expanded Polystyrene


Indicates 2" Min Expanded Polystyrene

Indicates Bearing Pad


 $\infty$  Indicates bundled bars

L	8'-0"	
	2'-0" 6'-0"	
CONCRETE BARRIER TYPE 836 (Mod)	2'-0"	
3,-0,	SEE NOTE 2  #5 Cont @ 15 Max (BUNDLED)  5'-6" @ 12	PAVING NOTCH  #5 6, @ 12,  HMA, SEE  HMA, PANDLE W/ #5 5'-6"
#5 Cont, Tot 5"		#5 @ 12
PREPARE AND STAIN CONCRETE  SHOTCRETE (FACIA)  2" CIT 6"	B #5 @ 12	© ————————————————————————————————————


## CONCRETE BARRIER SLAB WITH PAVING NOTCH 3/4" = 1'-0"











SECTION D-D


NO SCALE













18

SAME WIDTH AS LAGGING THICKNESS






#### **SECTION B-B**

NO SCALE




#### LAGGING DETAILS

NO SCALE




PART PLAN OF TIMBER LAGGING MEMBER NO SCALE



#### SECTION C-C

NO SCALE



SINGLE VEE-GROOVE

SINGLE BEVEL-GROOVE

#### FINISH COAT ON THE THREE EXPOSED PILE SURFACES (EXTERIOR FACE), SEE "TYPICAL SECTION" SHEET FOR LIMIT

LIMITS OF CLEAN & PAINT STEEL SOLDIER PILES

UNDERCOAT ON ALL

PILE SURFACES -

NO SCALE

#### NOTES:

- 1. No clipping of timber lagging corners allowed.
  Lagging corners may be chamfered to facilitate placement. Max 2 corner per logging
- 2. Spikes shall not be bent

## 1/8" $\phi \times 3 1/4$ ", COMMON NAIL (Galv) HIGH DENSITY POLYETHYLENE SHIM DETAIL NO SCALE





#### NOTES:

- 1. Single vee-groove and square groove permitted for all positions.
- 2. Single bevel-groove permitted for horizonal joints only.



Q WEB & 6" Ø DOUBLE-EXTRA STRONG (XX-STRONG) PIPE,







# P 1½ x 11 x 1'-6" SOLDIER PILE Typ ALL 4 SIDES

Тур

### SECTION D-D NO SCALE

## ELEVATION - SOLDIER PILE WITH SHGA THRU WEB






#### **BEARING PLATE**

NO SCALE

SECTION E-E


BEARING PLATE SHALL BE DESIGNED BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER FOR APPROVAL IN ACCORDANCE WITH THE STANDARD SPECIFICATION SECTION 50-1.01C.



TIMBER LAGGING


#### SOLDIER PILE WALL

NO SCALE




#### WALL DRAIN DETAIL AT WEEPHOLE

NO SCALE




#### **SECTION H-H**



#### WALL DRAIN DETAIL

NO SCALE



G GEOCOMPOSITE DRAIN

GEOCOMPOSITE DRAIN 3" Ø PERFORATED PVC PIPE ——— 90° PVC PIPE ELBOW CAP END

#### VIEW A-A NO SCALE

#### NOTES:

EA NO.:

REVISION DATE:

MARK
THOMAS

DESIGNED BY: JB

DRAWN BY: GB

REVIEWED BY: MM

APPROVED BY: JH

1. Geocomposite drain strip per Section 88 Geosynthetics of the Standard Specifications

COUNTY OF HUMBOLDT DEPARTMENT OF PUBLIC WORKS


MITCHELL ROAD STORM DAMAGE PROJECT

SOLDIER PILE WALL DETAILS NO. 2

20

21

2. Elevation of drains and weepholes as shown elsewhere on plans



#### PART ELEVATION DRAIN AT **SOLDIER PILE WALL**

NO SCALE

