RE: TOWN OF SAMOA SUBDIVISON PHASE 1 CONSISTING OF PHASES #1 THROUGH #9 OF APPLICATION #8827

FINAL MAP SUBDIVISION AGREEMENT

THIS AGREEMENT is executed:	n triplicate this day of, OF HUMBOLDT, a political subdivision of the State of
California, hereinafter called COUNTY at SUBDIVIDER.	ad SAMOA PACIFIC GROUP, LLC, hereinafter called
WITNESSETH:	
	_ SUBDIVIDER presented to the Board of Supervisors subdivision known as TOWN OF SAMOA

WHEREAS, COUNTY pursuant to Chapter 6 of Division 2 of Title III of the Humboldt County Code requires SUBDIVIDER to either complete all improvements required by the Humboldt County Code prior to the filing of the final map or enter into an improvements agreement which requires that the work on the required improvements be completed within the time specified; and

WHEREAS, the Board of Supervisors of COUNTY approved the final map subject to the execution of an improvements agreement between COUNTY and SUBDIVIDER pursuant to Chapter 6 of Division 2 of Title III of the Humboldt County Code; and

WHEREAS, SUBDIVIDER has presented to COUNTY improvement plans and specifications (hereinafter referred to as the "Improvement Plan") which are on file with the Public Works Department outlining therein the improvements to be constructed by SUBDIVIDER within the subdivision which are required by the Humboldt County Code as a condition precedent to the filing of the final map with the County Recorder; and

WHEREAS, SUBDIVIDER desires to complete the improvements described in the improvement plan after the final map is filed with the County Recorder and therefore desires to enter into this improvements agreement with the COUNTY;

NOW, THEREFORE, it is mutually agreed as follows:

(1) <u>FINAL MAP</u>

The term "final map" as defined in the Subdivision Map Act (Government Code sections 66410 *et seq.*) and the County Subdivision Ordinance (Division 2 of Title III of the Humboldt County Code), and as used in this agreement, shall refer to the map of the TOWN OF SAMOA SUBIVISION PHASE 1, which was conditionally approved by the Planning Commission of COUNTY on February 20, 2020. A copy of the final map is attached to this agreement as Exhibit A and incorporated by reference herein.

(2) **IMPROVEMENTS**

SUBDIVIDER, at their own expense, shall make all improvements required by Title III, Division 2 of the Humboldt County Code as set forth in the Improvement Plan, and the conditions of approval of the tentative subdivision map, which are attached hereto as Exhibit B and incorporated herein by reference. It is agreed by both parties that the Improvement Plan titled "Phase 1:Water & Sewer Improvement Plans" dated 06/09/2021 is in accordance with the conditions of the tentative subdivision map which was approved by the Public Works Department on 06/10/2021; and that the Improvement Plan titled "Vance Avenue Phase 1A Improvement Plans" dated 02/04/2020 is in accordance with the conditions of the tentative subdivision map which was approved by the Planning and Building Department on 03/10/2020.

SUBDIVIDER warrants that Improvement Plan is adequate to complete the improvements shown in the Improvement Plan in a good, workmanlike manner and in accordance with accepted construction practices. Should the Improvement Plan, at any time prior to completion of the work on the improvements, appear to be inadequate in any respect in the opinion of the Public Works Director or designee thereof, hereinafter referred to as "DIRECTOR," the SUBDIVIDER agrees to make such change in the Improvement Plan as the DIRECTOR determines are necessary to complete improvements according to the standards specified in Section 3 of this agreement.

(3) STANDARDS

All improvements provided for in the Improvement Plan shall be constructed in a good workmanlike manner, using accepted construction practices and in accordance with the standards contained in Title III, Division 2 of the Humboldt County Code. Improvements for which specifications are not provided by said ordinance or by this agreement shall be constructed in accordance with the standards required by the DIRECTOR.

All improvements shall be subject to inspection and approval by the DIRECTOR.

(4) COSTS

SUBDIVIDER shall have the sole responsibility for paying all costs associated with the construction of all improvements required by this agreement, including but not limited to all costs associated with the improvements described in the Improvement Plan; meeting all conditions of the tentative map and furnishing any and all required public utility services, including but not limited to installing all necessary public water, public sewer, gas, electrical and telephone facilities.

(5) **SERVICES**

All administration and inspection services rendered in connection with the work covered by this agreement shall be paid for by SUBDIVIDER in accordance with the latest Fee Schedule adopted by the Board of Supervisors. The cash deposit for administration and inspection fees required by Section 326-13 of the Humboldt County Code is set in the amount of \$10,000. SUBDIVIDER is responsible for costs above the deposit amount.

(6) <u>COMPLETION</u>

Pursuant to Humboldt County Code section 326-2(a), all improvements shall be completed, inspected, and approved by the DIRECTOR no later than two (2) years following recordation of the Final Map.

COUNTY shall not issue any building permits until such time as the DIRECTOR determines that the improvements are complete.

(7) <u>RIGHTS OF WAY</u>

SUBDIVIDER, at its own expense and as approved by the DIRECTOR, shall provide any and all restrictions, rights of way, street rights of way, and easements for drainage, utilities and/or other purposes.

(8) <u>GUARANTEE</u>

Pursuant to Humboldt County Code section 326-2(b), SUBDIVIDER guarantees that all improvements and associated equipment required by this agreement, including but not limited to street surfacing, sidewalks, curbs and gutters, culverts, bridges and storm drains, shall be free from defects of material or workmanship and shall perform satisfactorily for a period of at least one year from and after acceptance of such improvements as complete, and the SUBDIVIDER shall repair any defects in these improvements or replace any defective improvements which cannot be repaired which occur or arise within the one year period at SUBDIVIDER's own expense.

(9) HOLD HARMLESS

- (a) SUBDIVIDER shall hold COUNTY and its officers, employees, agents, volunteers, and representatives harmless against any and all damages arising out of the construction, maintenance, design, drainage, operation, and/or use of said subdivision including without limitation improvements specified in Section (2), and shall indemnify and defend the COUNTY against all claims. SUBDIVIDER shall also hold COUNTY and its officers, employees, agents, volunteers, and representatives harmless against any and all damages arising out of SUBDIVIDER's activities and operations in connection with the use, maintenance, design, and/or construction of the improvements in said subdivision prior to acceptance by COUNTY into the County Maintained Road System, and shall_indemnify and defend the COUNTY against all claims. Insofar as said improvements are concerned, prior to acceptance into the County Maintained Road System, SUBDIVIDER shall likewise hold COUNTY harmless from any and all liability that may occur by reason of flooding and the deposit of debris, or either of such occurrences, caused either by the construction of the subdivision or lack of continuance of construction operations once commenced, and_shall indemnify and defend the COUNTY against all claims.
- (b) SUBDIVIDER shall hold COUNTY, its officers, employees, agents, volunteers, and representatives harmless against any and all damages by reason of injury to property arising out of design of the subdivision occurring within five years of the acceptance of the improvements.

(10) <u>INSURANCE</u>

This Agreement shall not be executed by COUNTY and the SUBDIVIDER is not entitled to any rights, unless certificates of insurance, or other sufficient proof that the following provisions have been complied with, and such certificates are filed with the Clerk of the Humboldt County Board of Supervisors.

(a) <u>General Insurance Requirements</u>. Without limiting SUBDIVIDER's indemnification obligations set forth herein, SUBDIVIDER, and its contractors and subcontractors, shall take out and maintain, throughout the term of this Agreement, and any extensions thereof,

the following policies of insurance, placed with insurers authorized to do business in the State of California with a current A.M. Bests rating of no less than A: VII or its equivalent against personal injury, death and property damage which may arise from, or in connection with, the activities of SUBDIVIDER and its agents, officers, directors, employees, assignees or subcontractors:

- 1. Comprehensive or Commercial General Liability Insurance at least as broad as Insurance Services Office Commercial General Liability coverage (occurrence from CG 0001) in an amount of \$2,000,000.00 per occurrence. If work involves explosive, underground, or collapse risks, XCU must be included. If a general aggregate limit is used, either the general aggregate limit shall apply separately to this project or the general aggregate shall be twice the required occurrence limit.
- 2. SUBDIVIDER shall take out and maintain Automobile/Motor Liability Insurance with a limit of liability not less than One Million Dollars (\$1,000,000.00) combined single limit coverage. Such insurance shall include coverage of all owned, hired and non-owned vehicles, and be at least as broad as Insurance Service Offices Form Code 1 (any auto).
- 3. Workers' Compensation Insurance, as required by the California Labor Code, with statutory limits, and Employers Liability Insurance with a limit of no less than One Million Dollars (\$1,000,000.00) per accident for bodily injury or disease. Said policy shall contain, or be endorsed to contain, a waiver of subrogation against COUNTY and its agents, officers, officials, employees and volunteers, except for the negligence or willful misconduct of COUNTY and its agents, officers, employees and volunteers.
- (b) <u>Special Insurance Requirements</u>. Said policies shall, unless otherwise specified herein, be endorsed with the following provisions:
 - 1. The Comprehensive or Commercial General Liability Policy shall provide that COUNTY, and its agents, officers, officials, employees, and volunteers are covered as additional insured for liability arising out of the operations performed by or on behalf of SUBDIVIDER. The coverage shall contain no special limitations on the scope of protection afforded to the COUNTY, its officers, agents, and employees.
 - a. Includes contractual liability.
 - b. Does not contain exclusions as to property damage caused by explosion or collapse of structures or underground damage, commonly referred to as "XCU Hazards."
 - c. Is the primary insurance with regard to COUNTY.
 - d. Does not contain a pro-rata, excess only and/or escape clause.
 - e. Contains a cross liability, severability of interest or separation of insureds clause.

- The above-referenced policies shall not be canceled or materially reduced in 2. coverage without thirty (30) days prior written notice (10 days for non-payment of the premium). being provided to COUNTY in accordance with the notice requirements set forth herein. It is further understood that SUBDIVIDER shall not terminate such coverage until COUNTY receives adequate proof that equal or better insurance has been secured.
- The inclusion of more than one insurance shall not operate to impair the rights of 3. one insured against another insured, and the coverage afforded shall apply as though separate policies had been issued to each insured, but the inclusion of more than one insured shall not operate to increase the limits of the insurer's liability.
- For claims related to this project, the SUBDIVIDER's insurance is primary 4. coverage to the COUNTY, and any insurance or self-insurance programs maintained by the COUNTY are excess to SUBDIVIDER's insurance and will not be called upon to contribute with it.
- Any failure to comply with reporting or other provisions of the parties, including 5. breach of warranties, shall not affect coverage provided to COUNTY, or its agents, officers, officials, employees, and volunteers.
- SUBDIVIDER shall furnish COUNTY with certificates and original endorsements (c) effecting the required coverage prior to execution of this Agreement by COUNTY. The endorsements shall be on forms as approved by the County Risk Manager or County Counsel. Any deductible or self-insured retention over \$100,000.00 shall be disclosed to and approved by COUNTY. If SUBDIVIDER does not keep all required policies in full force and effect, COUNTY may, in addition to other remedies under this Agreement, take out the necessary insurance, and SUBDIVIDER agrees to pay the cost of said insurance.

(11)**SECURITY**

(a) Faithful Performance Security

In accordance with Section 66499 of the Government Code, SUBDIVIDER, at their sole expense, shall furnish COUNTY good and sufficient security in the sum of \$8,606,000 for the faithful performance of the provisions of this agreement requiring the construction of all improvements required by this agreement and associated equipment, including but not limited to street surfacing, sidewalks, curbs and gutters, culverts, bridges, and storm drains. Said security shall be maintained in full force and effect until the conditions thereof shall have been completely performed. The Humboldt County Board of Supervisors may, at its sole discretion and by official action, lower the amount of said security for faithful performance from time to time as portions of the improvements required by this agreement have been made.

(b) Payment Security

SUBDIVIDER shall furnish additional good and sufficient security in the sum of \$4,304,000, securing payment to the contractor, their subcontractors, and to persons renting equipment or furnishing labor, materials, or equipment. This security may, unless an appropriate waiver and release have been executed pursuant to Civil Code section 8122 et seq., after the passage of the time within which claims of lien are required to be recorded pursuant to Article 2 (commencing with Section 8410) of Chapter 4 of Title 2 of Part 6 of Division 4 of the Civil Code and after acceptance of the work by COUNTY, be reduced to an amount equal to the total claimed by all claimants for whom claims of lien have been recorded and notice thereof given in writing to the Humboldt County Board of Supervisors, and if no such claims have been recorded at the expiration of such time, the security shall be released in full.

If the security provided is not in the form of a bond and in the event the security for payment under this section becomes insufficient to pay all valid claims properly submitted, then the unencumbered balance, if any, of the other securities may be used for payment of such claims.

(c) Guarantee and Expenses Security

SUBDIVIDER shall furnish security in the sum of \$431,000, securing SUBDIVIDER's one-year guarantee of all work performed under this agreement. SUBDIVIDER shall also furnish security in the sum of \$431,000, securing payment of costs and reasonable expenses and fees, including attorney's fees, incurred by COUNTY in successfully enforcing this agreement. Said security shall be maintained until expiration of the one-year guarantee period set forth in Humboldt County Code section 326-2(b); thereafter, the Humboldt County Board of Supervisors may release such security. DIRECTOR shall furnish subdivider with the date upon which the one-year guarantee period commences.

(d) Monument Security

In accordance with Section 66496 of the Government Code, SUBDIVIDER has delivered to COUNTY the engineer's or surveyor's certificate which certifies on the final map where the monuments will be set. If the certificate states that the monuments will be set on or before a specified later date, SUBDIVIDER, at their sole expense, shall furnish COUNTY a good and sufficient corporate surety bond or a cash deposit in the amount of \$111,020 guaranteeing payment for the actual cost of the setting of the monuments.

If the security provided is not in the form of a bond and in the event the cash deposit under this section becomes insufficient to pay the actual cost of the setting of the monuments, then the unencumbered balance, if any, of the other securities may be used for payment of such costs.

(e) Tax Security

In accordance with Government Code section 66493, SUBDIVIDER, at their sole expense, shall furnish to COUNTY a good and sufficient surety bond approved by the Humboldt County Board of Supervisors, or in lieu thereof, a deposit of money or negotiable bonds of a kind approved for securing deposits of public money in the sum of \$0 for the benefit of COUNTY securing payment of all state, county, municipal, and local taxes and the current installment of principal and interest of all special assessments collected as taxes, which at the time the subdivision map is recorded are a lien against the property, but which are not yet payable.

(12) RELEASE OF SECURITY

(a) Pursuant to County Code Section 326-6.3, DIRECTOR may grant partial releases of Faithful Performance Security, Payment Security, and Monument Security as long as sufficient security remains to cover uncompleted work.

- (b) When the DIRECTOR has determined that work has been completed, the applicable Faithful Performance Security, Payment Security, and Monument Security may be released.
- (c) At the conclusion of the 12-month guarantee period and all remaining security may be released when the DIRECTOR has determined that all work is free from defects of material or workmanship and that the improvements perform satisfactorily.

(13) <u>DEFAULT ON SURETY BOND</u>

Should SUBDIVIDER fail to make all improvements required by this agreement within the time period herein specified, or should any improvements thereof fail to meet the standards imposed by this agreement and the security provided is in the form of a security bond, then COUNTY may elect to do the following:

- (a) Give to SUBDIVIDER and its surety a notice requiring that said improvements or any part thereof be completed and/or brought up to the standards required by the terms of this agreement within a 30-day period, together with a statement that if this is not done, surety will be required to complete and/or bring up to standards the improvements or parts thereof.
- (b) Upon failure of SUBDIVIDER to comply with the 30-day notice contained in subsection (a) of this paragraph, give to SUBDIVIDER and to said surety a notice demanding that the matters required in the notice given under subsection (a) of this paragraph be performed by said surety within a 30-day period, stating that if this is not done, such matters may be performed by COUNTY, either directly or indirectly by contracting with an outside contractor. In the event of such performance by COUNTY or an outside contractor hired by COUNTY, SUBDIVIDER and said surety shall be liable to COUNTY for all costs of such performance.

(14) <u>DEFAULT - CASH SURETY OR INSTRUMENT OF CREDIT</u>

Should SUBDIVIDER fail to make all the improvements required by this agreement within the time specified, or should such improvements or any part thereof fail to meet the standard imposed by this agreement and SUBDIVIDER has provided security other than in the form of a security bond, COUNTY may elect to give to SUBDIVIDER a notice requiring that said improvements or any part thereof be completed and/or brought up to standards imposed by this agreement within a 30-day period, together with a statement that if this is not done, such matters may be performed by COUNTY either directly or indirectly by contracting with an outside contractor. In the event of such performance by COUNTY or an outside contractor hired by COUNTY, SUBDIVIDER shall be liable to COUNTY for all costs of such performance. Such costs may be collected from SUBDIVIDER's security, and from SUBDIVIDER, if the costs exceed the amount of the security.

(15) <u>CONFLICT</u>

In the event of conflict between this agreement and applicable state laws or local ordinances, the applicable provisions of law shall prevail.

(16) **NOTICE**

Any notice that is provided for herein to be given to SUBDIVIDER shall be deemed to be given when it is placed in the United States mail, first class and postage prepaid, addressed to

SUBDIVIDER at 5251 Ericson Way, Ste A, Arcata Ca 95521, or such other address as SUBDIVIDER may designate by written notice filed with the Clerk of the Humboldt County Board of Supervisors.

(17) **TERMINATION**

(a) Pursuant to Humboldt County Code section 326-2(a), the SUBDIVIDER may request that this agreement be terminated, and all security released if the land subject to this agreement has been reverted to acreage in conformance with Humboldt County Code section 327-1 *et seq*.

In the event that the SUBDIVIDER has not commenced any work subject to this agreement, DIRECTOR may grant a full release of Faithful Performance Security, Payment Security, Guarantee and Expenses Security, and Monument Security.

In the event that the SUBDIVIDER has commenced with any work subject to this agreement, the DIRECTOR may require the SUBDIVIDER to bring that work to a logical point of conclusion prior to this agreement being terminated. DIRECTOR may grant a full release of Faithful Performance Security, Payment Security, and Monument Security. DIRECTOR may grant a partial release of Guarantee and Expenses Security, retaining a portion sufficient to cover the 12-month guarantee period. DIRECTOR shall furnish subdivider with the date upon which the one-year guarantee period commences. At the conclusion of the 12-month guarantee period, all remaining security may be released when the DIRECTOR has determined that all work is free from defects of material or workmanship and that the improvements perform satisfactorily.

- (b) This agreement may be terminated at the conclusion of the 12-month guarantee period and all remaining security may be released when the DIRECTOR has determined that all work is free from defects of material or workmanship and that the improvements perform satisfactorily.
- (c) This agreement shall not be terminated until any outstanding charges for Services provided in Section 5 have been paid in full.

(18) <u>AMENDMENT</u>

The terms of this agreement may be amended only in writing with the consent of both parties.

(19) ASSIGNMENT

SUBDIVIDER shall not assign its obligations, duties, or rights hereunder, either in whole or in part, without COUNTY's prior written consent. Any assignment by SUBDIVIDER in violation of this provision shall be void.

(20) AGREEMENT SHALL BIND SUCCESSORS

All provisions of this Agreement shall be fully binding upon, and inure to the benefit of, the parties and to each of their heirs, executors, administrators, transfers, successors and permitted assigns.

IN WITNESS WHEREOF, the parties hereto have caused this agreement to be executed by their duly authorized officers the day and year first above written.

(SEAL) ATTEST:	SUBDIVIDER:
CLERK OF THE BOARD	SAMOA PACIFIC GROUP, LLC
BY	BY DANIEL J. JOHNSON, MEMBER
INSURANCE CERTIFICATES REVIEWED AND APPROVED	COUNTY OF HUMBOLDT
BY RISK MANAGER	CHAIR, BOARD OF SUPERVISORS COUNTY OF HUMBOLDT, STATE OF CALIFORNIA

EXHIBITA

OWNER'S STATEMENT

THAT THE UNDERSIGNED, BEING THE PARTIES HAVING A RECORD TITLE INTEREST IN THE REAL PROPERTY BEING SUBDIVIDED BY THIS MAP, DO HEREBY CONSENT TO THE PREPARATION AND RECORDATION OF THIS MAP AND TO THE DEDICATION OF THE EASEMENTS FOR THE PURPOSES SHOWN HEREON. THE EXPRESSED RIGHTS

TO THE PUBLIC IN GENERAL AND TO THE SEVERAL UTILITY COMPANIES SHALL BE AND SHALL REMAIN INFERIOR TO THE SUPERIOR RIGHTS OF THE COUNTY OF HUMBOLDT.
SAMOA PACIFIC GROUP, LLC DATED 5-10-202
BY: DANIEL J. JOHNSON, MEMBER
DATED 5-10-2021
LEENDERT DEVRIES, BENEFICIARY OF A DEED OF TRUST RECORDED ON JUNE 8, 2001 AS INSTRUMENT NO. 2001-14061-15, HUMBOLDT COUNTY RECORDS
Fragryn Deller DATED 5-10-21
KATHRYN DEVRIES, BENEFICIARY OF A DEED OF TRUST RECORDED ON JUNE 8, 2001 AS INSTRUMENT NO. 2001-14061-15, HUMBOLDT COUNTY RECORDS
WORLD FLOWER, B.V. A NETHERLANDS COMPANY AND ROOYAKKERS, B.V. A NETHERLANDS COMPANY, BENEFICIARY OF A DEED OF TRUST RECORDED ON JUNE 8, 2001 AS INSTRUMENT NO. 2001-14061-15, HUMBOLDT COUNTY RECORDS
BY: DATED_ 5-1V- 2021
PRINTED NAME: LEENDERT DEVRIES TITLE: SPECIAL AGENT
COUNTY OF HUMBOLDT, BENEFICIARY OF DEEDS OF TRUST RECORDED: MAY 30, 2014 AS INSTRUMENT NO. 2014-009496-6, HUMBOLDT COUNTY RECORDS MAY 10, 2018 AS INSTRUMENT NO. 2018-008706, HUMBOLDT COUNTY RECORDS MAY J0, 2018 AS INSTRUMENT NO. 2018-008707, HUMBOLDT COUNTY RECORDS
BY: 5-21-21
PRINTED NAME: Army Nilsen TITLE: County Alministrative Office
TAY COLVECTION CONTRACTOR -
TAX COLLECTOR'S CERTIFICATE 1, JOHN BARTHOLOMEW, TAX COLLECTOR OF HUMBOLDT COUNTY, CALIFORNIA.
HERBBY CERTIFY THAT ACCORDING TO RECORDS OF THIS OFFICE, AS OF THIS DATE, THERE ARE NO TAX LIENS CURRENTLY DUE AGAINST THE LAND WITHIN THIS SUBDIVISION OR PARCEL DESCRIPTION DESCRIBED AS ASSESSOR'S PARCELS NO. 401-031-055 AND 401-031-070 FOR UNPAID COUNTY TAXES OR SPECIAL ASSESSMENTS.
I FURTHER CERTIFY THAT TAXES OR ASSESSMENTS WHICH WILL BECOME A LIEN ON THE PROPERTY, BUT WHICH ARE NOT YET CURRENTLY DUE, ARE ESTIMATED AT \$ 1944 AND THAT A BOND IN THIS AMOUNT HAS BEEN COLLECTED AND DEPOSITED WITH THIS OFFICE ON BEHALF OF THE BOARD OF SUPERVISORS.
JOHN BARTHOLOMEW HYMING DT COUNTY TANCOLLECTOR BY: WWW DEPUTY DATE: W/24/2021 PRINTED NAME: SMANNIN WISON
THE TANKS OF SETTINGS OF SETTINGS
CLERK OF THE BOARD STATEMENT
I, KATHY HAYES, CLERK OF THE BOARD OF SUPERVISORS OF THE COUNTY OF HUMBOLDT, STATE OF CALIFORNIA, HEREBY CERTIFY THAT SAID BOARD OF SUPERVISORS, AT A MEETING HELD ON 20, AT WHICH A QUORUM WAS PRESENT, APPROVED THE SUBDIVISION MAP. SAID BOARD ACCEPTED THOSE PARCELS OF LAND AND EASEMENTS AS OFFERED FOR DEDICATION FOR THE USES SET FORTH ON THE ACCOMPANYING SUBDIVISION MAP IN CONFORMITY WITH THE TERMS AND DEDICATIONS SUMMARIZED AS FOLLOWS:
BAY VIEW AVENUE - PUBLIC UTILITY EASEMENT ONLY CADMAN COURT - PUBLIC UTILITY EASEMENT ONLY CHURCH COURT - PUBLIC UTILITY EASEMENT ONLY CHURCH COURT - PUBLIC UTILITY EASEMENT ONLY
CUTTEN STREET - PUBLIC UTILITY EASEMENT ONLY FENWICK AVENUE - PUBLIC UTILITY EASEMENT ONLY MURPHY AVENUE - PUBLIC UTILITY EASEMENT ONLY PACIFIC COURT - PUBLIC UTILITY EASEMENT ONLY RIDEOUT STREET - PUBLIC UTILITY EASEMENT ONLY SAMOA COURT - PUBLIC UTILITY EASEMENT ONLY SUNSET AVENUE - PUBLIC UTILITY EASEMENT ONLY PUBLIC UTILITY EASEMENT ONLY PUBLIC UTILITY EASEMENT ONLY PARCEL D - PUBLIC UTILITY EASEMENT
I FURTHER CERTIFY TO THE ABANDONMENT OF THE EASEMENTS AS DESCRIBED IN THE ABANDONMENT STATEMENT HEREON, BY THE FILING OF THIS MAP, PURSUANT TO SECTION 66434(g) OF THE GOVERNMENT CODE.
KATHY HAYES CLERK OF THE BOARD OF SUPERVISORS
BY: DEPUTY DATE:

PRINT NAME

NOTARY ACKNOWLEDGMENT

A NOTARY PUBLIC OR OTHER OFFICER COMPLETING THIS CERTIFICATE VERIFIES ONLY THE IDENTITY OF THE INDIVIDUAL WHO SIGNED THE DOCUMENT TO WHICH THIS CERTIFICATE IS ATTACHED, AND NOT THE TRUTHFULNESS, ACCURACY, OR VALIDITY OF THAT DOCUMENT,

STATE OF CALIFORNIA

COUNTY OF HUMBOLAT

on May 10, 2021 BEFORE ME, HAIRY DEL APPEARED DANIEL V. Johnson	NOTARY PUBLIC, PERSONALLY , WHO PROVED TO ME ON THE
BASIS OF SATISFACTORY EVIDENCE TO BE THE ITO THE WITHIN INSTRUMENT AND ACKNOWLED THE SAME IN HIS/HER/THEIR AUTHORIZED CAPASIGNATURE(S) ON THE INSTRUMENT THE PERSON WHICH THE PERSON(S) ACTED, EXECUTED THE I	OGED TO ME THAT HE/SHEATHEY EXECUTED ACITY(198), AND THAT BY HIS/HER/THEIR NOW OR THE ENTITY LIPON BEHALF OF
I CERTIFY UNDER PENALTY OF PERJURY UNDER THAT THE FOREGOING PARAGRAPH IS TRUE ANI	
WITNESS MY HAND AND OFFICIAL SEAL:	MY PRINCIPAL PLACE OF BUSINESS IS IN
SIGNATURE JULIAN WORLD	Humboldt COUNTY
PRINTED NAME Hailty Del Grande	MY COMMISSION EXPIRES 8-24-23
(OFFICIAL SEAL NOT REQUIRED) NOTARY ACKNOWL	FDGMENT
TOTALL ACIDIO WE	EDGIVIENT
A NOTARY PUBLIC OR OTHER OFFICER COMI ONLY THE IDENTITY OF THE INDIVIDUAL WE WHICH THIS CERTIFICATE IS ATTACHED, AN ACCURACY, OR VALIDITY OF THAT DOCUME	O SIGNED THE DOCUMENT TO D NOT THE TRUTHFULNESS,
STATE OF CALIFORNIA	
COUNTY OF HYMBOLAT	
on May 10,2021 before me, Hailey De appeared Leendert Devrics and Kath	LYAYAL NOTARY PUBLIC, PERSONALLY ITYN DAYYES WHO PROVED TO ME ON THE
BASIS OF SATISFACTORY EVIDENCE TO BE THE I TO THE WITHIN INSTRUMENT AND ACKNOWLED THE SAME IN HISAHER/THEIR AUTHORIZED CAPA SIGNATURE(S) ON THE INSTRUMENT THE PERSO WHICH THE PERSON(S) ACTED, EXECUTED THE I	OGED TO ME THAT H E/SHE /THEY EXECUTED CITY(IES), AND THAT BY HS/HER /THEIR N(S), OR THE ENTITY UPON BEHALF OF
I CERTIFY UNDER PENALTY OF PERIURY UNDER THAT THE FOREGOING PARAGRAPH IS TRUE AND	
WITNESS MY HAND AND OFFICIAL SEAL:	MY PRINCIPAL PLACE OF BUSINESS IS IN
SIGNATURE JULIEN DELEMENTAL	HUMPO WT
PRINTED NAME HAILY DX GIVANAC (OFFICIAL SEAL NOT REQUIRED)	MY COMMISSION EXPIRES 8-24-23
NOTARY ACKNOWLI	EDGMENT '
A NOTARY PUBLIC OR OTHER OFFICER COMPONLY THE IDENTITY OF THE INDIVIDUAL WHEWHICH THIS CERTIFICATE IS ATTACHED, AND ACCURACY, OR VALIDITY OF THAT DOCUMEN	O SIGNED THE DOCUMENT TO D NOT THE TRUTHFULNESS,
STATE OF CALIFORNIA	
COUNTY OF Humbald+	
ON May 10, 2021 BEFORE ME, Haity D APPEARED LEONOCHT DENTICS	K) GYAYM NOTARY PUBLIC, PERSONALLY , WHO PROVED TO ME ON THE
BASIS OF SATISFACTORY EVIDENCE TO BE THE F TO THE WITHIN INSTRUMENT AND ACKNOWLED THE SAME IN HIS/HER/THEIR AUTHORIZED CAPA SIGNATURE(S) ON THE INSTRUMENT THE PERSON WHICH THE PERSON(S) ACTED, EXECUTED THE IN	PERSON(S) WHOSE NAME(S) IS/ARE SUBSCRIBED GED TO ME THAT HE/SHE/THEY EXECUTED CITY(LES), AND THAT BY HISA LEATHEIR N(S), OR THE ENTITY UPON BEHALF OF
I CERTIFY UNDER PENALTY OF PERJURY UNDER THAT THE FOREGOING PARAGRAPH IS TRUE AND	THE LAWS OF THE STATE OF CALIFORNIA
WITNESS MY HAND AND OFFICIAL SEAL:	MY PRINCIPAL PLACE OF BUSINESS IS IN
SIGNATURE Aprile Delemende	HUMPAIAT COUNTY
PRINTED NAME HAILY DEL GRANDE (OFFICIAL SEAL NOT REQUIRED)	MY COMMISSION EXPIRES 8-24-23

SEE SHEET 2 FOR ADDITIONAL NOTARY ACKNOWLEDGEMENT

SEE SHEET 15 FOR COUNTY DEDICATIONS, EASEMENTS CREATED BY THIS MAP. EASEMENTS OF RECORD, ABANDONMENT STATEMENT AND SURVEY NOTES.

NON-COUNTY LANE NOTE

IF THE PRIVATE LANE OR LANES SHOWN ON THIS PLAN OF SUBDIVISION, OR ANY PART $\,$ THEREOF, ARE TO BE ACCEPTED BY THE COUNTY FOR THE BENEFIT OF THE LOT OWNERS ON SUCH LANE RATHER THAN THE BENEFITS OF THE COUNTY GENERALLY, SUCH PRIVATE LANE OR LANES OR PARTS THEREOF SHALL FIRST BE IMPROVED AT THE SOLE COST OF THE AFFECTED LOT OWNER OR OWNERS, SO AS TO COMPLY WITH THE SPECIFICATIONS AS CONTAINED IN THE THEN-APPLICABLE SUBDIVISION REGULATIONS RELATING TO PUBLIC STREETS.

COUNTY RECORDER'S STATEMENT

FILED THIS	DAY OF	2021 AT _
IN BOOK	OF MAPS, PAGES	
COUNTY RECOR	DS AT THE REQUEST OF KEI	LLY-O'HERN ASSOCIA
KELLY E. SANDI HUMBOLDT COI	ER\$ JNTY RECORDER	
BY:	DEF	PUTY
PRINT NAM	E	
FEE:		
INSTRUMENT NO	n.	

COUNTY SURVEYOR'S STATEMENT

I HEREBY STATE THAT I HAVE EXAMINED THIS MAP; THAT THE SUBDIVISION, AS SHOWN, IS SUBSTANTIALLY THE SAME AS IT APPEARED ON THE TENTATIVE MAP AND ANY APPROVED ALTERATIONS THEREOF; THAT ALL PROVISIONS OF THE SUBDIVISION MAP ACT AND OF ANY LOCAL SUBDIVISION ORDINANCES OF THE COUNTY OF HUMBOLDT APPLICABLE AT THE TIME OF APPROVAL OF THE TENTATIVE MAP HAVE BEEN COMPLIED WITH; AND THAT I AM SATISFIED THAT THIS MAP IS TECHNICALLY CORRECT.

RONALD C. GARTON PLS 7177 HUMBOLDT COUNTY SURVEYOR

DATE

SURVEYOR'S STATEMENT

THIS MAP WAS PREPARED BY ME OR UNDER MY DIRECTION AND IS BASED UPON A FIELD SURVEY IN CONFORMANCE WITH THE REQUIREMENTS OF THE SUBDIVISION MAP ACT AND LOCAL ORDINANCE AT THE REQUEST OF DAN JOHNSON IN JUNE 2020. I HEREBY STATE THAT ALL THE MONUMENTS ARE OF THE CHARACTER. AND OCCUPY THE POSITIONS INDICATED, OR THAT THEY WILL BE SET IN THOSE POSITIONS BEFORE JULY 2022, AND THAT THE MONUMENTS ARE, OR WILL BE, SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED, AND THAT THIS FINAL MAP SUBSTANTIALLY CONFORMS TO THE CONDITIONALLY APPROVED TENTATIVE MAP. I HEREBY STATE THAT SAID SURVEY IS TRUE AND COMPLETE

Michael J. O'Her

MICHAEL J. O'HERN LS 4829

JUNE 19, 2021

J. O'HERN

MICHAEL

TRACT NO. TOWN OF SAMOA SUBDIVISION PHASE 1

SAMOA PACIFIC GROUP, LLC


SECTIONS 16 & 17 T5N, R1W, HUMBOLDT MERIDIAN IN THE UNINCORPORATED AREA OF HUMBOLDT COUNTY MARCH 2021


> **HUMBOLDT COUNTY** STATE OF CALIFORNIA


KELLY-O'HERN ASSOCIATES EUREKA, CALIFORNIA


SHEET 1 OF 15 SHEETS


BOOK OF MAPS, PAGE



































I IN TO THE PARTY				
LINE TABLE		VE TABLE J	SURVEY NOTES	EASEMENTS CREATED BY THIS MAP
BEARING DISTANCE	RADIUS DELTA LENGTH	RADIUS DELTA LENGTH C63 970.00 2°57'28" 50.07 R1&M C64 1652.09 0°15'30" 7.45 C65 1652.09 4°03'19" 116.93 C66 11.50 90°17'50" i8.12 C67 20.00 89°42'43" 31.32	A. THIS MAP REPRESENTS THE SUBDIVISION OF PARCEL TWO OF PARCEL MAP NO. 3606, FILED IN BOOK 36 OF PARCEL MAPS, PAGES 31 - 35, HUMBOLDT COUNTY RECORDS, INTO 136 LOTS AND A REMAINDER. B. THIS SURVEY IS BASED ON BOOK 36 OF PARCEL MAPS, PAGES 31 - 35, HUMBOLDT COUNTY RECORDS.	BAY VIEW AVENUE, CADMAN COURT, CUTTEN STREET, FENWICK AVENUE, MURPHY AVENUE, PACIFIC COURT, RIDEOUT STREET, SAMOA COURT, SUNSET AVENUE, SUNSET CIRCLE AND SUNSET EXTENSION ARE NON-EXCLUSIVE EASEMENTS FOR INGRESS, EGRESS AND PUBLIC UTILITIES FOR THE BENEFIT OF ALL LOTS IN PHASE I AND FUTURE PHASES OF THIS SUBDIVISION. PARCEL A - A NON-EXCLUSIVE EASEMENT, OF VARYING WIDTHS, FOR INGRESS AND
L7 S13°45'24'E 9.03 L8 S13°42'44"E 16.98 L9 S77°48'30"E 7.69 L10 N3°42'17"W 57.28 L11 N71°31'35"E 21.76 L12 N78°25'16"E 7.50 L13 N65°59'52"E 24.12 L14 N62°35'20"W 4.00 L15 N77°24'48"E 24.00 L16 NOT USED L17 NOT USED L18 NOT USED L19 NOT USED L19 NOT USED L10 S84°16'58"W 16.41 L21 S43°01'18"W 31.15 R1&M	C6 10.00 89°48′06″ 15.67 C7 .17.00 90°14′19″ 26.77 C8 17.00 90°14′19″ 26.77 C8 17.00 90°11′55″ 16.61 C9 22.00 62°53′52″ 24.15 C10 10.00 90°11′53″ 15.74 C11 10.00 90°07′33″ 15.73 C12 92.00 23°24′54″ 37.60 C13 25.00 66°24′53″ 28.98 C14 100.00 23°24′54″ 40.87 C15 140.00 49°29′21″ 120.93 C16 25.00 87°21′30″ 38.12 C17 10.00 89°52′27″ 15.69 C18 108.00 11°25′919″ 22.60 C19 108.00 11°25′919″ 22.60 C19 108.00 11°25′919″ 18.42 C20 132.00 7°59′44″ 18.42 C21 89.83 50°14′43″ 78.78	C68 15.00 92°19'21" 24.17 C69 220.00 4°51'17" 18.64 C70 15.00 86°07'05" 22.55 C71 220.00 14°51'01" 57.02 C72 180.00 19°13'23" 60.39 C73 220.00 13°51'05" 53.18 C74 220.00 10°35'00" 40.64 C75 220.00 4°45'14" 18.25 C76 37.50 94°25'42" 61.80 C77 200.00 48°53'36" 170.67 C78 57.50 94°25'42" 94.76 C79 180.00 16°44'27" 52.59 C80 77.50 94°25'42" 127.73 C81 738.00 3°32'238" 45.65 C82 750.00 4°30'33" 59.03 C83 762.00 4°20'26" 57.73	C. ACCESS ALONG VANCE AVENUE IS BASED ON THE RESERVATION ON A NON- EXCLUSIVE EASEMENT FOR INGRESS, EGRESS AND PUBLIC UTILITIES IN INSTRUMENT NO. 2019-004589, HUMBOLDT COUNTY RECORDS. D. EASEMENTS AND OTHER ENCUMBRANCES THAT AFFECT THE REMAINDER ONLY ARE NOT SHOWN HEREON. E. VARIOUS PUBLIC EASEMENTS ARE BEING ABANDONED BY THE FILING OF THIS MAP. SEE ABANDONMENT STATEMENT HEREON. F. THE BASIS OF BEARINGS OF THIS MAP IS BOOK 60 OF SURVEYS, PAGES 56 - 59, AS SHOWN ON SHEET 12 OF THIS MAP, THIS BASIS OF BEARINGS IS THE SAME AS BOOK 36 OF PARCEL MAPS, PAGES 31 - 35. G. ALL ROADS SHOWN HEREON ARE NON-COUNTY MAINTAINED, EXCEPT FOR NEW NAVY BASE ROAD.	EGRESS FOR THE BENEFIT OF LOTS 104, 105, 106 AND 107 OF THIS SUBDIVISION. PARCEL B - A NON-EXCLUSIVE EASEMENT, THIRTY TWO (32) FEET IN WIDTH, FOR INGRESS, EGRESS AND PUBLIC UTILITIES FOR THE BENEFIT OF LOTS 124 AND 125 OF THIS SUBDIVISION. PARCEL C - A NON-EXCLUSIVE EASEMENT, EIGHTEEN (18) FEET IN WIDTH, FOR INGRESS AND EGRESS FOR THE BENEFIT OF LOT 120 OF THIS SUBDIVISION. PARCEL E - A NON-EXCLUSIVE EASEMENT, THIRTY TWO (32) FEET IN WIDTH, FOR INGRESS, EGRESS AND PUBLIC UTILITIES FOR THE BENEFIT OF LOT 124 OF THIS SUBDIVISION. COUNTY DEDICATIONS
L22 S62°35'20"E 17.58 L23 S27°24'40"W 7.26 L24 S11°02'48"E 14.43 L25 N62°35'20"W 16.37 L26 N27°24'40"E 7.10 L27 S27°24'40"W 17.68 L28 N74°38'02"W 31.08 L29 S 5°38'24"E 44.12 L30 N17°17'50"W 9.02 L31 N27°24'40"E 2.59 L32 N26°29'52"E 12.80 L33 N62°48'44"W 2.96 L34 N26°29'52"E 22.62	C22 132.00 41°29'37" 95.59 C23 408.00 16°59'16" 120.97 C24 17.00 87°21'30" 25.92 C25 210.00 4°07'25" 15.11 C26 210.00 9°37'59' 35.31 C27 92.50 8°27'00" 13.64 C28 35.00 51°90'33" 31.16 C29 20.00 90°41'06" 31.66 C30 92.00 27°28'38 44.12 C31 408.00 2°40'38" 19.06 C32 100.00 36°50'28" 64.30 C33 65.00 50°59'14" 57.84 C34 10.00 90°0'000" 15.71	C83 762.00 4°20′26" 57.73 C84 738.00 0°57′55" 12.43 C85 762.00 0°10′07" 2.24 C86 315.00 3°44′16" 20.55 C87 315.00 15°11′39" 83.53 C88 175.00 42°46′43" 130.66 R1&M C89 205.00 42°46′43" 153.06 C90 235.00 42°46′43" 175.46 R1&M C91 1622.09 4°25′00" 125.04 C92 500.00 42°46′43" 30.51 R1&M C93 500.00 28°55′28" 252.41 C94 1447.69 20°0′31' 507.66 C95 315.00 40°24′21" 222.14 R1&M	PURSUANT TO SECTION 66434 (g) OF THE SUBDIVISION MAP ACT, THE FILING OF THIS FINAL MAP CONSTITUTES ABANDONMENT OF THOSE STREETS AND ACCESS RIGHTS ACQUIRED BY THE COUNTY OF HUMBOLDT PER: BOOK 5 OF MAPS, PAGE 74 - AMENDED MAP OF SAMOA OR WEST EUREKA BOOK 93 DEEDS, PAGE 151 - EASEMENTS GRANTED TO COUNTY OF HUMBOLDT BOOK 139 DEEDS, PAGE 42 - EASEMENT GRANTED TO COUNTY OF HUMBOLDT BOOK 190 DEEDS, PAGE 463 - EASEMENT GRANTED TO COUNTY OF HUMBOLDT	BAY VIEW AVENUE, CADMAN COURT, CUTTEN STREET, FENWICK AVENUE, MURPHY AVENUE, PACIFIC COURT, RIDEOUT STREET, SAMOA COURT, SUNSET AVENUE, SUNSET CIRCLE AND SUNSET EXTENSION ARE HEREBY OFFERED FOR DEDICATION AS EASEMENTS TO THE COUNTY OF HUMBOLDT FOR PUBLIC UTILITY PURPOSES AND ALL PURPOSES INCIDENTAL THERETO. PUBLIC UTILITY EASEMENTS (PUE) AND SIDEWALK EASEMENTS AS SHOWN HEREON ARE DEDICATED TO THE COUNTY OF HUMBOLDT FOR PUBLIC USE. PARCEL D - AN EASEMENT, TEN (10) FEET IN WIDTH, FOR PUBLIC UTILITIES DEDICATED TO THE COUNTY OF HUMBOLDT FOR PUBLIC USE.
L35 N26°29'52"E 1.84 L36 N26°29'51"E 32.80 L37 N26°29'51"E 2.11	C35 141.00 17°35′07" 43.28 C36 39.00 102°06′05" 69.50 C37 10.00 90°00′00" 15.71	C97 345.00 40°24'21" 243.30 C98 375.00 40°24'20" 264.45 R1&M C99 440.00 42°43'45" 328.14 R1&M	THIS PROPERTY MAY BE ENCLIMBEDED BY THE FOLLOWING PROPERTY	OF RECORD
L38 N63°13'11"W 25.69 L39 S26°46'47"W 6.03 L40 N58°13'42"W 4.01 L41 S36°46'49"E 20.08 L42 NOT USED L43 S76°14'12"W 8.00 L44 N76°49'50"E 21.89 L45 N15°42'48"E 26.48 R1&M L46 N66°0'115"W 22.74 L47 N13°45'24"W 21.10 L48 N76°14'36"E 20.00 L49 N76°28'56"E 20.65 L50 NORTH 14.70 L51 WEST 2.50 L52 S 5°34'50"E 15.52 L53 S29°17'13"E 110.15 L54 S27°05'52"W 22.20 L55 S36°44'08"W 5.29 L56 N48°11'26"W 86.73 L57 N46°04'25"W 82.68 L58 N52°33'13"W 73.67 L59 N56°06'52"W 118.02 L60 S49°36'19"W 67.01 L61 S33°06'29"W 112.06 L62 N26°46'17"W 67.52 L63 N52°14'33"W 33.64 L64 N59°20'43"W 33.50 L65 N25°04'26"E 56.16	C38 10.00 89°59'24" 15.71 C39 15.00 90°00'38" 23.56 C40 108.00 7°55'14" 14.93 C41 108.00 23°03'15" 43.46 C42 108.00 5°51'59" 11.06 C43 92.00 9°21'50" 51.04 C44 21.00 89°18'54" 32.74 C45 3175.00 0°22'59" 21.23 C46 3175.00 0°24'09" 50.02 C47 159.00 4°34'21" 12.69 C48 159.00 13°00'46" 36.11 C49 21.00 10°735'11" 39.43 C50 10.00 90°00'35" 15.71 C51 150.00 17°35'07" 46.04 C52 30.00 10°735'11" 56.33 C53 39.00 5°29'906" 3,73 C54 10.00 89°05'50" 15.50 C55 40.00 20°21'51" 14.21 C57 51.00 20°21'51" 14.21 C57 51.00 20°21'51" 18.13 C58 29.00 20°21'51" 18.13 C58 29.00 20°21'51" 10.31 C59 61.00 20°21'51" 10.31 C59 61.00 20°21'51" 21.68 C60 19.00 20°21'51" 10.31 C59 61.00 20°21'51" 10.31 C59 61.00 20°21'51" 11.68 C60 19.00 20°21'51" 5.71	C100 440.00 27°11'52" 208.86 C101 470.00 444'504" 367.10 C102 1447.69 6°28'51" 163.75 R1&M C103 40.00 94"34'28" 66.02 C104 148.00 4128'26" 107.13 C105 33.00 87"21'30" 50.32 C106 400.00 19"39"54" 137.29 C107 392.00 19"39"54" 134.54 C108 100.00 72"38'55" 126.80 C109 190.00 13"45'24" 45.62 C110 200.00 13"45'24" 48.02 C111 107.50 11"34'47" 21.73 C112 100.00 11"3'44'7" 20.21 C113 92.50 3"07'47" 5.05 C114 1652.09 0"29"26" 14.15 C115 235.00 25"52'08" 106.10 C116 3175.00 0"11'48" 10.90 C117 55.00 70"03'13" 67.25 C118 1417.69 6"19'22" 156.45 C119 66.00 24"13'24" 27.90 C120 1622.09 12"24'48" 351.43 R1&M C121 1622.09 12"24'48" 351.43 R1&M C121 1622.09 3"47'29" 107.34 C123 709.65 11"29"13" 142.27 R4&M C124 1652.09 7"36'32" 219.40	THIS PROPERTY MAY BE ENCUMBERED BY THE FOLLOWING RECORDED INSTRUMENTS: BOOK 656 O.R., PAGE 470 - EASEMENT FOR INGRESS, EGRESS AND PUBLIC UTILITIES GRANTED TO HUMBOLDT BAY MUNICIPAL WATER DISTRICT - SHOWN HEREON. BOOK 766 O.R., PAGE 271, BOOK 780 O.R., PAGE 7, BOOK 844 O.R., PAGE 124, BOOK 956 O.R., PAGE 38 - EASEMENTS FOR INGRESS, EGRESS AND PUBLIC UTILITIES GRANTED TO PACIFIC GAS AND ELECTRIC COMPANY - SHOWN HEREON. INSTRUMENT NO. 1995-22774-6 - EASEMENT FOR PUBLIC UTILITIES, INGRESS, EGRESS AND PUMP STATION GRANTED TO HUMBOLDT BAY MUNICIPAL WATER DISTRICT - SHOWN HEREON. INSTRUMENT NO. 1999-12525-6 - DEED RESTRICTION AND GRANT OF EASEMENT - SHOWN HEREON. INSTRUMENT NO. 2001-24109-10 - EASEMENT FOR INGRESS AND EGRESS - SHOWN HEREON. BOOK 60 SURVEYS, PAGE 122 - "PROPOSEDEASEMENT FOR INGRESS AND EGRESS" - SHOWN HEREON. INSTRUMENT NO. 2010-23037-30 O.R A COVENANT AND AGREEMENT EXECUTED BY SAMOA PACIFIC GROUP, LLC IN FAVOR OF CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD FOR THE NORTH COAST REGION - SHOWN HEREON. SEE SHEET 2 FOR EXISTING EASEM	
DETAIL 1	DETAIL 2_ -NOT TO SCALE-			TRACT NO TOWN OF SAMOA SUBDIVISION PHASE 1
MURPHY AVENUE SELECTION OF SELE	\$60°35'18"E 260'95	862-3818-A 260-80- A 260-80-80- A 260-80-80- A 260-80-80- A 260-80-80-	NOT TO SCALE- NO	SAMOA PACIFIC GROUP, LLC IN SECTIONS 16 & 17 TSN, RIW, HUMBOLDT MERIDIAN IN THE UNINCORPORATED AREA OF HUMBOLDT COUNTY MARCH 2021

STATE OF CALIFORNIA

KELLY-O'HERN ASSOCIATES EUREKA, CALIFORNIA


HUMBOLDT COUNTY

SHEET 15 OF 15 SHEETS

BOOK _____ OF MAPS, PAGE

EXHIBIT B

RECEIVED
MAR 0.2 7000
Humsold County Ja



CEC GENERAL NOTES

- 1.) THE CONSTRUCTION CONTRACTOR SHALL AGREE, THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY, THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS AND THE CONSTRUCTION CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD CONSULTING ENGINEER, SAMOA PACIFIC GROUP, AND THE COUNTY OF HUMBOLDT HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT. EXCEPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE CONSULTING DESIGN PROFESSIONAL, SAMOA PACIFIC GROUP, OR THE COUNTY OF HUMBOLDT.
- 2.) ALL CONSTRUCTION MATERIALS, METHODS AND WORKMANSHIP SHALL CONFORM TO THE COUNTY OF HUMBOLDT PUBLIC WORKS IMPROVEMENT STANDARDS, ADDPTED LATEST EDITION OF STATE OF CALIFORNIA, DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS, AND THE CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS (RANK SHALL BE IN ABOVE USTED ORDER WHERE DISCREPANCIES EXIST). ALL WORK IS BUBLECT TO THE APPROVAL OF COUNTY ENGINEER OR HIS AUTHORIZED REPRESENTATIVE. CERTIFICATION FOR CONFORMANCE WITH COUNTY SPECIFICATIONS WILL BE REQUIRED FOR ALL MATERIALS USED ON THE PROJECT UNLESS SPECIFICALLY WAIVED BY THE COUNTY ENGINEER.
- 3.) THE CONTRACTOR SHALL NOTIFY THE COUNTY ENGINEER 72—HOURS PRIOR TO COMMENCING WORK AND 24—HOURS PRIOR TO RESUMPTION AFTER INTERRUPTION.
- 4.) THE CONTRACTOR SHALL OBTAIN ALL NECESSARY ENCROACHMENT PERMITS FOR THE PROJECT, AND BE IN RECEIPT OF SUCH PERMITS AND APPROVED PLANS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- 5.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPUNANCE WITH ALL CURRENTLY APPLICABLE SAFFLY LAWS OF ANY JURISDICTIONAL BOOLES. FOR MORE INFORMATION, PLEASE CONTACT THE STATE INDUSTRIAL SAFFLY DEPARTMENT (916-456-5816).
- 8.) THE CONTRACTOR SHALL BE HELD RESPONSIBLE TO SEE THAT ALL SUBCONTRACTORS AND SUPPLIERS HAVE CURRENT COUNTY BUSINESS LICENSES. THE WORK MILL NOT BE ACCEPTED FOR COMPLETION UNTIL SUBMITTAL OF A COMPLETE LIST WITH LICENSE NUMBERS TO THE COUNTY ENGINEER.
- 7.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF EXISTING PUBLIC AND PRIVATE IMPROVEMENTS WITHIN AND ADJACENT TO THE WORK AND SHALL ADEQUATELY BARRICADE PROJECT TO KEEP THE GENERAL PUBLIC FROM THE SITE. ANY DAMAGE TO CITY OF PRIVATE IMPROVEMENTS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AT HIS EXPENSE TO CURRENT STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS.
- 8.) THE CONTRACTOR IS TO EXPOSE THE ENDS OF WATER MAINS, SEWER AND DRAIN LINES AND EXISTING GRAVITY LINES FOR THE SURVEYOR TO VERIFY LOCATION AND DEPTH OF FACILITIES PRIOR TO PLACEMENT OF FIPE.
- 9.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPORTING ALL CONFLICTS, ERRORS, OMISSIONS, ETC. TO THE CONSULTING ENGINEER IMMEDIATELY UPON DISCOVERY. IF SO DIRECTED BY THE ENGINEER OR COUNTY ENGINEER, THE CONTRACTOR SHALL STOP WORK UNIL MITIGATIONS CAN BE MADE. ANY COSTS INCURRED RESULTING FROM THE CONTRACTOR'S FAILURE TO STOP WORK AS DIRECTED SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 10.) THE CONTRACTOR SHALL AT ALL TIMES COORDINATE HIS WORK WITH THAT OF OTHERS ON THE SITE. THE CONTRACTOR SHALL HAVE A RESPONSIBLE PARTY, WHO SHALL HAVE THE AUTHORITY-TO REPRESENT AND ACT ON HIS BEHALF, ON THE JOB SITE DURING ALL WORKING HOURS.
- 11.) THE COUNTY OF HUMBOLDT IS A MEMBER OF THE UNDERGROUND SERVICE ALERT (U.S.A.) ONE CALL SYSTEM. THE CONTRACTORS SHALL NOTIFY THE U.S.A. CENTER 72—HOURS IN ADVANCE OF PERFORMING ANY EXCAVATION WORK BY CALLING 1—800—227—2800—2
- 12.) THE CONTRACTOR SHALL MARK IN WHITE PAINT ALL AREAS TO BE EXCAVATED PRIOR TO CONTACTING U.S.A. $\,$
- 13.) CONTRACTOR SHALL SUBMIT TO THE PUBLIC WORKS DEPARTMENT INSPECTOR A COPY OF THE COMPANY ANNUAL DALOSHA TRENCRING PERMIT AND A COPY OF THE COMPANIES LETTER INFORMING CALOSHA OF THE TIME OF TRENCHING PRIOR TO EXCAVATION OF TRENCHES 5 OR
- 14.) ALL WORK SHALL BE IN ACCORDANCE WITH THE COUNTY'S NOISE ORDINANCE.
- 16.) IF ANY AMOUNT OF BONES, STONE OR ARTIFACTS ARE UNCOVERED, WORK WITHIN 165 FEET OF THE AREA SHALL CEASE IMMEDIATELY AND A QUALIFIED ARCHEOLOGIST SHALL BE CONSULTED TO DEVELOP (IF NECESSARY) FURTHER MINICATION MEASURES TO REDUCE ANY ARCHEOLOGICAL IMPACT TO A LESS THAN SIGNIFICANT EFFECT BEFORE CONSTRUCTION RESUMES IN THE AREA.
- 16.) CONTRACTOR SHALL PROVIDE THE COUNTY ENGINEER WITH SUBMITTALS FOR ALL MATERIALS TO BE USED. THE SUBMITTALS SHALL BE DELIVERED TO THE DEPARTMENT OF PUBLIC WORKS A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE.
- 17.) CERTIFICATION FOR CONFORMANCE WITH THE COUNTY OF HUMBOLDT SPECIFICATIONS WILL BE REQUIRED OF ALL MATERIAL USED ON THE PROJECT UNLESS SPECIFICALLY WAIVED BY THE ENGINEER.
- 18.) CONTRACTOR SHALL ADEQUATELY BARRICADE PROJECT TO KEEP THE GENERAL PUBLIC FROM THE SITE.
- 19.) ALL APPLICABLE FEES TO BE PAID AND PERMITS REQUIRED SHALL BE OBTAINED BY THE CONTRACTOR BEFORE COMMENCEMENT OF CONSTRUCTION.
- 20.) A SOILS ENGINEER SHALL BE ENGAGED BY THE OWNER TO CERTIFY THAT THE VARIOUS ITEMS OF COMPACTION COMPLY WITH THE SPECIFICATIONS AND THAT SPECIAL WORK REQUIRED HAS BEEN DONE SATISFACTORILY.
- 21.) THE CONTRACTOR SHALL USE A WATER TRUCK WHEN REQUIRED TO MAINTAIN ADEQUATE DUST CONTROL.
- 23.) EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE PLANS AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP).
- 24.) PRIOR TO THE BEGINNING OF EARTHWORK THE CONTRACTOR SHALL CLEAR ALL ROOTS, ORGANIG MATTER, DEBRIS, PAWING, CURB, AND VEGETATION DESIGNATED TO BE SAVED, FROM THE AREA WITHIN WHICH EXCAVATION AND GRADING ARET OBE CONDUCTED OR STORAGE OF EXCAVATED MATERIALS OF FILL IS TO BE MADE. VEGETATION CLEARED FROM THESE AREAS SHALL BE DISPOSED OF BY THE CONTRACTOR, AND INCLUDED IN THE COST OF CLEARING AND GRUBBING.
- 25.) IN TRANSITION AREAS FROM ONE STREET WIDTH TO ANOTHER STREET WIDTH, THE HEAVIER STRUCTURAL SECTION SHALL BE USED.
- 26.) DIMENSIONS SHOWN ON PLANS ARE TO CENTERLINE OF PIPE, UNLESS OTHERWISE NOTED.

CEC GENERAL NOTES CONTINUED

- 27.) SEWER AND WATER AND SERVICES TO HAVE A MINIMUM 10 FEET HORIZONTAL SEPARATION.
- 28.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES.
- 29.) CONTRACTOR SHALL POTHOLE ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY LOCATION AND DEPTH. THE TYPES, LOCATIONS, SIZES AND DEPTH OF EXISTING UTILITIES WERE OBTAINED FROM SOURCES OF VARYING RELABILITY, THE CONTRACTOR IS CAUTIONED THAT ONLY EXCAVATIONS WILL REVEAL ACTUAL INFORMATION. A REASONABLE FROM THE MADE TO DELINEATE UTILITIES, HOWEVER, CALIFORNIA ENGINEERING COMPANY ASSUMES NO RESPONSIBILITY FOR THE COMPLETENESS, NOR ACCURACY, NOR FOR OTHER UTILITIES WHICH MAY BE ENCOUNTERED. THE CONTRACTOR IS HEREBY NOTHED THAT THEY ARE RESPONSIBLE FOR VERIFICATION OF THE LOCATION OF ALL UTILITIES AT THE CONSTRUCTION STEIL IN THE EVENT CONFLICTS EXIST OR SUBSTANTIAL DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IMMEDIATELY AND ALLOW 2 WORKING DAYS FOR CHANGE TO BE MADE, COORDINATED AND APPROVED.

GRADING NOTES

- 1.) A SOILS ENGINEER SHALL CERTIFY THAT THE VARIOUS ITEMS OF COMPACTION AND MATERIALS HAVE BEEN ACCOMPLISHED. GRADING SHALL CONFORM TO CHAPTER 70 UBC, LATEST EDITION, AND TO THE RECOMMENDATION OF THE GEOTECHNICAL ENGINEERING REPORT, AND COUNTY REQUIREMENTS, WHICHEVER IS GREATER.
- 2.) ALL COMPACTION TESTING SHALL BE PERFORMED BY A LICENSED GEOTECHNICAL ENGINEER IN ACCORDANCE WITH THE GEOTECHNICAL AND COUNTY SPECIFICATIONS AND BE PAID FOR BY THE DEVELOPER (OR CONTRACTOR IN CASE OF RE-TESTING). THOSE TESTS WITHIN THE RIGHT-OF-WAY SHALL BE APPROVED BY THE COUNTY OF HUMBOLDT AND ALL TESTING OUTSIDE THE RIGHT-OF-WAY CERTIFICE BY THE SOLIS ENGINEER FOR THE PROJECT. THE RESULTS OF SOIL COMPACTION TESTING SHALL BE SUBMITTED TO THE COUNTY BI-MONTHLY.
- 3.) ALL UNSUITABLE AND SURPLUS MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED.
- 4.) SUFFICIENT EQUIPMENT SHALL BE AVAILABLE TO PROVIDE DUST CONTROL AT ALL TIMES DURING CONSTRUCTION. A WATER TRUCK SHALL BE USED, WHEN REQUIRED, TO MAINTAIN ADEQUATE DUST CONTROL. AREAS SURROUNDING THE WORK SHALL BE KEPT CLEAN AND RETURNED TO ORGINAL CONDITION UPON COMPLETION OF THE CONTRACT. THE CONTRACT SHALL OBTAIN A FIRE HYDRANT WATER METER PRIOR TO COMMENCEMENT OF WORK.
- 5.) ROUTES TO THE PROJECT SITE FOR HEAVY EQUIPMENT AND MATERIAL SHALL BE APPROVED BY
- 7.) WINTERIZATION NOTE *THE FOLLOWING ARE REQUIRED IF GRADING AND CLEARING IMPROVEMENTS ARE INCOMPLETE BY OCTOBER 15TH; EROSION PROTECTION ON SLOPES 10:1 OR STEEPER AND SWALES WITH SLOPES 26 OR GREATER, NO SEDIMENT SHALL LEAVE THE PROJECT AREA. GRADE GUTTER SAG POINTS TO DRAIN. PROVIDE FOR DRAINAGE OF IMPROVEMENTS. PREVENT SEDIMENTATION IN EXISTING STORM DRAIN SYSTEM AND CLEAN PIPES PER SECTION SSGO—05 (CAL—TRANS SPECS). SEAL OFF ALL SANITARY SEWER CONNECTION TO EXISTING SYSTEMS, IT IS THE CONTRACTORS RESPONSIBILITY TO MAINTAIN WINTERIZATION FACILITIES AT ALL TIMES OR UNTIL IMPROVEMENTS ARE FINAL.
- 8.) ALL EROSION CONTROL SHALL BE PLACED AS SPECIFIED ON THESE PLANS OR AS SHOWN ON THE SWPPP.
- 9.) TARPAULINS OR OTHER EFFECTIVE COVERS SHALL BE USED ON ALL STOCKPILED EARTH MATERIAL AND ON HAUL TRUCKS TO MINIMIZE DUST.
- 10.) THE COUNTY SHALL HAVE THE AUTHORITY TO STOP ALL GRADING OPERATIONS, IF, IN OPINION OF COUNTY STAFF, INADEQUATE DUST CONTROL MEASURES ARE BEING PRACTICED OR EXCESSIVE WIND CONDITIONS CONTRIBUTE TO PUGITIVE DUST EMISSIONS.
- 11.) ADJACENT STREET FRONTAGES SHALL BE SWEPT AT LEAST ONCE A DAY TO REMOVE SILT AND OTHER DIRT WHICH IS EMDENT FROM CONSTRUCTION ACTIVITIES.
- 12.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING CONSTRUCTION VEHICLES LEAVING THE SITE ON A DAILY BASIS TO PREVENT DUST, SILT, AND DIRT FROM BEING RELEASED OR TRACKED OFFSTE.
- 13.) PRIOR TO INITIATING CLEARING AND GRUBBING ALL PROTECTIVE FENCING SHALL BE INSTALLED.

STREET/PARKING NOTES

- 1.) UPON COMPLETION OF CURB AND GUTTER POUR AND PRIOR TO THE SETTING OF THE CONCRETE, ALL CUITTERS SHALL BE WATER TESTED. WATER TESTING SHALL CONSIST OF POURING WATER ONTO THE FLOW LINE AND FOLLOWING THE WATER DOWNSTREAM REMOVING ALL HIGH AND LOW AREAS IN THE FLOW LINE.
- 2.) CURB OR MOW STRIP SHALL BE BRANDED WITH AN "S", "W", OR "I" AT SEWER AND WATER SERVICE LOCATIONS AND IRRIGATION CROSSINGS RESPECTIVELY.
- 3.) SIDEWALK RAMPS SHALL BE CONSTRUCTED AT THE CENTER OF ALL CURB RETURNS OR AS SHOWN.
- 4.) STREET NAME SIGNS SHALL BE PLACED ON THE RIGHT SIDE OF EACH INTERSECTION. MATERIALS, LOCATIONS, AND INSTALLATION PER THE CITY OF EUREKA IMPROVEMENT STANDARDS.
- 5.) THE CONTRACTOR SHALL COORDINATE WITH OTHER WORK TO ASSURE THAT ALL UNDERGROUND CONDUITS AND UTILITIES ARE INSTALLED PRIOR TO PAVING. ALL PIPES IN PAVED AREAS SHALL BE PLACED PRIOR TO PLACING AGGREGATE BASE.
- 8.) EXISTING AC SURFACE SHALL BE CUT TO A NEAT STRAIGHT LINE PARALLEL WITH AND PERPENDICULAR TO THE STREET CENTERLINE AND THE EXPOSED BASE AND EDGE MATERIAL SHALL BE TACKED WITH EMULSION PRIOR TO PAVING, THE EXPOSED BASE MATERIAL SHALL BE GRADED, RE-COMPACTED, AND RESALED PRIOR TO PAVING, ANY CONCRETE, AC, TREES, FENCES, AND/OR OTHER OBSTRUCTIONS REQUIRED TO CONSTRUCT THE PROPOSED IMPROVEMENTS SHALL BE REMOVED. AND BE INCLUDED IN THE PRICES FOR VARIOUS ITEMS OF WORK. VERTICAL FACES OF ALL GUTTERS SHALL BE TACKED WITH EMULSION PRIOR TO PAVING.
- 7.) WHERE WORK IS ADJACENT TO A TRAFFIC LANE AND THERE IS A PAVEMENT CUT, DITCH, OR THENCH GREATER THAN 2-INCHES IN DEPTH, AT A MINIMUM, THE CONTRACTOR SHALL MAINTAIN CONTINUOUS BARRICADES SPACED AT APPROXIMATELY 50-FOOT INTERVALS. IF THE CUT, DITCH, OR TRENCH IS GREATER THAN 10-FEET FROM A TRAFFIC LANE, THE SPACING MAY BE GREATER, BUT, SPACING SHALL NOT EXCEED 200-FEET.

SANITARY SEWER NOTES

- 1.) ALL SANITARY SEWER CONSTRUCTION MATERIALS AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS AND THE MANUFACTURERS SPECIFICATIONS. ALL SANITARY SEWER INITIAL BACK FILL SHALL BE THE SAME MATERIAL USED FOR PIPE BEDDING AND SHALL BE PLACED TO 6* ABOVE TOP OF PIPE.
- 3.) ALL SERVICE SEWERS ENTERING A MANHOLE WILL BE SET NOT LOWER THAN FLOWLINE-TO-CROWN WITH EXISTING PIPE UNLESS OTHERWISE SHOWN.
- 5.) THE CONTRACTOR SHALL MAINTAIN ALL EXISTING SEWER FACILITIES WITHIN THE CONSTRUCTION AREA UNTIL NEW IMPROVEMENTS ARE IN PLACE AND APPROVED.
- 6.) ANY WATER ENTERING THE SANITARY SEWER SYSTEM TO BE CONSTRUCTED UNDER THESE IP LANS SHALL NOT BE DISCHARGED TO THE EXISTING SANIL. PLUGS SHALL BE INSTALLED EXISTING MAINLOLES AS NECESSARY TO PERMIT PUMPING THE NEW SYSTEM CLEAR OF WATER AND DEBRIS PRIOR TO ACCEPTANCE. CARE SHALL BE EXERCISED IN LOCATING PLUGS TO AVOID INTERRUPTING SERVICE TO EXISTING CONNECTIONS. MORTAR OR BRICK PLUGS SHALL BE USED, INFLATABLE DEVICES ARE NOT SATISFACTORY.
- 7.) ALL SERVICES SHALL HAVE 3' MINIMUM, PER CITY OF EUREKA STANDARDS, OF COVER AT THE PROPERTY LINE AND SHALL BE TO THE CENTER OF THE LOT UNLESS OTHERWISE NOTED ON THE PLANS. THE CONTRACTOR SHALL PLACE A 4"X4" REDWOOD POST AT THE END OF EACH SERVICE EXTENDING FROM THE END OF PIPE TO AT LEAST 12" ABOVE SURFACE.
- 8), A VACUUM TEST SHALL BE DONE ATTER ASSEMBLY OF THE MANHOLE, BUT BEFORE BACK FILL ALL FIFTHCES SHALL BE FILED WITH NON-SHRINK GROUT, ALL PIPES ENTERING THE MANHOLE SHALLEF FILED WITH NON-SHRINK GROUT, ALL PIPES ENTERING THE MANHOLE SHALLEF THE FULL FROM EDIO ROYAWN INTO THE SHALLEF THE FULL THE SHALLEF THE SHALLEF THE SHALLEF THE MANHOLEF THE MANUFACTURERS RECOMMENDATIONS. A VACCIUM FOR TO TO' OF MERCURY (APPROXIMATELY SPS) SHALL BE DRAWN AND THE VACUUM PUMP SHUT OFF, WITH THE VACUUM FULL FROM THE MANUFACTURE FOR THE VACUUM FULL FOR THE STALLEF THE MANHOLE FAILS THE INITIAL TEST, NECESSARY REPAIRS SHALL BE MADE WITH A NON-SHRINK GROUT WHILE THE VACUUM IS STILL BEING DRAWN, RETESTING SHALL PROCEED UNTIL A SATISFACTORY TEST IS OBTAINED. THE CONTRACTOR IS TO PERFORM THE TEST AND SUPPLY ALL TEST EQUIPMENT.
- 9.) ALL MANHOLES SHALL BE 48" IN DIAMETER, UNLESS OTHERWISE NOTED.
- 10.) CURB OR MOW STRIP TO BE BRANDED WITH S AT SEWER SERVICE LOCATIONS.
- 11.) ALL SEWER SERVICES CONNECTING TO SEWER MAIN SHALL BE CONNECTED WITH 'Y FITTING IN THE DIRECTION OF FLOW.

WATER FACILITIES NOTES

- 1.) ALL WATER FACILITIES INCLUDING BUT NOT LIMITED TO LIMES, SERVICE BOXES, VALVES, AND ALL MISCELLANEOUS APPURTENANCES SHALL CONFORM TO THE CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS, AND HUMBOLD'S BAY MUNICIPAL WATER DISTRICT STANDARDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION, REQUIREMENTS, AND DRAWNGS NECESSARY TO BID AND COMPLETE THE WORK SHOWN ON THESE PLANS AND INSTALLED PER MANUFACTURERS SPECIFICATIONS. PIPE ALTERNATIVES SHALL BE: POLYMNYL CHLORIDE PIPE AWWA C900 CLASS 150 DUCTILE IRON PIPE AWWA 151 CLASS
- 2.) FIRE HYDRANTS SHALL BE APPROVED BY THE COUNTY ENGINEER AND SAMOA PENINSULA FIRE DISTRICT.
- 3.) ALL RUNS OF SEWER FORCE MAIN AND WATER MAIN PIPE SHALL HAVE NO.10 GAUGE, SOLID INSULATED SOFT-DRAWN COPPER WRE TAPED ALONG THE TOP OF PIPE. THE WIRE SHALL BE STUBBED UP INSIDE EACH VALVE BOX AND DEAD END BLOWOFF ASSEMBLY AND BE INSTALLED AS PER STANDARD DRAWNRO ASSEMBLY WING. ASLED OF ALL SPLICES SOLDERED AND SHRINK-WRAPPED OR
- 4.) AT UTILITY CROSSING MAINTAIN A MINIMUM 12" VERTICAL CLEARANCE BETWEEN WATER LINES AND ALL OTHER FACILITIES. ALL SEWER/WATER CROSSINGS, INCLUDING SERVICES, SHALL CONFORM TO STATE HEALTH DEPARTMENT REQUIREMENTS WITH 10" MINIMUM HORIZONTAL CLEARANCE.
- 5.) ALL VALVES SHALL BE FLANGED TO TEES AND/OR CROSSES, ALL MAINLINE VALVES 16-INCH AND LARGER SHALL BUTTERFLY VALVES WHERE VALVE NUT IS GREATER THAN 30-INCH BELOW FINISHED GRADE. A VALVE OPERATING EXTENSION SHALL BE REQUIRED.
- 6.) ALL WATER SERVICES SHALL BE PER CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS.
- 7.) WATER METER BOXES AND COVERS SUBJECT TO TRAFFIC SHALL BE REINFORCED CONCRETE.
- 8.) SERVICE CONNECTION TO EXISTING WATER MAIN (S), OR TO AN EXTENSION OF AN EXISTING WATER MAIN (S), WIL BE MADE BY A QUALIFIED CONTRACTOR. THE CONTRACTOR SHALL NOTIFY COUNTY 72 HOURS IN ADVANCE, SCHEDULE AND PROCEED WITH THE SERVICE CONNECTION WITH MINIMUM INTERFERENCE OF DEISTING WATER AND FIRE SERVICES. AN INSPECTION BY THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO ALL CONNECTIONS MADE BY THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO THE CONTRACTOR IS REQUIRED PRIOR TO BACKET INTERFERENCE TO THE CONTRACTOR IS REQUIRED.
- 9.) PIPE JOINTS WILL NOT BE ALLOWED WITHIN SIX FEET (6') OF VALVE, FITTING OR HYDRANT.
- 10.) UNDER NO CIRCUMSTANCES SHALL PIPE OR JOINT DEFLECTION EXCEED MANUFACTURERS RECOMMENDATION. DEFLECTION OF PIPE WILL NOT BE ALLOWED WITHIN TEN FEET (10") OF ANY FITTING OR VALVE.
- 11.) STANDARD PIPE LENGTHS (MINIMUM EIGHTEEN (18) TO TWENTY (20) FEET, SHALL BE USED FOR ALL HORIZONTAL AND VERTICAL DEFLECTIONS, PIPE LENGTHS LESS THAN STANDARD LENGTH SHALL BE APPROVED BY THE COUNTY ENGINEER.
- 12.) IN THE EVENT THAT THIS PROJECT INDICATES THAT WATER MAINS WILL BE CONSTRUCTED WITHOUT THE PROTECTION OF AN OVERLAYING PAVEMENT, PLASTICZED METALUL LOCATING TAPE SHALL BE PLACED EIGHTEEN INCHES (187) ABOVE ALL SAID WATER MAINS.
- 13.) WATER SYSTEM CONTRACTOR SHALL COORDINATE WITH THE STREET LIGHTING CONTRACTOR TO AVOID CONFLICTS WITH WATER SERVICES AND STREET LIGHT FOUNDATIONS AND ELECTRICAL PULLBOXES.
- 14) CONTRACT TO PROVIDE 72-HOUR NOTIFICATION TO THE COUNTY DEPARTMENT OF PUBLIC
- 15.) ALL WATER LINE FITTINGS 11-½ DEGREE OR GREATER, TEES, CROSSES, DEAD ENDS AND REDUCERS/INCREASERS SHALL BE PROVIDED WITH BOTH THRUST BLOCKS AND RESTRAINED JOINT PIPE LENGTHS.

STORM DRAIN NOTES

- 1.) THE STORM DRAIN FACILITIES SPECIFIED IN THESE PLANS, INCLUDING MATERIALS AND METHOD OF INSTALLATION, SHALL BE IN ACCORDANCE WITH THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS, AND THE MANUFACTURERS SPECIFICATIONS (50 YEARS SERVICE LIFE), THE FOLLOWING PIPE ALTERNATES SHALL BE USED:
 A PENIFORCED CONCERTE PIPE CLASS III, JUNIESS SPECIFIED OTHERWISE IN THESE PLANS. PIPE SHALL CONFORM TO ASTM C76, LATEST REVISION. THE ASSEMBLY OF JOINTS SHALL BE IN ACCORDANCE WITH THE PIPE MANUFACTURE'S RECOMMENDATION AND THE REQUIREMENTS OF ASTM C 443.

 BE DELYWAYN, CHARGINE PIPE (PEV) COMPOSITION TO OME OF THE FOLLOWING

 - RECOMMENDATION AND THE REQUIREMENTS OF ASTM C 443.
 B, POLYMYNI, CHICRIDE PIPE (PVC) CONFORMING TO ONE OF THE FOLLOWING SPECIFICATIONS:
 DIAMETER ASTM. DESIGNATION
 12 INCH D3034, SDR 35 / C900, DR 18
 15 INCH D3034, SDR 35 / C905, DR 18
 16 INCH D2241, SDR 51 / C905, DR 18
 21 INCH D2241, SDR 51 / C905, DR 18
 21 INCH D2241, SDR 51 / C905, DR 18
 - 21 INCH D2241, SDR 51 / C905, DR 18
 27 INCH D2241, SDR 51 / C905, DR 18
 27 INCH D2241, SDR 51 / C905, DR 18
 30 INCH C905, DR 1
 - OR 97 TYPE S OR TYPE D WITH INSIDE DIAMETERS OF 12 TO 60 INCHES. PIPE JOINTS SHALL BE BELL AND SPIGOT OR WELDED TYPE, CERTRIED CAPABLE OF WATERIGHT PERFORMANCE, WITH O-RING GASKETS MEETING ASTM F-477. THE ASSEMBLY OF JOINTS SHALL BE IN ACCORDANCE WITH THE PIPE MANUFACTURERS RECOMMENDATIONS AND THE REQUIREMENTS OF ASTM D-3212.
 - THE CONTRACTOR SHALL MAINTAIN ALL EXISTING DRAINAGE FACILITIES WITHIN THE CONSTRUCTION AREA UNTIL NEW DRAINAGE IMPROVEMENTS ARE IN PLACE AND FUNCTIONING.
- 3.) EXISTING STORM DRAIN FACILITIES SHALL BE EXPOSED AND INVERT VERIFIED PRIOR TO PLACEMENT OF PIPE WITH ALL CONSTRUCTION CONFORMING TO MANUFACTURERS SPECIFICATIONS AND TO THE REQUIREMENTS OF THE COUNTY OF HUMBOLDT. ALL COSTS FOR SUCH EXCAVATION AND BACK FILL STALL BE INCLUDED IN THE BID PRICE.
- 4.) THE CONTRACTOR SHALL NOT ALLOW ANY SEDIMENT TO BE WASHED INTO OR ENTER STORM DRAINAGE FACILITIES. SHOULD EXCESSIVE SEDIMENTATION OCCUR, THE CONTRACTOR SHALL BE REQUIRED TO FLUSH OUT AND CLEAN THE FACILITIES AND BE APPROVED BY THE COUNTY ENGINEER PRIOR TO FINAL ACCEPTANCE.
- 5.) ALL MANHOLES SHALL BE 48" IN DIAMETER, UNLESS OTHERWISE SHOWN.
- 5.) MANHOLES LOCATED OUTSIDE OF PAVED AREAS SHALL HAVE RIM SET 0.5 FEET ABOVE OROUND SURFACES, OR TO GRADE AS NOTED.
- 7.) DURING CONSTRUCTION, NEW AND EXISTING PIPES OR UTILITIES LOCATED WITHIN THE CONSTRUCTION AREA SHALL BE PROTECTED WITH PLATE SITEL OR MAIN ADEQUATE COVER TO PREVENT ANY DAMAGE FROM HEAVY EQUIPMENT. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ANY DAMAGE TO PIPES OR UTILITIES DURING CONSTRUCTION.
- 8.) ALL DROP INLETS SHALL INCLUDE A " NO DUMPING " PUBLIC NOTICE.
- 9.) ALL DRAINAGE INLET GRATES SHOWN ON PLAN ARE DEPRESSED, LOWER THAN PROJECTED GUTTER FLOWLINE SLOPES. THE CONTRACTOR SHALL PAY SPECIAL ATTENTION STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND GUTTER SLOPES TO ENSURE THAT CURB AND GUTTER, AND DRAINAGE INLET GRATES ARE HISTALLED AT PROPER ELEVATIONS. SPECIAL CARE SHOULD BE TAKEN TO THOROUGHLY REVIEW THE MINSTON POPER ELEVATIONS.
- 10.) ALL CAST-IN-PLACE CONCRETE PIPE CONSTRUCTION SHALL CONFORM TO "SECTION 83: CAST-IN-PLACE CONCRETE PIPE" OF THE STATE OF CALIFORNIA STANDARD SPECIFICATIONS. THE OWNER AND/OR CONTRACTOR SHALL RETAIN SERVICES OF A FULL-TIME, QUALIFIED CONSTRUCTION OF MONITOR AND OSSERVE CONSTRUCTION, AND PERFORM TESTING TO ENSURE CONSTRUCTION CONFORMS TO THE SPECIFICATION. QUALITY ASSURANCE/QUALITY CONTROL REPORTS SHALL BE SUBMITTED TO THE COUNTY REGULARLY. THE CONCRETE SHALL MEET OR EXCEED A COMPRESSIVE STRENGTH OF 3000 PSI PRIOR TO ANY BACKFILL OPERATIONS.

CONSTRUCTION STAKING

- 1.) THE SURVEYOR FOR THIS PROJECT SHALL PROVIDE ONE (1) SET OF CONSTRUCTION STAKES FOR LINE AND GRADE UNLESS OTHERWISE REQUESTED BY THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING MODILMENTS AND OTHER SURVEY MARKERS DURING CONSTRUCTION. ALL SUCH MODILMENTS OR MARKERS DESTROYED DURING CONSTRUCTION SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.
- 2.) IN THE EVENT OF A DISAGREEMENT OR DESTROYED STAKE OR MONUMENT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE SURVEYOR PRIOR TO ANY FURTHER CONSTRUCTION.
- 3.) THE CONTRACTOR SHALL GIVE THE SURVEYOR 72—HOURS NOTICE PRIOR TO EACH PHASE OF CONSTRUCTION OR IN THE EVENT OF NEEDED RE-STAKING. PRIOR TO REQUESTING ACCEPTANCE OF IMPROVEMENTS, THE SURVEYOR FOR THIS PROJECT SHALL SET SURVEY MONUMENTS AS SPECIFIED IN THE IMPROVEMENT STANDARDS.
- 4.) THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING MONUMENTS AND OTHER SURVEY MARKERS.

MINIMUM FINISH FLOOR ELEV.

1.) NEW PERMANENT RESIDENTIAL DWELLING UNITS SHALL BE DESIGNED SO THE LOWEST HABITABLE FLOOR IS AT A LEVEL NOT LOWER THAN 32 FEET ABOVE MEAN SEA LEVEL PER LOCAL COASTAL PROGRAM AMENDMENT, STMP (HAZARDS) POLICY 5.

G 830 7, 4, 5, 530 Fax Fenter Yuba

ш


U


MARKED 世界 1 0 2020 Humbold County Building Division

NOTES


œ 62

12-201





Collinate Engineering Company & no.




1.) WHERE (E) PIPES AND FITTINGS ARE PRESENT, THEY SHALL BE SAWCUT ALONG THE SPRINGLINE TO FORM THE FLOW CHANNEL WITHIN THE MANHOLE. MANHOLE BASE SECTIONS SHALL BE FILLED WITH CONCRETE TO A LEVEL EQUAL TO THE SPRINGLINE OF THE EXPOSED PIPES, AND SHALL BE FORMED AT THE SLOPE SHOWN TO DRAIN INTO THE FLOW CHANNEL TOWARD THE OUTLET PIPES.

2.) WHERE (E) PIPES AND FITTINGS ARE NOT PRESENT WITHIN THE MANHOLE, THE FLOW CHANNEL SHALL BE HAND-FORMED AT THE SLOPE THE APPROXIMATE LEVEL OF THE TOP OF THE PIPE. WANHOLE BASE SECTIONS SHALL BE FILLED WITH CONCRETE TO

- 3.) WATERSTOPS SHALL BE INSTALLED AS SHOWN IN THIS DETAIL.
- 4.) ALL JOINTS SHALL BE SEALED WITH CLASS B MORTAR ON BOTH THE INNER AND OUTER FACES OF EACH JOINT.
- 5.) MANHOLES SHALL BE CONSTRUCTED WITH A 0.10' ELEVATION DROP (OR AS SHOWN ON THE PLANS) BETWEEN THE INLET AND OUTLET PIPES, IF POSSIBLE,

6.) #10 COPPER TRACER WIRE WITH GREEN INSULATION SHALL BE INSTALLED AT ALL NEW AND EXISTING MANHOLE LOCATIONS. TRACER WIRE SHALL EITHER BE CONTINUOUS ALONG (N) SANITARY PIPE AND UP TO THE MANHOLE FRAME OR SHALL BE SECURELY CONNECTED TO THE (E) TRACER WIRE WHERE PIPE REPLACEMENT IS NOT PERFORMED. NOTE THAT TRACER WIRE IS NOT REQUIRED ON MANHOLES WHEN THE (E)

SANITARY SEWER MANHOLE DETAILS



- 1.) MINIMUM PIPE SLOPES SHALL BE 1% (%" PER FOOT) UNLESS OTHERWISE APPROVED BY THE ENGINEER.
- 2.) FACTORY MANUFACTURED FITTINGS SHALL BE USED EXCLUSIVELY.
- 3.) SEWER SADDLES SHALL ONLY BE USED AFTER APPROVAL BY THE ENGINEER.
- 4.) ALL FITTINGS AND LATERAL PIPING SHALL BE 4" (MIN) PVC SDR-35 SEWER PIPE.
- 5.) ALL LATERALS SHALL BE INSTALLED WITH A #10 COPPER TRACER WIRE WITH GREEN INSULATION TAPED TO THE SANITARY SEWER PIPE. LATERAL TRACER WIRE SHALL BE SECURELY CONNECTED TO AND ELECTRICALLY CONTINUOUS WITH THE SEWER MAIN TRACER WIRE AT ONE END WITH WATERPROOF CORROSION RESISTANT CONNECTOR, AND SHALL TERMINATE IN A LOOP JUST BELOW THE LID IN THE CLEANOUT BOX AT THE OTHER END.
- 6.) PVC RISER SHALL NOT END IN A BELL FLANGE OR "CAULDER"—TYPE COUPLING. RISER SHALL TERMINATE AT THE REQUIRED CLEARANCE WITH A LEVEL CUT.
- 7.) ALL AREAS BEHIND THE SIDEWALK THAT ARE DISTURBED BY THE INSTALLATION OF SEWER LATERALS SHALL BE RESTORED TO A CONDITION THAT IS AS GOOD IN THE OPINION OF THE ENGINEER, AS WHEN THE CONTRACTOR BEGAN CONSTRUCTION, WHICH MAY INCLUDE THE INSTALLATION OF TOPSOIL, GRASS SEED, AC PAVEMENT, OR OTHER MATERIALS.

SECTION

1.) THE REQUIREMENTS FOR FILL SLOPES AS DELINEATED AND NOTED ON THIS DRAWING ARE INTENDED FOR MINIMUM SLOPE STANDARD CONSTRUCTION. ENGINEERS ARE ENCOURAGED TO CONSIDER HILLSIDE CONSTRUCTION OR DESIGN WHICH WHILD BLEND WITH ENSTRING NATURAL CONDITIONS, INCLUDING INNOVATIVE FEATURES AND FLATTER SLOPES THAN ARE REQUIRED BY MINIMUM SLOPE STANDARDS.

- ALL FILL SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE APPLICABLE PROVISIONS OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS.
- 3.) HORIZONTAL KEYS SHALL BE CONSTRUCTED INTO STABLE GROUND, AT A MINIMUM OF 10 FEET WIDE FOR THE FIRST KEY AND 4 FEET MIDE THEREAFTER. HORIZONTAL KEYS ARE NOT REQUIRED IF THE ORIGINAL GROUND SLOPE IS THATIET THAN 5:1.
- 4.) CONTINUOUS (NOT CONTAINING A ROAD OR MAJOR STRUCTURE) FILL SLOPES STEEPER THAN 8:1 SHALL NOT EXCEED 60 FEET IN VERTICAL HEIGHT FROM TOP TO TOE OF SLOPE UNLESS SPECIAL PERMISSION IS GRANTED BY THE COUNTY ENGINEER, PERMISSION SHALL BE CONTINGENT UPON SUBMISSION ON AN ACCEPTABLE SOILS REPORT AND, WHERE DEEMED NECESSARY, A SUPPLEMENTAL GEOLOGICAL REPORT.
- 5.) THE MINIMUM DISTANCE "X" BETWEEN THE TOE OF FILL SLOPE AND OWNERSHIP BOUNDARY SHALL BE ONE FOURTH THE VERTICAL HEIGHT OR 5 FEET, WHICHEVER IS LESS, UNLESS A LETTER OF PERMISSION FROM THE ADJACENT PROPERTY OWNER IS ON FILE WITH THE COUNTY.
- 6.) DRAINAGE DITCHES ARE REQUIRED AT THE TOP OF FILL SLOPES WHERE: A) SURFACE DRAINAGE IS TOWARD THE FILL SLOPE; B) 50 SQUARE FEET DRAINAGE AREA WILL BE INTERCEPTED BY ONE LINEAL FOOT

OF DITCH; AND C) THERE IS A CONCENTRATION OF 1,000 SQUARE FEET OR MORE OF AREA TO BE DRAINED. BROW DITCHES SHALL NOT EXCEED 400 FEET IN LENGTH WITHOUT A DOWNDRAIN BETWEEN THE TOP AND THE TOE OF THE SLOPE EXCEPT AS OTHERWISE APPROVED BY THE COUNTY ENGINEER.


7.) DURING CONSTRUCTION, TEMPORARY CHAIN LINK FENCES OR EQUIVALENT BARRIERS SHALL BE PROVIDED ADJACENT TO THE TOE OF FILL SLOPES WHICH ARE ADJACENT TO DEVELOPED PROPERTY OR PUBLIC RIGHT-OF-WAY WHEN RECURNED BY THE COUNTY ENGINEER.

B.) ALL FILL SLOPES IN EXCESS OF 5 FEET IN VERTICAL HEIGHT AT A GRADIENT STEEPER THAN 6 HORZONTAL TO I VERTICAL SHALL BE PLANTED IN ACCORDANCE WITH COUNTY SPECIFICATIONS, AND PLANT MATERIALS USED SHALL BE APPROVED BY THE COUNTY ENGINEER.

9.) A SOIL STABILIZER OR OTHER IMMEDIATE PROTECTION SATISFACTORY TO THE COUNTY ENGINEER SHALL BE USED ON ALL FILL SLOPES ADJACENT TO DEVELOPED PROPERTY OR PUBLIC RIGHT-OF-WAY.

10.) ALL SLOPES IN EXCESS OF 10 FEET IN VERTICAL HEIGHT SHALL BE ROUNDED ALONG THE INTERSECTION OF THE FACE OF THE SLOPE AND THE TOP OF THE FILL. THIS ROUNDING SHALL BE UNIFORM ALONG THE ENTIRE INTERSECTION OF THE SLOPE. THE AMOUNT OF ROUNDING SHALL BE χ_0 THE MAXIMUM HEIGHT OF THE SLOPE.

FILL SLOPE DETAIL



1.) THE REQUIREMENTS FOR CUT SLOPES AS DELINEATED AND NOTED ON THIS DRAWING ARE INTENDED FOR MINIMUM SLOPE STANDARD CONSTRUCTION. ENGINEERS ARE ENCOURAGED TO CONSIDER HILLSIDE CONSTRUCTION ON DESCION WHICH WILL BLEND WITH EXISTING NATURAL CONDITIONS, NICLULINIOS INNOVATIVE FEATURES AND FLATTER SLOPES THAM ARE REQUIRED BY MINIMUM SLOPE STANDARDS.

- 3.) CONTINUOUS (NOT CONTAINING A ROAD OR MAJOR STRUCTURE) CUT SLOPES STEEPER THAN 6:1 SHALL NOT EXCEED 60 FEET IN VERTICAL HEIGHT FROM TOP TO TOE OF SLOPE UNLESS SPECIAL PERMISSION IS GRANTED BY THE COUNTY ENGINEER. PERMISSION SHALL BE CONTINGENT UPON SUBMISSION ON AN ACCEPTABLE SOILS REPORT AND, WHERE DEEMED NECESSARY, A SUPPLEMENTAL GEOLOGICAL REPORT.
- 4.) THE MINIMUM DISTANCE "X" BETWEEN THE TOP OF CUT SLOPE AND OWNERSHIP BOUNDARY SHALL BE OTHER TENTH THE VERTICAL HEIGHT OR 5 FEET, WHICHEVER IS LESS, UNLESS A LETTER OF PERMISSION FROM THE ADJACENT PROPERTY OWNER IS ON PILE WITH THE COUNTY.
- 5.) DRAINAGE/BROW DITCHES ARE REQUIRED AT THE TOP OF CUT SLOPES WHERE: A) SURFACE DRAINAGE IS TOWARD THE CUT SLOPE; B) 100 SQUARE FEET DRAINAGE AREA WILL BE INTERCEPTED BY ONE LINEAL FOOT OF DITCH; AND C) THERE IS A CONCENTRATION OF 1,500 SQUARE FEET OR MORE OF AREA TO BE DRAINED.
- 6.) WHEN BROW DITCHES ARE USED: A. THEY SHALL BE CONSTRUCTED PRIOR TO ANY ADJACENT SLOPE EXCAVATION WORK. B. A SUITABLE OUTLET STRUCTURE SHALL BE PROVIDED.
- C. THEY SHALL BE LINED WITH 3" 480-C-2000 OR 3" 2500 PSI AIR PLACED CONCRETE WITH 1/2X1/2 17 GAGE STUCCO NETTING.

D. THEY SHALL NOT EXCEED 400 FEET IN LENGTH WITHOUT A DOWNDRAIN BETWEEN THE TOP AND THE TOE OF THE SLOPE EXCEPT AS OTHERWISE APPROVED BY THE COUNTY ENGINEER.

7.) DURING CONSTRUCTION, TEMPORARY CHAIN LINK FENCES OR EQUIVALENT BARRIERS SHALL BE PROVIDED ADJACENT TO THE TOE OF OUT SLOPES WHICH ARE ADJACENT TO DEVELOPED PROPERTY OR PUBLIC RIGHT-OF-WAY WHEN REQUIRED BY THE COUNTY ENGINEER.

8.) ALL CUT SLOPES IN EXCESS OF 5 FEET IN VERTICAL HEIGHT AT A GRADIENT STEEPER THAN 6 HORIZONTAL TO 1 VERTICAL SHALL BE APPROVED BY THE COUNTY ENGINEER AND/OR PROJECT GEOLOGIST DESCRIPTIONS AT THE COUNTY ENGINEER AND/OR PROJECT GEOLOGIST DESCRIPTION AND A COUNTY ENGINEER AN

9.) A SOIL STABILIZER OR OTHER IMMEDIATE PROTECTION SATISFACTORY TO THE COUNTY ENGINEER SHALL BE USED ON ALL CUT SLOPES ADJACENT TO DEVELOPED PROPERTY OR PUBLIC RIGHT—OF—WAY, AND ALL PLANT MATERIALS USED SHALL BE APPROVED BY THE COUNTY ENGINEER.

10.) ALL SLOPES IN EXCESS OF 10 FEET IN VERTICAL HEIGHT SHALL BE ROUNDED ALONG THE INTERSECTION OF THE FACE OF THE SLOPE AND THE NATURAL GROUND. THIS ROUNDING SHALL BE UNIFORM ALONG THE ENTIRE INTERSECTION OF THE SLOPE. THE AMOUNT OF ROUNDING SHALL BE χ_0 THE MAXIMUM HEIGHT OF THE CUT SLOPE.

CUT SLOPE DETAIL


(530) (530) (4,4,4) Fax Fax enter Yuba


APPROVED 2020


DETAILS

Ø

SANITARY SEWER LATERAL DETAIL










- 1.) ALL WATER SERVICE MATERIALS SHALL BE AS LISTED ON THE MATERIALS LIST (OR APPROVED EQUAL).
- 2.) FACTORY MANUFACTURED FITTINGS SHALL BE USED EXCLUSIVELY.
- 3.) #10 COPPER TRACER WIRE WITH BLUE INSTALLATION SHALL BE TAPED TO ALL WATER MAINS, SERVICES, AND FITTINGS. TRACER WIRE SHALL BE SECURELY CONNECTED TO THE WATER MAIN TRACER WIRE AT ONE END, AEND SHALL TERMINATE IN A LOOP JUST BELOW THE LID IN THE METER BOX AT THE OTHER END.
- 4.) ALL WATER SERVICE SADDLES SHALL HAVE ALL EXPOSED NUTS AND BOLTS COMPLETELY COVERED WITH SPRAY-ON RUBBERIZED UNDERCOATING.
- 5.) CONNECTIONS BETWEEN FITTINGS AND WATER SERVICE PIPING SHALL BE MADE WITH PACK JOINTS, AND STAINLESS STEEL INSERT STIFFEMERS SHALL BE USED AS NEEDED WHEN CONNECTING WATER SERVICE PIPING TO PACK JOINTS.

WATER SERVICE INSTALLATION 3/4" & 1"







- 1.) ALL RESTRAINED JOINT GLANDS SHALL CONFORM TO RESTRAINED JOINT PIPE INSTALLATION DETAILS.
- 2.) THE CONTRACTOR SHALL PLACE AND SECURE A YELLOW BAG OVER THE HYDRANT IMMEDIATELY UPON EITHER INSTALLATION OR REMOVAL FROM SERVICE. THIS BAG SHALL BE REMOVED AND REPLACED WITH A BLUE BAG ONCE THE HYDRANT IS READY FOR USE. THE CITY SHALL SUPPLY ALL BAGS FOR THE CONTRACTOR'S USE.
- 4.) THE HYDRANT BURY SHALL BE SHIMMED IN SUCH A WAY THAT THE WEEKEND BREAKAWAY JOINT ON THE BREAKAWAY ASSEMBLY IS 1.5" ABOVE THE SUFFACE OF THE RECONSTRUCTED SIDEWALK. IN ADDITION, BREAK-OFF BOLTS SHALL BE USED ON THE BOTTOM FLANGE OF THE BREAKAWAY ASSEMBLY ASSEMBLY ASSEMBLY IS NOTED.
- 5.) WHERE NO SIDEWALKS EXIST,A 4" THICK. 4' x 4' CONCRETE PAD SHALL BE INSTALLED.
- 6.) BLUE REFLECTIVE PAYEMENT MARKERS SHALL BE PLACED ONE FOOT INSIDE THE STREET CENTERLINE OF THE FACING STREET. IF HYDRANT LIES WITHIN 20' FET OF THE CORNER, AN ADDITIONAL MARKER SHALL BE PLACED IN THE STREET PERPENDICULAR TO THE HYDRANT ONE FOOT INSIDE THAT STREET CENTERLINE.
- 7.) HYDRANT SHALL BE CLOW MODEL 75 OR 78, AS DETERMINED BY TE ENGINEER.

Fox Fox Ш

œ


99

12-201

APPROVED


2020 Humbuldt County Build pay Olivision

FIRE HYDRAINT INSTALLATION



H > 6', no splices are allowed within H/4


above the top of footing.





Case II 1/2:1 Limited slope (5'-0" Max height)

+ 240 psf surcharge

Case II 1/2:1 Unlimited slope







Ш

Gutter Elev or toe of slope intersection 78 / 78 / 18 · FG/ Backfill sufficiently
to prevent ponding.
To be done after
removal of wall
forms and before
backfilling behind Place waterstop as shown when required Place concrete in toe against undisturbed material, except as permitted by the Engineer. DESIGN

TABLE OF RE	INFORCING	STEEL, DI	MENSIONS	AND DAT	Ά
Design H	4'	ι ε΄	8'	10'	12'
W	4'-0"	5'-0"	6'-6"	8'-0"	9'-6"
F Spread Footing	1'-4"	1'-4"	1'-6"	1′-6"	1'-10"
Batter	None	None	None	100:3	100:6
(a) Bars; # @ in	#5 @ 16	#5 @ .16	#5 @ 16	#5 @ 12	#5 @ 10
Short(a) Bars, # @ in	None	None	#5 @ 16	#5 @ 12	#5 @ 10
(b) Bars, # @ In	#5 @ 16	#5 @ 16	#5 0 8	#5 @ 6	#5 @ 5
Total (e) Bars	8 - #6	8 - #6	10 - #6	8 - #6	6 - #6
Toe Pressure k8f					
Loading Case I	1.7	2.2	2.5	3.0	3.6.
Loading Case II	1.6	2.1	2.7	3.4	4-1
Loading Case II	1.7	2.3	2.9	3.9	4.4
Loading Case IV	2.0	3.2	4.2	5,3	6.5

NOTES:


DESIGN CONDITIONS:

DESIGN H MAY BE EXCEEDED BY 6" BEFORE GOING TO THE NEXT SIZE. SPECIAL FOOTING DESIGN IS REQUIRED WHERE FOUNDATION MATERIAL ES INCAPABLE OF SUPPORTING TOE PRESSURE LOADS LISTED IN TABLE.

DESIGN DATA:

Fo = 1,450 PSI, F'c = 3,600 PSI, Fa = 24,000 PSI, n = 10, EARTH = 120 PCF. CASE II, III, IV - WALL DESIGN IS BASED ON RANKINE'S FORMULA WITH θ = 33'42'.

CALT RANS RETAINING WALL TYPE 5




	PILE SP 90 KIP		
Design	Front Row	Back Row	
H	1:3 Batter	Vertical	- 1
4'	18'-0"	18'-Q"	,
6'	12'-0"	18'-0"	1
8'	9'-0"	18'-0"	
10'	6'-0"	12'-0"	'
12'	4'-0"	8'-0"	

For actual spacing, see Wall Layout. Pile layout does not apply to Case W conditions.

DETAILS RETAINING WALL ω . ö 12-201

G7



CEC


RETAINING WALL DETAILS

знеп G8 оғ 8


JECT NUMB


Office (530) 751-0952 Fox (530) 751-0953 c Center Bivd., Sulte 404 Yuba Cliy, CA 95993


APP (CSED)
3020
Humbokit County
Building Oldsion



APPICES 2000
Hambolet County
British 10 Oktober









APPROVED


EN 10 2020
Humboldt County
Bodding Division







APPROVED


TO 2020
Hombeddt County




AFF 200 Hamchelt County Buddyn Ordston









APPROVED
11:21 O 2020
Reshold County
Buildys Prisson





APPRIVED
UT15 2020
Hundelft Conty
Butch Better




RPPRIVEO 1:000 Hambeet County Build Ordelon










Callonia Engineering APPROPRIED 1920 Hunters Fostly Budgy Incides








EPPROVED
MAR 1 0 2020
Humburd County
Buildy Colvision











CHC

VANCE AVENUE CROSS SECTIONS

9 . ö

SHEET S5


PROJECT NUMBI


AFPROVED


LAN 1 0 2020

Humbold County


Built fig Division








Bong Ennyages Homopolis Conuga 5050



APPROVED 1 2020 Humbeldt County Bulbling Disaston



"CHILDREN CROSSING" SIGN, 1,25' FROM SW SEE SHEET M4 MARK "SLOW SCHOOL XING" IN 8" TALL YELLOW LETTERS PER CAL TRANS STD PLAN A24D VANCE AVENUE "CHILDREN CROSSING" _ SIGN, 1.25' FROM SW MARK "SLOW SCHOOL XING" IN 8" TALL YELLOW LETTERS PER CAL TRANS STD PLAN A24D 4" YELLOW CENTERLINE PER CALTRANS DETAIL 1 PAGE A 20A OF STANDARD PLANS, TYP R470.00' --/

> C C C C VANCE AVENUE SIGN AND STRIPING
> STA: 60+50 TO 65+00
> VANCE AVE AND PHASE 1A IMPROVEMENT PLANS

> > SHEET M5 OF

12-201

Office (530) 751-0952 Fax (530) 751-0953 ic Center Bivd., Suite 404 Yuba City, CA 95993

ACETICATED

1 120
Homboth County
Building Cartain


1+00 12" WHITE CROSS-WALK STRIPING, TYP 12" WHITE CROSS-WALK STRIPING, TYP ,8.00 VANCE AVENUE 8.00' STOP SIGN/STREET SIGN
"VANCE AVENUE" AND
"HAMMOND STREET" PER
CALTRANS TRAFFIC
MANUALT 2:5" FROM EP "STOP" IN 8' TALL WHITE LETTERS PER CALTRANS STD PLAN A24D STOP SIGN/STREET SIGN
"VANCE AVENUE" AND
"HAMMOND STREET" PER
CALTRANS TRAFFIC
MANUAL 2.5" FROM EP "STOP" IN 8" TAL WHITE LETTERS PER CAL TRANS STD PLAN A24D R100.00' -PC . Office (530) 751-0952 Fox (530) 751-0953 Center BIvd., Sulte 404 Yuba City, CA 95993 YIELD SIGN 1.25' FROM EP PER CALTRANS HIGHWAY MANUAL HAMMOND STREET END STRIPING
AT CURB RETURN,
TYP YIELD SIGN 1,25' FROM EP PER CALTRANS HIGHWAY MANUAL END STRIPING

AT CURB RETURN,
TYP APPROXIB Handon Court Bally Villence Ш Ü 4" YELLOW CENTERLINE PER CALTRANS DETAIL 1 PAGE A 20A OF STANDAR PLANS, TYP HAMMOND & MURRAY SIGN & STRIPE VANCE AVE AND PHASE 1A IMPROVEMENT PLANS -4 PROJECT NUMB ö знеет **М6** с


7 60 7


12

n a L




APPROVED






17.57



184

4) /s



ABBREVIATIONS: IOINT TRENCH AGGREGATE BASE LIP OF GUTTER APPROX. -APPROXIMATELY AVENUE MANHOLE BLOW OFF VALVE BUILDING CURB AND GUTTER MONUMENT MARKER ORIGINAL GROUND CL C.O.T.G. CLEAN OUT TO GRADE POINT OF CURVATURE PROPERTY LINE POWER POLE POINT OF TANGENCY CR CULV. CURS RETURN CULVERT DRAIN INLET PUBLIC UTILITY ESMT. R/W RIGHT-OF-WAY ELEVATION

SCHEDULE STORM SEWER SHEET SANITARY SEWER EDGE OF PAVEMENT EASEMENT EX. EXP. FXISTING FLARED END SECTION FIRE DEPT. CONNECTION FIRE HYDRANT STATION STD. S/W STANDARD SIDEWALK SEWER FORCE MAIN

TOP BACK OF CURB TOP BACK OF WALK TOE OF SLOPE TOP OF SLOPE FND. GRADE BREAK TELEPHONE POLE VERT. VERTICAL INTERSECTION WATER WATER METER BOX WATER VALVE

IOINT POLE

GAS VALVE

EXISTING GRADE

GAS LINE

IRON PIPE

LEGEND DESCRIPTION (E) EXISTING (P)PROPOSED STORM DRAIN SANITARY SEWER WATER MAIN MANHOLE DRAIN INLET SANITARY CLEAN-OUT WATER SERVICE GATE VALVE HYDRANT BLOW OFF VALVE STREET LIGHT TRANSFORMER PULL BOX & PEDISTA ELECTRIC VAULT POWER POLE (B) GUY WIRE OVER-HEAD LINES -- OH ---- он -CURB. GUITER & WALK _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ RIGHT OF WAY PUBLIC UTILITY EASEMENT CENTER LINE BOUNDARY LINE FENCE -IT-JOINT TRENCH WATER WELL

UTILITY REPRESENTATIVES

--- GAS ---

857.56

CEC GENERAL NOTES

MINIMUM OF TWO WORKING DAYS TO ADDRESS THE ISSUE

BASIS OF BEARINGS:

1.) ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THESE PLANS AND SPECIFICATIONS, AND TO THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS, LATEST EDITION. THE CONTRACTOR SHALL OBTAIN A COPY OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS PRIOR TO CONSTRUCTION, IN THE ABSENCE OF A SPECIFICATION FOR AN ITEM IN THESE PLANS AND THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS HELD HAVE SET OF A SPECIFICATION FOR AN ITEM IN THESE PLANS AND THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS HELD HAVE SET OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS HELD HAVE SET OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS HELD HAVE SET OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS HELD HAVE SET OF THE STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS HELD HAVE SET OF THE STATE OF THE STANDARD PLANS HELD HAVE SET OF THE STANDARD PLANS HELD PLANS HELD HAVE SET OF THE STANDARD PLANS HE STANDARD PLANS HELD HAVE SET OF THE STANDARD PLANS HELD HAVE SE

APPLICABLE FEDERAL AND STATE LAWS ARE TO BE ADHERED TO AND MEET CURRENT ENGINEERING

2.) THE TYPES, LOCATIONS, SIZES, AND DEPTHS OF EXISTING UTILITIES WERE OBTAINED FROM SOURCES OF VARYING RELIABILITY. THE CONTRACTOR IS CAUTIONED THAT ONLY ACTUAL EXCAVATIONS WILL REVEAL SUCH INFORMATION, A REASONABLE EFFORT WAS MADE TO DELINEATE UTILITIES, HOWEVER, CALIFORNIA ENGINEERING COMPANY, INC. ASSUMES NO RESPONSIBILITY FOR THE COURT LETERS.

FOR OTHER UTILITIES THAT MAY BE ENCOUNTERED. THE CONTRACTOR IS HEREBY NOTHER ON THAT HE IS RESPONSIBLE FOR VERIFICATION OF THE LOCATION OF ALL UTILITIES AT THE CONSTRUCTION SITE. IN THE EVENT THAT SUBSTANTIAL DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE ENGINEER FOR DIRECTION.

COMPLETENESS AND ACCURACY OF THE LOCATION OF THE EXISTING LITHLITIES ON THE PLANS NO

3.) IN THE EVENT THERE IS A DISCREPANCY OR TYPOGRAPHICAL ERROR WITHIN THESE PLANS, OR

4.) ONLY SIGNED PLANS BY ALL PARTIES INVOLVED SHALL BE CONSIDERED APPROVED. THE CONTRACTOR SHALL NOT BEGIN WORK BEFORE THE PLANS HAVE BEEN APPROVED. THE CONTRACTOR SHALL HAVE ALL PERMITS AND APPROVED PLANS ON-SITE AT ALL TIMES DURING CONSTRUCTION.

THE BASIS OF BEARINGS OF THESE IMPROVEMENT PLANS IS A TIE FROM THE

SOUTHWEST CORNER OF SECTION 16, T.SN.R.I.W., HUMBOLDT MERIDIAN TO A 1/2*
IRON PIPE WITH PLASTIC PLUG IS 4829 ON THE SOUTH LINE OF SECTION 16. THE TIE
BEING SOUTH 89324/6* EAST, 1082.55 PEET AS SHOWN IN BOOK 60 OF SURVEYS,
PAGES 122-124, HUMBOLDT COUNTY RECORDS

REQUEST FOR INFORMATION, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY FOR DIRECTION. THE CONTRACTOR IS HEREBY NOTIFIED THAT THE ENGINEER SHALL BE ALLOWED A

OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS, ALL

AND CONSTRUCTION STANDARD PRACTICES TO THE SATISFACTION OF THE COUNTY ENGINEER.

UTILITY	COMPANY	CONTACT	PHONE
SEWER	SAMOA PACIFIC GROUP LLC	CHUCK BARNHART	(707) 922-9000
DRAINAGE	SAMOA PACIFIC GROUP LLC	CHUCK BARNHART	(707) 922-9000
WATER	\$AMOA PACIFIC GROUP LLC	CHUCK BARNHART	(707) 922-9000
IRRIG. WATER	SAMOA PACIFIC GROUP LLC	CHUCK BARNHART	(707) 922-900
FIRE	SAMOA PENINSULA FIRE DISTRICT	DALE UNEA	(707) 443-9042
CA8LE TV	COMCAST	STAFF	
ELECTRICAL.	PACIFIC GAS & ELECTRIC (PG&E)	STAFF	(800) 743-500
GAS	PACIFIC GAS & ELECTRIC (PG&E)	STAFF	(800) 743-500
PHONE	AT&T	STAFF	(707) 445-4069
USA	UNDERGROUND SERVICE ALERT	STAFF	(800) 227-2600

TOWN OF SAMOA


PHASE 1: WATER AND SEWER IMPROVEMENT PLANS- EXISTING TOWN

FOR USE IN CONJUNCTION WITH IMPROVEMENT PLANS FOR: VANCE AVENUE, SAMOA AFFORDABLE HOUSING, WATER STORAGE SYSTEM, AND WWTP REHABILITATION PROJECTS

TOWN OF SAMOA, HUMBOLDT COUNTY, CALIFORNIA

SUBMITTAL NO. 1

MAY 2021



/ICINITY MAP NOT TO SCALE

SHEET INDEX:

- COVER SHEET
 GENERAL NOTES
 CIVIL SHEET INDEX
 STANDARD DETAILS- SEWER
- STANDARD DETAILS- WATER STREET SECTIONS
- STREET SECTIONS
- RIDEOUT STREET STA: 1+00 TO 6+00

- RIDEOUT STREET STA: 1+00 TO 6+00

 RIDEOUT/SUNET STREET STA: 6+00 TO 11+50

 SUNSET AVE STA: 11+50 TO 15+25

 WATERLINE SOUTH OF NEW NAYY BASE ROAD

 SUNSET EXTN STA: 1+00 TO 6+50

 SUNSET EXTN STA: 1+00 TO 10+25

 SUNSET EXTN STA: 6+50 TO 10+25

 SUNSET AVE DRIVEWAY STA: 1+00 TO 5+50

 BAY YIEW AVE STA: 1+00 TO 6+50

 BAY YIEW AVE STA: 1+00 TO 6+50

 BAY YIEW AVE STA: 1+00 TO 14+50
- C9 BAY VIEW AVE STA: 6+50 TO 12+00 C10 BAY VIEW AVE STA: 12+00 TO 16+50
- C10 BAY YIEW AVE \$1A: 12+00 TO 14+50
 C11 FENWICK AVE \$1A: 16+50 TO 21+00
 C12 CADMAN COURT \$1A: 1+00 TO 64+50
 CUITEN \$1REET \$1A: 1+50 TO 34+50
 PARKING ALLEY \$1A: 1+00 TO 34+50
 ARKING ALLEY \$1A: 1+00 TO 34+50
 ARKING ALLEY \$1A: 1+00 TO 34-50
 ARKING ALLEY \$1A: 1+00 TO 34-50
- MURPHY AVE STA: 1+00 TO 2+50 C15 MURPHY AVE STA: 2+50 TO 5+50
- SAMOA COURT STA: 1+00 TO 3+50
- SAMOA COURT STA: 1+00 TO 3+50
 C16 SAMOA COURT STA: 3+50 TO 9+00
 C17 SAMOA COURT STA: 3+50 TO 9+00
 BAY YIEW SPUR STA: 1+00 TO 1+00
 BAY YIEW SPUR STA: 1+00 TO 3+50
 C18 SEWER MAIN SOUTH OF ŘÁIROAD STA: 1+50 TÖ 7+00
 C19 SEWER MAIN SOUTH OF RAILROAD STA: 7+00 TO 12+00

SOMOA CSD

COUNTY OF HUMBOLDT

CALIFORNIA ENGINEERING COMPANY, INC.

ROBERT W. BRONKALL, P.E.

OFFICER IN CHARGE P.E. EXP. 12/31/20 - P.L.S. EXP. 06/30/20 06/09/2021

06-09-2021

Ö CALIFORNIA ENGINEERING

SHEE

24 Ö G G

AND FEDERAL APPROVALS AND PERMITS ASSOCIATED WITH WORK SHOWN IN THESE PLANS, AND ASSUMES ALL LIABILITY ASSOCIATED THEREWITH,

12.) CONTRACTOR TO FIELD VERIFY ALL EXISTING ELEVATION AND INVERTS ON ALL EXISTING UTILITIES PRIOR TO INSTALL ANY PIPE.

5.) THE CONTRACTOR SHALL CONTACT UNDERGROUND SERVICE ALERT BEFORE DIGGING (800-227-2800) AT LEAST 72 HOURS BEFORE BEGINNING WORK.

7.) THE CONTRACTOR SHALL CONTACT THE COUNTY OF HUMBOLDT PUBLIC WORKS DEPARTMENT AT LEAST 48 HOURS IN ADVANCE/PRIOR TO COMMENCEMENT OF WORK.

8,) ADJACENT STREET FRONTAGES SHALL BE SWEPT AT LEAST ONCE A DAY TO REMOVE SILT AND

9.1 ALL TESTING IS THE RESPONSIBILITY OF THE CONTRACTOR AND ALL REQUIRED TESTS SHALL BE

COORDINATED AND APPROVED BY THE PROJECT ENGINEER AND COUNTY OF HUMBOLDT

10.) ADDITIONAL NOTES AND DETAILS ARE LOCATED ON THE FOLLOWING SHEETS.

6.) IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WORK WITH ALL

SUBCONTRACTORS, UTILITY COMPANIES, AND THE COUNTY OF HUMBOLDT

OTHER DIRT WHICH IS EVIDENT FROM CONSTRUCTION ACTIVITIES

THE ELEVATION DATUM OF THIS PROJECT IS BASED ON USCAGS BENCHMARK Y1091, ELEVATION 36.75 FEET. THE BENCHMARK IS A BRASS CAP IN CONCRETE AT THE NORTHEAST CORNER OF A PGAE TRANSMISSION TOWER, WEST OF THE FORMER LOUSSIANA-PACIFIC PULP MILL AND WEST OF VANCE AVENUE.

VERTICAL DATUM:

CEC GENERAL NOTES

1.) THE CONSTRUCTION CONTRACTOR SHALL AGREE, THAT IN ACCORDANCE WITH GENERALLY ACCEPTED RUCTION PRACTICES. THE CONSTRUCTION CONTRACTOR WILL BE REQUIRED TO ASSUME SQLE AND COMPLETE RESPONSIBILITY FOR THE JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND TO THE LIMITED TO NORMAL WORKING HOURS AND THE CONSTRUCTION
CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD CONSULTING SINGHER, SAMP ACKING
RORUP, AND THE COUNTY OF HUMBOLD! THANKLESS FROM MAY AND ALL LIMIBITY, REAL OR ALLEGED, IN
CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT. EXCEPTING LIBILITY ARISING FROM THE
SOLE NEGLIGENCE OF THE CONSULTING DESIGN PROFESSIONAL, SAMOA PAGICIEG GROUP, OR THE COUNTY OF

2.) ALL CONSTRUCTION MATERIALS, METHODS AND WORKMANSHIP SHALL CONFORM TO THE COUNTY OF 2.) ALL CONSTRUCTION MATERIALS, METHODS AND WORKMANSHIP SHALL CONFORM TO THE COUNTY OF HUMBOLDT PUBLIC WORKS IMPROVEMENT STANDARDS, ADOPTED LATES EDITION OF STATE OF CALLFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS AND SPECIFICATIONS, AND CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS (RANK SHALL BE IN ABOVE LISTED ORDER WHERE BISOREPANCIES EXST), ALL WORK IS SUBJECT TO THE APPROVAL OF COUNTY BEGINEER OR HIS AUTHORIZED REPRESENTATIVE. CERTIFICATION FOR CONFORMANCE WITH COUNTY SPECIFICATIONS WILL BE REQUIRED FOR ALL MATERIALS USED ON THE PROJECT UNLESS SPECIFICALLY WAIVED BY THE COUNTY ENGINEER.

3.) THE CONTRACTOR SHALL NOTIFY THE COUNTY ENGINEER 72-HOURS PRIOR TO COMMENCING WORK AND

4.) THE CONTRACTOR SHALL OBTAIN ALL NECESSARY ENCROACHMENT PERMITS FOR THE PROJECT, AND BE IN RECEIPT OF SUCH PERMITS AND APPROVED PLANS PRIOR TO THE BEGINNING OF CONSTRUCTION.

5.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLIANCE WITH ALL CURRENTLY APPLICABLE SAFETY LAWS OF ANY JURISDICTIONAL BODIES. FOR MORE INFORMATION, PLEASE CONTACT THE STATE INDUSTRIAL SAFETY DEPARTMENT (916-455-5818).

6.) THE CONTRACTOR SHALL BE HELD RESPONSIBLE TO SEE THAT ALL SUBCONTRACTORS AND SUPPLIERS HAVE CURRENT COUNTY BUSINESS LICENSES. THE WORK WILL NOT BE ACCEPTED FOR COMPLETION UNTIL SUBMITTAL OF A COMPLETE LIST WITH LICENSE NUMBERS TO THE COUNTY FENSIMER.

7.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTENANCE OF EXISTING PUBLIC AND PRIVATE IMPROVEMENTS WITHIN AND ADJACENT TO THE WORK AND SHALL ADEQUATELY BARRICADE PROJECT TO KEEP THE GENERAL PUBLIC FROM THE SITE. ANY DAMAGE TO CITY OR PRIVATE IMPROVEMENTS SHALL BE REPLACED OR REPAIRED BY THE CONTRACTOR AT HIS EXPENSE TO CURRENT STATE OF CALIFORNIA DEPARTMENT OF TRANSPORTATION STANDARD PLANS,

8.) THE CONTRACTOR IS TO EXPOSE THE ENDS OF WATER MAINS, SEWER AND DRAIN LINES AND EXISTING GRAVITY LINES FOR THE SURVEYOR TO VERIFY LOCATION AND DEPTH OF FACILITIES PRIOR TO PLACEMENT OF PIPE.

9.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPORTING ALL CONFLICTS, ERRORS, OMISSIONS, ETC. TO THE CONSULTING ENGINEER IMMEDIATELY UPON DISCOVERY. IF SO DIRECTED BY THE ENGINEER OR COUNTY ENGINEER, THE CONTRACTOR SHALL STOP WORK LINTIL MITIGATIONS CAN BE MADE. ANY COSTS INCURRED RESULTING FROM THE CONTRACTOR'S FAILURE TO STOP WORK AS DIRECTED SHALL BE THE RESPONSIBILITY

10,) THE CONTRACTOR SHALL AT ALL TIMES COORDINATE HIS WORK WITH THAT OF OTHERS ON THE SITE. THE CONTRACTOR SHALL HAVE A RESPONSIBLE PARTY, WHO SHALL HAVE THE AUTHORITY TO REPRESENT AND ACT ON HIS BEHALF, ON THE JOB SITE DURING ALL WORKING HOURS,

11.) THE COUNTY OF HUMBOLDT IS A MEMBER OF THE UNDERGROUND SERVICE ALERT (U.S.A.) ONE CALL SYSTEM. THE CONTRACTORS SHALL NOTIFY THE U.S.A. CENTER 72-HOURS IN ADVANCE OF PERFORMING EXCAVATION WORK BY CALLING 1-800-227-2600.

12.) THE CONTRACTOR SHALL MARK IN WHITE PAINT ALL AREAS TO BE EXCAVATED PRIOR TO CONTACTING U.S.A.

13.) CONTRACTOR SHALL SUBMIT TO THE PUBLIC WORKS DEPARTMENT INSPECTOR A COPY OF THE COMPANY ANNUAL CALOSHA TRENCHING PERMIT AND A COPY OF THE COMPANIES LETTER INFORMING CALOSHA OF THE TIME OF TRENCHING PRIOR TO EXCAVATION OF TRENCHES 6' OR DEEPER.

14.) ALL WORK SHALL BE IN ACCORDANCE WITH THE COUNTY'S NOISE ORDINANCE

15.) IF ANY AMOUNT OF BONES, STONE OR ARTIFACTS ARE UNCOVERED, WORK WITHIN 165 FEET OF THE AREA 10, IF ANT AND UP DOVES, AND A CUALIFIED ARCHEOLOGIST SHALL BE CONSULTED TO DEVELOP, (IF, SHALL CEASE IMMEDIATELY AND A CUALIFIED ARCHEOLOGIST SHALL BE CONSULTED TO DEVELOP, (IF, NECESSARY) FURTHER MITIGATION MEASURES TO REDUCE ANY ARCHEOLOGICAL IMPACT TO A LESS THAN SIGNIFICANT EFFECT BEFORE CONSTRUCTION RESIMES IN THE AREA.

16.) CONTRACTOR SHALL PROVIDE THE COUNTY ENGINEER WITH SUBMITTALS FOR ALL MATERIALS TO BE USED, THE SUBMITTALS SHALL BE DELIVERED TO THE DEPARTMENT OF PUBLIC WORKS A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PRE-CONSTRUCTION CONFERENCE.

17.) CERTIFICATION FOR CONFORMANCE WITH THE COUNTY OF HUMBOLDT SPECIFICATIONS WILL BE REQUIRED OF ALL MATERIAL USED ON THE PROJECT UNLESS SPECIFICALLY WAIVED BY THE ENGINEER.

18.) CONTRACTOR SHALL ADEQUATELY BARRICADE PROJECT TO KEEP THE GENERAL PUBLIC FROM THE SITE

19.) ALL APPLICABLE FEES TO BE PAID AND PERMITS REQUIRED SHALL BE OBTAINED BY THE CONTRACTOR BEFORE COMMENCEMENT OF CONSTRUCTION.

20.) A SOILS ENGINEER SHALL BE ENGAGED BY THE OWNER TO CERTIFY THAT THE VARIOUS ITEMS OF COMPACTION COMPLY WITH THE SPECIFICATIONS AND THAT SPECIAL WORK REQUIRED HAS BEEN DONE SATISFACTORILY.

21.) THE CONTRACTOR SHALL USE A WATER TRUCK WHEN REQUIRED TO MAINTAIN ADEQUATE DUST CONTROL

22.) INTERMEDIATE TRENCH BACK FILL SHALL BE IN MAXIMUM LIFTS OF 8" AND SHALL HAVE A MINIMUM RELATIVE COMPACTION OF 90% OR AS DIRECTED BY THE SOILS ENGINEER. COMPACTION SHALL BE BY THE

23.) EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH THE PLANS AND STORM WATER POLLUTION PREVENTION PLAN (SWPPP).

24.) PRIOR TO THE BEGINNING OF EARTHWORK THE CONTRACTOR SHALL CLEAR ALL ROOTS, ORGANIC MATTER, DEBRIS, PAVING, CURB, AND VEGETATION DESIGNATED TO BE SAVED, FROM THE AREA WITHIN WHICH EXCAVATION AND GRADING ARE TO BE CONDUCTED OR STORAGE OF EXCAVATE OMATERIALS OR FILL IS TO BE MADE. VEGETATION CLEARED FROM THESE AREAS SHALL BE DISPOSED OF BY THE CONTRACTOR, AND INCLUDED IN THE COST OF CLEARING AND GRUBBING.

25,) IN TRANSITION AREAS FROM ONE STREET WIDTH TO ANOTHER STREET WIDTH, THE HEAVIER STRUCTURAL

26.) DIMENSIONS SHOWN ON PLANS ARE TO CENTERLINE OF PIPE, UNLESS OTHERWISE NOTED

CEC GENERAL NOTES CONTINUED

28.) SEWER AND WATER AND SERVICES TO HAVE A MINIMUM 10 FEET HORIZONTAL SEPARATION

29.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ALL EXISTING UTILITIES.

30.) CONTRACTOR SHALL POTHOLE ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION TO VERIFY LOCATION AND DEPTH. THE TYPES, LOCATIONS, SIZES AND DEPTH OF EXISTING UTILITIES WERE OBTAINED FROM. SOURCES OF VARYING RELIABILITY, THE CONTRACTOR IS CAUTIONED THAT ONLY EXCAVATIONS WILL REVEAL ACTUAL INFORMATION. A REASONABLE EFFORT WAS MADE TO DELINEATE UTILITIES, HOWEVER, CALIFORNIA ENGINEERING COMPANY ASSUMES NO RESPONSIBILITY FOR THE COMPLETENESS, NOR ACCURACY, NOR FOR OTHER UTILITIES WHICH MAY BE ENCOUNTERED. THE CONTRACTOR IS HERSEY NOTHIFED THAT THEY ARE RESPONSIBLE FOR VERIFICATION OF THE LOCATION OF ALL UTILITIES AT THE CONSTRUCTION SITE. IN THE EVENT CONTRACTOR SHALL MOTHER SHALL PROPERTY OF THE LOCATION OF ALL UTILITIES AT THE CONSTRUCTION SITE. EVENT CONFLICTS EXIST OR SUBSTANTIAL DISCREPANCIES ARE FOUND, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IMMEDIATELY AND ALLOW 2 WORKING DAYS FOR CHANGE TO BE MADE, COORDINATED

GRADING NOTES

1.) A SOILS ENGINEER SHALL CERTIFY THAT THE VARIOUS (TEMS OF COMPACTION AND MATERIALS HAVE BEEN ACCOMPLISHED, GRADING SHALL CONFORM TO CHAPTER 70 UBC, LATEST EDITION, AND TO THE RECOMMENDATION OF THE GEOTECHNICAL ENGINEERING REPORT, AND COUNTY REQUIREMENTS,

2.) ALL COMPACTION TESTING SHALL BE PERFORMED BY A LICENSED GEOTECHNICAL ENGINEER IN ACCORDANCE WITH THE GEOTECHNICAL AND COUNTY SPECIFICATIONS AND BE PAID FOR BY THE DEVELOPER (OR CONTRACTOR IN CASE OF RE-TESTING). THOSE TESTS WITHIN THE INDIFFLORMY SHALL BE APPROVED BY THE COUNTY OF HUMBOLDT AND ALL TESTING OUTSIDE THE RIGHT-OF-WAY CERTIFIED BY THE SOLLS ENGINEER FOR THE FROLECT. THE RESULTS OF SOIL COMPACTION TESTING SHALL BE SUBMITTED TO THE

3.) ALL UNSUITABLE AND SURPLUS MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL

4.) SUFFICIENT EQUIPMENT SHALL BE AVAILABLE TO PROVIDE DUST CONTROL AT ALL TIMES DURING CONSTRUCTION. A WATER TRUCK SHALL BELSED, WHEN REQUIRED, TO MAINTAIN ADEQUATE DUST CONTROL. A
REAS SURROUNDING THE WORK SHALL BE KEPT CLEAN AND RETURNED TO ORIGINAL CONDITION UPON
COMPLETION OF THE CONTROL. THE CONTRACT SHALL BE KEPT CLEAN AND RETURNED TO ORIGINAL CONDITION UPON
COMPLETION OF THE CONTRACT. THE CONTRACTOR SHALL DISTAIN A RISE HYDRAMT WATER METER PRIOR TO

5.) ROUTES TO THE PROJECT SITE FOR HEAVY EQUIPMENT AND MATERIAL SHALL BE APPROVED BY THE

6.) EROSION CONTROL HYDROSEEDING SHALL BE APPLIED TO ALL GRADED OR DISTURBED SOILS WITHIN THE WORK AREA AFTER COMPLETION OF IMPROVEMENTS OR IF PRACTICAL AFTER GRADING ALSO TO REDUCE DUST,

7.) WINTERIZATION NOTE "THE FOLLOWING ARE REQUIRED IF GRADING AND CLEARING IMPROVEMENTS ARE INCOMPLETE BY OCTOBER 15TH; EROSION PROTECTION ON SLOPES 10:1 OR STEEPER AND SWALES WITH SLOPES 28:0 OR GREATER, NO SEDIMENT SHALL LEAVE THE PROJECT AREA. GRADE GUTTER SAG POINTS TO DRAIN, PROVIDE FOR DRAINAGE OF IMPROVEMENTS, PREVENT SEDIMENTATION IN EXISTING STORM DRAIN SYSTEM AND CLEAN PIESE PER SECTION SSO-06 (CALTARNS SPECS), SEAL OFF ALL SANTARY SEWER CONNECTION TO EXISTING SYSTEMS, IT IS THE CONTRACTORS RESPONSIBILITY TO MAINTAIN WINTERIZATION FACILITIES AT ALL TIMES OR UNTIL IMPROVEMENTS ARE FINAL,

8.) ALL EROSION CONTROL SHALL BE PLACED AS SPECIFIED ON THESE PLANS OR AS SHOWN ON THE SWPPP.

9.) TARPAULINS OR OTHER EFFECTIVE COVERS SHALL BE USED ON ALL STOCKPILED EARTH MATERIAL AND ON

10.) THE COUNTY SHALL HAVE THE AUTHORITY TO STOP ALL GRADING OPERATIONS, IF, IN OPINION OF COUNTY STAFF, INADEQUATE DUST CONTROL MEASURES ARE BEING PRACTICED OR EXCESSIVE WIND CONDITIONS CONTRIBUTE TO FUGITIVE DUST EMISSIONS.

11.) ADJACENT STREET FRONTAGES SHALL BE SWEPT AT LEAST ONCE A DAY TO REMOVE SILT AND OTHER DIRT WHICH IS EVIDENT FROM CONSTRUCTION ACTIVITIES.

12.) THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING CONSTRUCTION VEHICLES LEAVING THE SITE ON A DAILY BASIS TO PREVENT DUST, SILT, AND DIRT FROM BEING RELEASED OR TRACKED OFFSITE.

13.) PRIOR TO INITIATING CLEARING AND GRUBBING ALL PROTECTIVE FENCING SHALL BE INSTALLED.

CONSTRUCTION STAKING

1.) THE SURVEYOR FOR THIS PROJECT SHALL PROVIDE ONE (1) SET OF CONSTRUCTION STAKES FOR LINE AND GRADE UNLESS OTHERWISE REQUESTED BY THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING MONUMENTS AND OTHER SURVEY MARKERS DURING CONSTRUCTION. ALL SUCH MONUMENTS OR MARKERS DESTROYED DURING CONSTRUCTION SHALL BE REPLACED AT THE

IN THE EVENT OF A DISAGREEMENT OR DESTROYED STAKE OR MONUMENT, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE SURVEYOR PRIOR TO ANY FURTHER CONSTRUCTION.

3.) THE CONTRACTOR SHALL GIVE THE SURVEYOR 72-HOURS NOTICE PRIOR TO EACH PHASE OF CONSTRUCTION OR IN THE EVENT OF NEEDED RE-STAKING, PRIOR TO RECUESTING ACCEPTANCE OF IMPROVEMENTS, THE SURVEYOR FOR THIS PROJECT SHALL SET SURVEY MONIMEMTS AS SPECIFIED IN THE

4.) THE CONTRACTOR IS RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING MONUMENTS AND OTHER

5.) THE CONTRACTOR SHALL HAVE THE SITE STAKED PRIOR TO CONSTRUCTION OF ANY IMPROVEMENTS TO ENSURE PROPER ALIGNMENTS AND ELEVATIONS,

WATER FACILITIES NOTES

1.) ALL WATER FACILITIES INCLUDING BUT NOT LIMITED TO LINES, SERVICE BOXES, VALVES, AND ALL MISCELLANEOUS APPURTENANCES SHALL CONFORM TO THE CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS, AND HUMBOLD TRAY MUNICIPAL WATER DISTRICT STANDARDS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION, REQUIREMENTS, AND DRAWINGS NECESSARY TO BID AND COMPLETE THE WORK SHOWN ON THESE PLANS AND INFLALED PER MANUFACTURERS SPECIFICATIONS, PIPE ALTERNATIVES SHALL BE: POLYVINYL CHLORIDE PIPE - AWWA - C900 CLASS 150 INCITE LE OWN BUIES. DUCTILE - IRON PIPE - AWWA 151 CLASS 50

2.) FIRE HYDRANTS SHALL BE APPROVED BY THE COUNTY ENGINEER AND SAMOA PENINSULA FIRE DISTRICT.

3.) ALL RUNS OF SEWER FORCE MAIN AND WATER MAIN PIPE SHALL HAVE NO.10 GAUGE, SOLID INSULATED SOFT-DRAWN COPPER WIRE TAPED ALONG THE TOP OF PIPE. THE WIRE SHALL BE STUBBED UP INSIDE EACH VALVE BOX AND DEAD END BLOWOFF ASSEMBLY AND BE INSTALLED AS PER STANDARD DRAWING ASSEMBLY W-5, ALL SPLICES SOLDERED AND SHRINK-WRAPPED OR TAPPED,

4.) AT UTILITY CROSSING MAINTAIN A MINIMUM 12" VERTICAL CLEARANCE BETWEEN WATER LINES AND ALL OTHER FACILITIES, ALL SEWER/MATER CROSSINGS, INCLUDING SERVICES, SHALL CONFORM TO STATE HEALTH DEPARTMENT REQUIREMENTS WITH 10" MINIMUM HORIZONTAL CLEARANCE,

5.) ALL VALVES SHALL BE FLANGED TO TEES AND/OR CROSSES. ALL MAINLINE VALVES 16-INCH AND LARGER SHALL BUTTERFLY VALVES WHERE VALVE NUT IS GREATER THAN 30-INCH BELOW FINISHED GRADE. A VALVE OPERATING STERNISCH SHALL BE REQUIRED.

6.) ALL WATER SERVICES SHALL BE PER CITY OF EUREKA STANDARD DETAILS AND SPECIFICATIONS 7.) WATER METER BOXES AND COVERS SUBJECT TO TRAFFIC SHALL BE REINFORCED CONCRETE.

8.) SERVICE CONNECTION TO EXISTING WATER MAIN(S), OR TO AN EXTENSION OF AN EXISTING WATER MAIN(S), WILL BE MADE BY A QUALLFIED CONTRACTOR. THE CONTRACTOR SHALL NOTIFY COUNTY 72 HOURS IN ADVANCE, SCHEDULE AND PROCEED WITH THE SERVICE CONNECTION WITH MIMMUM INTERFERENCE TO EXISTING WATER AND FIRE SERVICES, AN INSPECTION BY THE COUNTY CONSTRUCTION INSPECTOR OF ALL CONNECTIONS MADE BY THE CONTRACTOR IS REQUIRED PRIOR TO BACKFILLING.

9,) PIPE JOINTS WILL NOT BE ALLOWED WITHIN SIX FEET (6') OF VALVE, FITTING OR HYDRANT,

10.) UNDER NO CIRCUMSTANCES SHALL PIPE OR JOINT DEFLECTION EXCEED MANUFACTURERS RECOMMENDATION, DEFLECTION OF PIPE WILL NOT BE ALLOWED WITHIN TEN FEET (10') OF ANY FITTING OR

11.) STANDARD PIPE LENGTHS (MINIMUM EIGHTEEN (18) TO TWENTY (20) FEET, SHALL BE USED FOR ALL HORIZONTAL AND VERTICAL DEFLECTIONS, PIPE LENGTHS LESS THAN STANDARD LENGTH SHALL BE APPROVED BY THE COUNTY PROMINEER.

12.) IN THE EVENT THAT THIS PROJECT INDICATES THAT WATER MAINS WILL BE CONSTRUCTED WITHOUT THE TION OF AN OVERLAYING PAVEMENT. PLASTICIZED METALLIC LOCATING TAPE SHALL BE PLACED EIGHTEEN INCHES (18") ABOVE ALL SAID WATER MAINS.

13.) WATER SYSTEM CONTRACTOR SHALL COORDINATE WITH THE STREET LIGHTING CONTRACTOR TO AVOID CONFLICTS WITH WATER SERVICES AND STREET LIGHT FOUNDATIONS AND ELECTRICAL PULLBOXES.

14.) CONTRACTOR TO PROVIDE 72-HOUR NOTIFICATION TO THE COUNTY DEPARTMENT OF PUBLIC WORKS AND HISIMOD PRIOR TO DISINEGE TO AN

15.) ALL WATER LINE FITTINGS 11.1 DEGREE OR GREATER, TEES, CROSSES, DEAD ENDS AND REDUCERS/INCREASERS SHALL BE PROVIDED WITH BOTH THRUST BLOCKS AND RESTRAINED JOINT PIPE

SANITARY SEWER NOTES

1.) ALL SANITARY SEWER CONSTRUCTION MATERIALS AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE COUNTY OF HUMBOLDT PUBLIC FACILITIES IMPROVEMENT STANDARDS AND THE MANUFACTURERS

2.) THE CONTRACTOR SHALL EXPOSE THE ENDS OF EXISTING SEWER LINES AND VERIFY, VIA POTHOLING, THE LOCATION AND ELEVATION PRIOR TO THE PLACEMENT OF PIPE. ALL COSTS FOR SUCH EXCAVATION AND BACK FILL SHALL BE INCLUDED IN BID PRICE.

3.) ALL SERVICE SEWERS ENTERING A MANHOLE WILL BE SET NOT LOWER THAN FLOWLINE-TO-CROWN WITH EXISTING PIPE UNLESS OTHERWISE SHOWN.

4.) ALL SEWER MANHOLES NOT IN PAVEO AREAS SHALL HAVE RIMS SET 6" ABOVE EXISTING GROUND, OR GRADES AS NOTED, AND INSTALLED WITH LOCK-DOWN COVERS, PINKERTON A-840 OR EQUAL,

5.)THE CONTRACTOR SHALL MAINTAIN ALL EXISTING SEWER FACILITIES WITHIN THE CONSTRUCTION AREA UNTIL NEW IMPROVEMENTS ARE IN PLACE AND APPROVED.

6.) IN THE EVENT THAT THE EXISTING SEWER MAIN FAILS AT THE PLANNED CONNECTION, CONTRACTOR SHALL REPLACE SEWER MAIN TO A PROPER CONNECTION POINT AT THE ADDITIONAL PRICE AGREED UPON IN THE CONTRACT FOR THIS WORK.

CONIC

Ü RNIA ERINC

CALIFOF ENGINEE


(d)

NOTES

GENERAL

24 G2 ġ

ä



1.) COMPACTION TESTS SHALL BE ORDERED AND PAID FOR BY THE CONTRACTOR IN EACH LAYER, TYPE, OR CLASS OF BACKFILL THAT REQUIRES COMPACTION AND AT AN INTERVAL OF EVERY 50 FEET. COPIES OF FIELD TEST REPORTS SHALL BE SUBMITTED TO THE COUNTY PRIOR TO FINAL PAVING, TESTS SHALL BE PERFORMED BY AN INDEPENDENT GEOTECHNICAL ENGINEERING FIRM ACCEPTABLE TO THE ENGINEER.

2.) THE CONTRACTOR SHALL ADEQUATELY SHORE HIS EXCAVATION TO PREVENT THE TRENCH WALLS FROM SLOUGHING INTO THE TRENCH. NO ADDITIONAL PAYMENT WILL BE MADE TO THE CONTRACTOR FOR EXTRA BACKFILL THAT MAY BE REQUIRED DUE TO SLOUGHING TRENCH WALLS.

3.) BEDDING MATERIAL UNDER COUPLING BELLS SHALL BE HAND EXCAVATED SO THAT THERE IS A MINIMUM CLEARANCE OF 1" UNDER THE BELL.

4.) #10 INSULATED COPPER TRACE WIRE (TAPED IN PLACE) SHALL BE COLOR CODED AS FOLLOWS: WATER MAINS & SERVICES - BLUE INSULATION, SEWER MAINS & LATERALS - GREEN INSULATION, STORM DRAIN MAINS - GREEN INSULATION.

5.) ALL WATER MAIN FITTINGS SHALL HAVE ALL EXPOSED NUTS AND BOLTS COMPLETELY COVERED WITH SFRAY-ON RUBBERIZED UNDERCOATING, AND ALL FITTINGS SHALL BE WRAPPED WITH 6 MIL POLYETHYLENE PLASTIC PRIOR TO TRENCH BACKFILL.

6.) BACKFILL MATERIAL SHALL BE COMPACTED IN 12" LIFTS. TRENCH BACKFILL IN ERODED OVERLAND AREAS SHALL MATCH EXISTING GRADE


7.) COMPLETED SURFACING SHALL BE THOROUGHLY COMPACTED AND SHALL BE FREE OF RUTS, BUMPS, DEPRESSIONS AND IRREGULARITIES. IF EXISTING STREET IS SHOWING CONCRETE, NEW PAVEMENT SHALL BE 6"THICK AND CONSIST OF 9000 PSI, 6-SACK CONCRETE, OWNELED AND EPOXIED INTO EXISTING CONCRETE PAVEMENT, BRUSHED (AND COLORED BLACK) TO MATCH. DOWELS SHALL BE #4 REBAR AT 24" O.C. WITH 6"-12" EMBEDMENT TO EXISTING AND NEW CONCRETE.

8.) FOR NON-TRAFFIC AREAS, THE CONTRACTOR SHALL PLACE AND INCORPORATE STRAW AND SEED INTO THE TOPSOIL TO PREVENT EROSION, THE SEED MIX SHALL BE SUBMITTED TO AND APPROVED BY THE ENGINEER PRIOR TO APPLICATION,

9.) FOR PAVED AREAS, IN ANY LOCATION WHERE REMAINING PAVEMENT WIDTH IS LESS THAN 2" BETWEEN EDGE OF TRENCH AND EDGE OF PAVEMENT, THE CONTRACTOR SHALL REMOVE AND REPLACE PAVEMENT TO EDGE OF ROAD.

10.) TRENCH BACKFILL FOR SERVICE LATERALS AND PIPES 2" AND SMALLER IN DIAMETER MAY CONSIST OF SAND IN THE PIPE ZONE TO 6" ABOVE THE PIPE, FOLLOWED WITH COMPACTED CLASS 2 AGGREGATE BASE AS SHOWN.

TRENCH TYPICAL DETAILS



1.) WHERE (E) PIPES AND FITTINGS ARE PRESENT, THEY SHALL BE SAWCUT ALONG THE SPRINGLINE TO FORM THE FLOW CHANNEL WITHIN THE MANHOLE. MANHOLE BASE SECTIONS SHALL BE FILLED WITH CONCRETE TO A LEVEL EQUAL TO THE SPRINGLINE OF THE EXPOSED PIPES, AND SHALL BE FORMED AT THE SLOPE SHOWN TO DRAIN INTO THE FLOW CHANNEL TOWARD THE OUTLET PIPES.

2.) WHERE (E) PIPES AND FITTINGS ARE NOT PRESENT WITHIN THE MANHOLE, THE FLOW CHANNEL SHALL BE HAND-FORMED AT THE SLOPE SHOWN TO THE ORAN INTO THE FLOW CHANNEL TOWARD THE OUTLET PIPE. MANHOLE BASE SECTIONS SHALL BE FILLED WITH CONCRETE TO THE APPROXIMATE LEVEL OF THE TOP OF THE PIPE.


3.) WATERSTOPS SHALL BE INSTALLED AS SHOWN IN THIS DETAIL.

4.) ALL JOINTS SHALL BE SEALED WITH CLASS B MORTAR ON BOTH THE INNER AND OUTER FACES OF EACH JOINT.

5.) MANHOLES SHALL BE CONSTRUCTED WITH A 0.10' ELEVATION DROP (OR AS SHOWN ON THE PLANS) BETWEEN THE INLET AND OUTLET PIPES, IF POSSIBLE,

8.) PIO COPPER TRACER WIRE WITH GREEN INSULATION SHALL BE INSTALLED AT ALL NEW AND EXISTING MANHOLE LOCATIONS. TRACER WIRE SHALL EITHER GE CONTINUOUS ALONG (N) SANITARY PIPE AND UP TO THE MANHOLE FRAME OR SHALL BE SECURELY CONNECTED TO THE (E) TRACER WIRE WHERE PIPE REPLACEMENT IS NOT PERFORMED, NOTE THAT TRACER WIRE IS NOT REQUIRED ON MANHOLES WHEN THE (E) SEWER MAIN HAS NO TRACER WIRE.

SANITARY SEWER MANHOLE DETAILS



1.) MINIMUM PIPE SLOPES SHALL BE 1% (PER FOOT) UNLESS OTHERWISE APPROVED BY THE ENGINEER.

2.) FACTORY MANUFACTURED FITTINGS SHALL BE USED EXCLUSIVELY,

3.) SEWER SADDLES SHALL ONLY BE USED AFTER APPROVAL BY THE ENGINEER.


ALL FITTINGS AND LATERAL PIPING SHALL BE 4" (MIN) PVC SDR-35 SEWER PIPE


5.) ALL LATERALS SHALL BE INSTALLED WITH A #10 COPPER TRACER WIRE WITH GREEN INSULATION TAPED TO THE SANITARY SEWER PIPE, LATERAL TRACER WIRE SHALL BE SECURELY CONNECTED TO AND ELECTRICALLY CONTINUOUS WITH THE SEWER MAIN TRACER WIRE AT ONE END WITH WATERPROOF CORROSION RESISTANT CONNECTOR, AND SHALL TERMINATE IN A LOOP JUST BELOW THE LID IN THE CLEANOUT BOX AT THE OTHER END.

6.) PVC RISER SHALL NOT END IN A BELL FLANGE OR "CAULDER"-TYPE COUPLING, RISER SHALL TERMINATE AT THE REQUIRED CLEARANCE WITH A LEVEL CUT,

7.) ALL AREAS BEHIND THE SIDEWALK THAT ARE DISTURBED BY THE INSTALLATION OF SEWER LATERALS SHALL BE RESTORED TO A CONDITION THAT IS AS GOOD IN THE OPINION OF THE ENGINEER, AS WHEN THE CONTRACTOR BEGAN CONSTRUCTION, WHICH MAY INCLUDE THE INSTALLATION OF TOPSOIL, GRASS SEED, AC PAVEMENT, OF OTHER MATERIALS.

8.) LATERALS AND CLEANOUTS SHALL BE PLACED AS SHOWN PER PLAN AND SPACED 10' FROM WATER SERVICE,







1.) ALL WATER SERVICE MATERIALS SHALL BE AS LISTED ON THE MATERIALS LIST (OR APPROVED EQUAL)

2.) FACTORY MANUFACTURED FITTINGS SHALL BE USED EXCLUSIVELY,


3.) #10 COPPER TRACER WIRE WITH BLUE INSTALLATION SHALL BE TAPED TO ALL WATER MAINS, SERVICES, AND FITTINGS, TRACER WIRE SHALL BE SECURELY CONNECTED TO THE WATER MAIN TRACER WIRE AT ONE END, AEND SHALL TERMINATE IN A LOOP JUST BELOW THE LID IN THE METER BOX AT THE OTHER END,


4.) ALL WATER SERVICE SADDLES SHALL HAVE ALL EXPOSED NUTS AND BOLTS COMPLETELY COVERED WITH SPRAY-ON RUBBERIZED UNDERCOATING,

6.) CONNECTIONS BETWEEN FITTINGS AND WATER SERVICE PIPING SHALL BE MADE WITH PACK JOINTS, AND STAINLESS STEEL INSERT STIFFENERS SHALL BE USED AS NEEDED WHEN CONNECTING WATER SERVICE PIPING TO PACK JOINTS.

6.) WATER SERVICE SHALL BE PLACED AS SHOWN PER PLAN AND SPACED 10' FORM SEWER SERVICE.


WATER SERVICE INSTALLATION 3/4" & 1"






NOTES:

- TRUNCATED DOME EDGE SHALL BE LOCATED SO THE EDGE NEAREST THE TRANSITION BETWEEN THE MOW STRIP AND STREET IS 6° Min and 8° Max.



6" MOW STRIP DETAIL



1.) ALL RESTRAINED JOINT GLANDS SHALL CONFORM TO RESTRAINED JOINT PIPE INSTALLATION DETAILS.

2.) THE CONTRACTOR SHALL PLACE AND SECURE A YELLOW BAG OVER THE HYDRANT IMMEDIATELY UPON EITHER INSTALLATION OR REMOVAL FROM SERVICE. THIS BAG SHALL BE REMOVED AND REPLACED WITH A BLUE BAG ONCE THE HYDRANT IS READY FOR USE. THE CITY SHALL SUPPLY ALL BAGS FOR THE CONTRACTORS USE.

3.) #10 COPPER TRACER WIRE WITH BLUE INSULATION SHALL BE TAPED TO ALL WATER MANUS, FITTINGS, AND SERVICES, SERVICE TRACER WIRE SHALL BE SECURELY CONNECTED TO THE WATER MAIN TRACER WIRE AT ONE END WITH WATERPROF, CORROSION RESISTANT CONNECTOR, SHALL BE LOOPED JUST BELOW THE LID OF THE TRAFFIC BOX, AND SHALL TERMINATE AT THE BREAKOFF FLANGE.

4.) THE HYDRANT BURY SHALL BE SHIMMED IN SUCH A WAY THAT THE WEEKEND BREAKAWAY JOINT ON THE BREAKAWAY ASSEMBLY IS 1.5° ABOVE THE SURFACE OF THE RECONSTRUCTED SIDEWALK, IN ADDITION, BREAK-OFF BOLTS SHALL BE USED ON THE BOTTOM FLANGE OF THE BREAKAWAY ASSEMBLY AS NOTED.

5.) WHERE NO SIDEWALKS EXISTS, A 4" THICK, 4" x 4" CONCRETE PAD SHALL BE INSTALLED,

6.) BLUE REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED ONE FOOT INSIDE THE STREET CENTERLINE OF THE FACING STREET, IF HYDRANT LIES WITHIN 20'FEET OF THE CORNER, AN ADDITIONAL MARKER SHALL BE PLACED IN THE STREET PERPENDICULAR TO THE HYDRANT ONE FOOT INSIDE THAT STREET CENTERLINE.

7.) HYDRANT SHALL BE CLOW MODEL 75 OR 76, AS DETERMINED BY TE ENGINEER.

FIRE HYDRANT INSTALLATION

o N						
7/18/2019	NONE	MRH	IGG :48	3Y: DLS		_
DATE	SCALE	DRAWN BY:	DESIGNED BY:	CHECKED BY:		
TOPES TON						
			NO		1	3

CALIFORNIA ENGINEERING

(d)

DETAILS-ANDARD

G5

12-201

TRUNCATED DOME PARAMETERS SUCH AS SIZE, SPACING, COLOR, AND CONTRAST SHALL BE PER PROVISION 118-705 OF THE CALIFORNIA BUILDING CODE.

DETECTABLE WARNINGS AT CURB RETURN

